

## PROJECT FEATURE

**PROJECT TITLE** : PROPOSED IMPROVEMENT OF CONTAINER YARD

**LOCATION** : Fort San Pedro, Iloilo

**SCOPE OF WORK** A. IMPROVEMENT OF CONTAINER YARD

1. Demolition of existing asphalt and concrete pavement (2,205 sq.m.); removal and upgrading of existing CHB fence including construction of perimeter steel fence; upgrading of existing lateral drainage and catch basins including fabrication of concrete cover to replace damaged steel gratings
2. Excavation of existing fill, stockpiling of reusable materials and disposal of excess at designated areas (2,523 cu.m)
3. Sub-grade preparation (13,869 sq.m.)
4. Spreading and compaction of selected fill (2,422 cu.m.) gravel base course (2,126 cu.m.), cement treated base course (954 cu.m.), leveling sand cushion (318 cu.m.); extraction of existing interlocking concrete blocks pavement (ICBP; 11,664 sq.m.) and reinstallation of portions extracted (5,852 sq.m.); construction of PCC Pavement (7,513 sq.m.) and shear key (505 sq.m.) including steel reinforcements

**APPROVED BUDGET FOR THE CONTRACT** : P 32,476,250.13

**TOTAL PROJECT COST** : P 34,587,206.38

**PROJECT DURATION** : 240 C.D.