

PROJECT FEATURE

PROJECT TITLE : CONSTRUCTION OF BACK-UP AREA

LOCATION : Port of Lipata, Lipata, Antique

SCOPE OF WORK

A. RECLAMATION (1,943 sq.m.)

1. Construction of containment area including supply and driving of PSC and RC sheet piles (1,190 l.m.), concrete works for retaining wall, coping wall, anchor blocks and slotted RC curb (240 cu.m.), rockworks(1,739 cu.m.), fill materials(6,530 cu.m.) and tie rods (30 sets-32mm ϕ of various length)
2. Installation of interlocking concrete block pavement (ICBP 1,819 sq.m.), including gravel base course(150mm thk., 273 cu.m) and cement treated base course(150mm thk., 273 cu.m)
3. Construction of shear keys (167 sq.m.)
4. Construction of lateral drain (63 l.m.) with hot-dipped galvanized trench grate cover

B. PORT LIGHTING SYSTEM

1. Installation of hot dip galvanized steel tapered lamp post (3 pcs-10 mts ht) with floodlight fixtures (6 units), including construction of RC lamp post foundation (3 units), RC duct bank(4 l.m.) and RC hand hole(2 units.).

APPROVED BUDGET FOR THE CONTRACT : **Php 42,443,909.65**
Sources of Funding : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 45,202,763.78**

PROJECT DURATION : **360 CALENDAR DAYS**



9/