

## PROJECT FEATURE

<b>PROJECT TITLE</b>	:	<b>MATNOG PORT EXPANSION PROJECT</b>
<b>LOCATION</b>	:	<b>Port of Matnog, Sorsogon</b>
<b>SCOPE OF WORK</b>		<b>A. BACK-UP AREA (Area = 4,734 sq.m.)</b> <ol style="list-style-type: none"><li>1. Construction of containment area including rockworks (9,131 cu.m.), fill materials (23,919 cu.m.), concrete works (241 cu.m.),</li><li>2. Installation of interlocking concrete blocks pavement (ICBP 4,297 sq.m.)</li><li>3. Construction of shear keys (296 sq.m.)</li><li>4. Construction of 610mm <math>\phi</math> Reinforced Concrete Pipe culvert (120 l.m.) and catch basin (3 units)</li><li>5. Construction of lined canal (54 l.m.) including hot-dipped galvanized trench grate cover</li></ol> <b>B. R.C. DECK ON PILES (Area = 1,252 sq.m.) AND TWO (2) RORO RAMPS</b> <ol style="list-style-type: none"><li>1. Construction of R.C. deck including supply and driving of 450mm x 450mm PSC piles (9,793 l.m.) and concrete works (847 cu.m.)</li><li>2. Supply and install rubber dock fender (6 sets - V-type, V500mm H x 1,500mm L)</li><li>3. Supply and install mooring bollard (4 sets - 50T, T-head)</li></ol> <b>C. PORT LIGHTING SYSTEM</b> <ol style="list-style-type: none"><li>1. Construction of Port Lighting System including RC handhole, concrete duct bank, floodlight pole foundation including 0.45m x 0.45m x 26m PSC pile, hot-dipped galvanized floodlight steel pole, 12m high (1 unit) and floodlight fixtures, SON-T 400 watt HPS (4 pcs.)</li></ol>
<b>APPROVED BUDGET FOR THE CONTRACT</b>	:	<b>P 190,189,003.80</b>
<b>Sources of Funding</b>	:	<b>PPA Corporate Fund</b>
<b>TOTAL PROJECT COST</b>	:	<b>P 202,551,289.05</b>
<b>PROJECT DURATION</b>	:	<b>450 C.D.</b>

A

✓

F