

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Berth and Manuevering Areas at Port of Zamboanga, Zamboanga del Sur

LOCATION : City of Zamboanga, Zamboanga del Sur

SCOPE OF WORK :

- 1) Rock Breaking of 57,00 cu.m. coral/rock formation using drop hammer
- 2) Blasting of 8,00 cu.m. hard dead coral/rock formation
- 3) Dredging/Removal of 65,000 cu.m. broken rock/coral formation and medium to highly dense seabed comprising clayish soil/sand, pebbles, stones granulized corals/seashells & cobbles

Designed Depth : 11.00 m below MLLW

- 3) Disposal of dredged/excavated soil materials.

Disposal Site : 3.5nm away from the dredging Site at 20.0 m depth

APPROVED BUDGET FOR THE CONTRACT : P 84,480,290.45

TOTAL PROJECT COST : P 87,437,100.62

PROJECT UNIT COST

a) Rock Breaking & Dredging Works	:	P	715.46	per cubic meter
b) Blasting Works	:	P	3760.96	per cubic meter
c) Dredging Works (after blasting works)	:	P	600.96	per cubic meter

PROJECT DURATION : 200 calendar days
(inclusive of Sundays/Holidays)

