

PROJECT FEATURE

PROJECT TITLE	: Proposed Dredging of the Ports of Pio Duran, Castilla, Bulan, Virac, Tabaco and Jose Panganiban
LOCATION	: Bicol Region
MAJOR SCOPE OF WORK	<p>1) Dredging along berths and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:</p> <p>5.00m for the Ports of Pio Duran, Castilla and Bulan 6.50m for Virac Port 11.00m for Tabaco Port 5.50m for Jose Panganiban Port</p> <p>2) Total Volume to be Dredged : 242,000 cu.m. of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials. (20,000 cu.m. for Pio Duran; 50,000 cu.m. for Castilla; 40,000 cu.m. for Bulan; 21,500 cu.m. for Virac; 62,500 cu.m. for Tabaco; 48,000 cu.m. for Jose Panganiban)</p> <p>3) Disposal of dredged soil materials 16.00 kms away from the project site</p>
APPROVED BUDGET FOR THE CONTRACT	: P 125,126,313.35
TOTAL PROJECT COST	: P 129,505,734.32
PROJECT (DREDGING) UNIT COST	: P 486.46 per cubic meter (Dredging Works Only, excluding General Expenses and Re-imbursable Items)
PROJECT DURATION	: 345 calendar days (inclusive of Sundays / Holidays and unworkable condition)

