

PROJECT FEATURE

PROJECT TITLE : PROPOSED RAHABILITATION/IMPROVEMENT OF WHARF

LOCATION : Port of Catbalogan, Catbalogan City, Samar

SCOPE OF WORK A. REHABILITATION/IMPROVEMENT OF WHARF

(Area = 248.02 sq.m.)

1. Demolish and dispose existing stairlanding (279 sq.m.),
2. Construction of rock bulkhead (1,803 cu.m.), fill materials(146 cu.m), reinforced concrete for slotted rc curb, mooring block and stairlanding (73 cu.m. of concrete and 17,395 kg of reinforcing steel bars of various sizes)
3. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 254 sq.m.), including aggregate base course (43 cu.m.).
4. Supply and install of geotextile fabric (201 sq.m.) and mooring cleat (18 sets)

APPROVED BUDGET FOR THE CONTRACT : P 11,138,250.87

Sources of Funding : General Appropriation Act (GAA)

TOTAL PROJECT COST : P 12,500,000.00

PROJECT DURATION : 150 C.D.