

PROJECT FEATURE

PROJECT TITLE	:	PROPOSED VILLABA PORT DEVELOPMENT PROJECT
LOCATION	:	Port of Villaba, Brgy. Silad, Villaba, Leyte
SCOPE OF WORK	A.	CONSTRUCTION OF BACK-UP AREA / REPAIR OF DAMAGED CAUSEWAY (Area = 927.5 sq.m.) <ol style="list-style-type: none">1. Demolish and dispose existing concrete pavement (130 sq.m.), excavation of existing materials (149 cu.m.) and chipping of rc curb (45 l.m.).2. Construction of rock bulkhead (3,295 cu.m.), fill materials(2,425 cu.m), reinforced concrete for slotted rc curb, mooring block and stairlanding (59 cu.m. of concrete and 2,272 kg of reinforcing steel bars of various sizes),3. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 958 sq.m.), including aggregate base course (185 cu.m.).4. Supply and install of geotextile fabric (759 sq.m.) and mooring cleat (4 sets)
APPROVED BUDGET FOR THE CONTRACT	:	P 18,610,233.03
Sources of Funding	:	General Appropriation Act (GAA)
TOTAL PROJECT COST	:	P 20,000,000.00
PROJECT DURATION	:	210 C.D.