

PROJECT FEATURE

PROJECT TITLE	:	PROPOSED TINGLOY PORT DEVELOPMENT PROJECT
LOCATION	:	Port of Tingloy, Tingloy, Batangas
SCOPE OF WORK	:	A. RECONSTRUCTION OF BACK-UP AREA (Area = 265.05 sq.m.) 1. Demolish and dispose existing concrete pavement (148 sq.m.), excavation of existing materials (91 cu.m.), chipping of existing rc curb (11 l.m.) and existing piles up to elevation MLLW (56 pcs) 2. Construction of rock bulkhead (1,803 cu.m.), fill materials(148 cu.m), reinforced concrete for mooring block and stairlanding (46 cu.m. (of concrete and 2,557 kg of reinforcing steel bars of various sizes) 3. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 148 sq.m.), including aggregate base course (28 cu.m.). 4. Supply and install of geotextile fabric (96 sq.m.) and mooring cleat (7 sets)
APPROVED BUDGET FOR THE CONTRACT	:	P 9,305,117.44
Sources of Funding	:	General Appropriation Act (GAA)
TOTAL PROJECT COST	:	P 10,000,000.00
PROJECT DURATION	:	150 C.D.