

PROJECT FEATURE

PROJECT TITLE	:	PROPOSED BADCOC PORT DEVELOPMENT PROJECT
LOCATION	:	Port of Badoc, Badoc, Ilocos Norte
SCOPE OF WORK	:	<p>A. CONSTRUCTION OF BACK-UP AREA (Area = 927.5 sq.m.)</p> <ol style="list-style-type: none">1. Demolish and dispose existing rc curb (72 l.m.),2. Construction of rock bulkhead (2,210 cu.m.), fill materials(3,199 cu.m), reinforced concrete for slotted rc curb, mooring block and stairlanding (79 cu.m. of concrete and 3,978 kg of reinforcing steel bars of various sizes),3. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 977 sq.m.), including aggregate base course (224 cu.m.).4. Supply and install of geotextile fabric (662 sq.m.) and mooring cleat (10 sets) <p>B. CONSTRUCTION OF PASSENGER SHED (Area = 253 sq.m.)</p> <ol style="list-style-type: none">1. Construction of one storey building (253 sq.m.) with complete electrical, water and drainage facilities
APPROVED BUDGET FOR THE CONTRACT	:	P 18,936,327.48
Sources of Funding	:	General Appropriation Act (GAA)
TOTAL PROJECT COST	:	P 20,000,000.00
PROJECT DURATION	:	210 C.D.