



## PROJECT FEATURE

PROJECT TITLE	: Proposed Dredging of Curimaø Port
LOCATION	: Currimao, Ilocos Norte
MAJOR SCOPE OF WORK	: <ul style="list-style-type: none"> <li>1.1) Dredging of right side berth of Pier 1 to a designed depth of 8.0 meter below Mean Lower Low Water (MLLW)</li> <li>1.2) Total Volume to be Dredged : 100,000.00 cu.m. of loose to medium dense clayish soil, mud, silt and sand</li> <li>1.3) Offshore disposal of dredged soil materials 16.00 kms away from the project site</li> <li>2.1) Excavation of Rock Formation near the Passenger Terminal to a designed depth of 3.0 meter below MLLW</li> <li>2.2) Total Volume to be Dredged : 3,200 cu.m. of broken rocks/corals and medium dense to highly dense clayish soil/sand, stones</li> <li>2.3) Land disposal of excavated soil materials 5.00 kms away from the project site</li> </ul>
APPROVED BUDGET FOR THE CONTRACT	: P 55,517,135.45
TOTAL PROJECT COST	: P 57,460,235.19
PROJECT (DREDGING) UNIT COST	: P 488.41 per cubic meter (Dredging Works Only excluding General Expenses, Excavation Works and Re-imbursable Item)
PROJECT DURATION	: 165 calendar days (inclusive of Sundays / Holidays and unworkable condition)