

PROJECT FEATURE

PROJECT TITLE

: PROPOSED EXTENSION OF RC PIER

LOCATION

: Port of Currimao, Currimao, Ilocos Norte

SCOPE OF WORK

A. CONSTRUCTION OF RC PIER EXTENSION
(Area = 3,348.00 sq.m.)

1. Supply and drive A252 Grade 2, 700mm ϕ x 13mm thk. Steel Pipe Piles (2,292 m.t.- 10,404 l.m.) including application of polyurethane external coating (2,710 sq.m.) , splicing (308 pcs), cutting (308 pcs) and installation of reinforcing band tip (308 pcs)
2. Supply and place 3,500 psi concrete filler (1,900 cu.m.) and reinforcing steel cage (438,618 kgs of various sizes) for steel pipe piles including extraction of clogged materials (341 cu.m.)
3. Supply and place 3,500 psi concrete (1,996 cu.m.) and reinforcing steel bars (246,285 kg of various sizes) for superstructure
4. Supply and install mooring bollard, 50 tons, T-head (16 sets), and rubber dock fender, V-type, 500H x 2500L (32 sets)

APPROVED BUDGET FOR THE CONTRACT : P

351,191,971.85

Sources of Funding

: PPA Corporate Fund

TOTAL PROJECT COST

: P 382,799,249.31

PROJECT DURATION

: 540 C.D.