

PROJECT FEATURE

PROJECT TITLE	:	AMBULONG PORT EXPANSION PROJECT	
LOCATION	:	Port of Ambulong, Magdiwang, Romblon	
SCOPE OF WORK	:	A. PORT OPERATIONAL AREA <ol style="list-style-type: none"> 1 Chipping & disposal of existing R.C. Curb (108 l.m.) 2 Removal of existing Mooring Bollard (1 set) 3 Supply & placing of 3,500 psi concrete for retaining wall (208 cu.m.) 4 Supply & installation of steel reinforcement for retaining wall (27,570 kg.) 5 Supply & placing of core rocks & armour rocks (2,841 cu.m.) 6 Supply & placing of fill materials (12,444 cu.m.) 7 Construction of PCC Pavement including Agg. Base Course (3,595 sq.m.) 8 Construction of security fence (183 l.m.) 9 Supply & installation of Portlighting system (4 sets) B. R.C. PIER, PLATFORM & RORO RAMP <ol style="list-style-type: none"> 1 Supply, delivery & driving of PSC square pile (7,053 l.m.) 2 Supply & placing of 3,500 psi concrete for Superstructure (692 cu.m.) 3 Supply & installation of steel reinforcement for Superstructure (100,277 kg.) 4 Supply & installation of construction joints (1 lot) 5 Supply & installation of Rubber dock fenders (21 sets) 6 Supply & installation of Mooring bollards (10 sets) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	166,483,539.26 ✓
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	188,126,399.36 ✓
PROJECT DURATION	:	420 Calendar Days	✓

P

J

mf

8