

PROJECT FEATURE

PROJECT TITLE : TAPAL PORT EXPANSION PROJECT

LOCATION : Port of Tapal, Brgy. Tapal, Ubay, Bohol

- SCOPE OF WORK :**
- A. REMOVAL AND EXCAVATION WORKS**
 - 1 Chipping of existing R.C. Curb
 - 2 Removal and disposal of existing Fence
 - 3 Excavation of existing sea bed
 - 4 Excavation of existing fill materials
 - 5 Removal and relocation of existing lamp post
 - B. PORT OPERATIONAL AREA & CONTINUOUS RORO RAMP**
 - 1 Supply, driving and cutting of PSC anchor piles
 - 2 Supply & driving of Steel Pipe pile including polyurethane coating
 - 3 Supply, fabricate band tip for the steel pipe piles
 - 4 Handling, pitching & driving of Steel Pipe piles
 - 5 Supply & installation of steel waling and splice plate
 - 6 Extraction of clogged materials inside the SPP
 - 7 Supply & placing of concrete filler for SPP
 - 8 Supply & installation of reinforcing steel cage for SPP
 - 9 Supply & placing of 3,500 psi concrete
 - 10 Supply & installation of reinforcing steel bars
 - 11 Supply & placing of gravel bedding
 - 12 Supply & placing of 50 to 1000 kg. rocks
 - 13 Supply & placing of sacked concrete
 - 14 Supply & placing of concrete blocks
 - 15 Supply & installation of Tie-rod
 - 16 Supply & installation of geotextile fabric
 - 17 Supply & placing of fill materials
 - 18 Supply & placing of aggregate base course
 - 19 Construction of PCC Pavement
 - 20 Construction of security fence
 - 21 Supply and installation of Portlighting system
 - 22 Construction of Drainage system
 - 24 Supply & installation of Rubber dock fenders
 - 25 Supply & installation of mooring bollards
 - C. RC WHARF EXTENSION**
 - 1 Supply & driving of Steel Pipe pile including polyurethane
 - 2 Handling, pitching & driving of Steel Pipe piles
 - 3 Supply, fabricate band tip for the steel pipe piles
 - 4 Extraction of clogged materials inside the SPP
 - 5 Supply & placing of concrete filler for SPP
 - 6 Supply & installation of reinforcing steel cage for SPP
 - 7 Supply & placing of 3,500 psi. concrete for the superstructure
 - 8 Supply & installation of reinf. steel bar for the superstructure
 - 9 Supply & installation of construction joints
 - 10 Supply & installation of Rubber dock fenders
 - 11 Supply & installation of mooring bollards

APPROVED BUDGET FOR THE CONTRACT : Php 608,220,754.83 ✓

SOURCES OF FUNDING : PPA Corporate Fund

TOTAL PROJECT COST : Php 679,990,803.90 ✓

PROJECT DURATION : 660 Calendar Days

