

## PROJECT FEATURE

PROJECT TITLE : CONSTRUCTION OF BACK-UP AREA AND RORO RAMP

LOCATION : Port of Tapal, Bohol

- SCOPE OF WORK :
- A. DEMOLITION, REMOVAL & EXCAVATION WORKS
    - 1 Demolition/removal of existing fence (18 l.m.)
    - 2 Excavation and backfill (82 cu.m.)
    - 3 Removal of existing mooring bollard (1 set)
    - 4 Chipping of existing R.C. Curb (23 l.m.)
    - 5 Demolition & disposal of existing concrete pavement (50 sq.m)
    - 6 Excavation of existing fill (15 cu.m)
    - 7 Excavation of existing fill & seabed (139 cu.m)
  - B. BACK-UP AREA & RORO RAMP (ON FILL)
    - 1 Supply & placing of concrete (194 cu.m.)
    - 2 Supply & installation of steel reinforcement (13,511 kg.)
    - 3 Supply & installation of concrete blocks (44 cu.m.)
    - 4 Supply, driving & chipping of PSC Sheet piles & corner piles (726 l.m.)
    - 5 Supply, driving & chipping of PSC square piles (60 l.m.)
    - 6 Supply & placing of gravel bedding (6 cu.m.)
    - 7 Supply & installation of core rocks ( 2,022 cu.m.)
    - 8 Supply & installation of armour rocks ( 1,648 cu.m.)
    - 9 Supply & installation of geotextile fabric (1,316 sq.m.)
    - 10 Supply & placing of fill materials (7,733 cu.m.)
    - 11 Supply & placing of aggregate base course (36 cu.m.)
    - 12 Supply & installation of Interlocking Concrete Paving Blocks (2,468 sq.m.)
    - 13 Construction of perimeter fence (112 l.m.)
    - 14 Construction of Portland Cement Concrete Pavement (374 sq.m.)
    - 15 Supply & installation of Tie-rods (13 sets)
    - 16 Supply & installation of rubber dock fenders & mooring bollards (6 sets)

APPROVED BUDGET FOR THE CONTRACT	:	Php	56,559,225.82
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	63,911,925.18
PROJECT DURATION	:	300 Calendar Days	