

**BID SUMMARY**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
 Port of Malalag, Malalag, Davao del Sur

NO.	DESCRIPTION OF WORK	AMOUNT(Pesos)
BILL NO. 1	GENERAL EXPENSES	
BILL NO. 2	CONSTRUCTION OF PORT OPERATIONAL AREA ON FILL	
BILL NO. 3	CONSTRUCTION OF PORT OPERATIONAL AREA ON PILES	
BILL NO. 4	RESTORATION OF EXISTING PORT OPERATIONAL AREA	
<b>BID PRICE</b>		

\_\_\_\_\_  
 Name of Firm

\_\_\_\_\_  
 Name of Bidder/Authorized Representative  
 (Signatory's Legal Capacity)

\_\_\_\_\_  
 Date

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 1</b>	<b>GENERAL EXPENSES</b>				
1.01	Mobilization, demobilization and cleaning	lot	1		
1.02	Rental of temporary site office and residence for the Engineer and staff	mo.	20		
1.03	Maintain temporary site office and residence for the Engineer and staff	mo.	20		
1.04	Provide Construction Safety and Health Program in the execution of the project	mo.	20		
<b>TOTAL FOR BILL NO. 1</b>					-

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 2</b>	<b>CONSTRUCTION OF PORT OPERATIONAL AREA ON FILL</b>				
2.01	Existing RC curb to be chipped-off and smoothen with mortar	l.m.	102		
2.02	Supply and deliver to site steel pipe sheet piles (A252 Grade 2, 900mm Ø x 13mm thk.) including welding of interlock connectors, sand blasting and other incidental works	m.t.	624		
2.03	Application of polyurethane external coating for steel pipe sheet piles (Polyurethane : 32-10 @ 1,500 microns dry film thickness or equivalent)	sq.m.	2,010		
2.04	Supply and install 9mm thk. reinforcing band tip for steel pipe sheet piles	no.	79		
2.05	Handle, pitch and drive steel pipe sheet piles (900mm Ø x 13mm thk.)	l.m.	2,054		
2.06	Cutting of driven steel pipe sheet piles up to cut-off elevation including turn-over to authority of excess piles	no.	79		
2.07	Supply, fabricate and install steel channel wale including splice plates, bolts, washers and other accessories	kg.	5,917		
2.08	Extract clogged materials from steel pipe sheet piles	cu.m.	301		
2.09	Supply and place sand filler for steel pipe sheet piles	cu.m.	474		
2.10	Supply and place 3,500 psi concrete filler for steel pipe sheet piles	cu.m.	190		

Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.11	Supply and install reinforcing steel cage for steel pipe sheet piles	kg.	24,069		
2.12	Supply and deliver to site 0. 35m x 0. 525m PSC sheet piles	l.m	1,225		
2.13	Supply and deliver to site RC corner sheet piles a) RC Sheet corner pile no.1 b) RC Sheet corner pile no.2	l.m l.m	50 50		
2.14	Handle, pitch and drive 0.35m x 0.525m PSC sheet piles and RC corner sheet piles	l.m.	1,325		
2.15	Supply and install 60mmØ x 17m tie-rod including accessories	set	52		
2.16	Supply and deliver to site 0. 45m x 0. 45m PSC anchor piles	l.m.	1,300		
2.17	Handle, pitch and drive 0.45m x 0.45m PSC anchor piles	l.m.	1,300		
2.18	Chipping and cutting of driven concrete piles up to cut-off elevation including disposal of debris	no.	105		
2.19	Supply & place 3,500 psi. concrete for retaining walls, anchor block , rc curb chb column, lamp post foundation and pedestal post	cu.m.	414		
2.20	Supply & install steel reinforcement for retaining walls, anchor block, rc curb, chb column, lamp post foundation and pedestal post	kg.	30,357		
2.21	Supply and place 1,000 kg. Armour rocks	cu.m.	137		

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.22	Supply and place 50-100 kg. Core rocks	cu.m.	3,190		
2.23	Supply and install Geotextile Fabric	sq.m.	1,833		
2.24	Supply and place sand and gravel fill	cu.m.	8,036		
2.25	Supply, place and compact aggregate sub-base course	cu.m.	2,640		
2.26	Supply, spread and compact aggregate base course	cu.m.	544		
2.27	Supply and place portland cement concrete pavement (PCCP, 300mm thk.)	sq.m.	96		
2.28	Construct concrete edging including steel reinforcement	sq.m.	245		
2.29	Supply, spread and compact 10% cement treated base course (150mm)	cu.m.	489		
2.30	Supply and spread leveling sand cushion (50mm thk.)	cu.m.	163		
2.31	Supply and install Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm)	sq.m.	3,262		
2.32	Construct CHB wall (150mm thk.) for perimeter fence including reinforcement	sq.m.	128.00		
2.33	Supply and place plain cement plaster finish for CHB wall and column	sq,m,	290.00		

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
2.34	Supply, fabricate and install various materials for cyclone wire mesh fence including barbed wire	sq.m.	191.00 ✓		
2.35	Supply and apply paint for concrete surfaces (2-coats)	sq.m.	290.00 ✓		
2.36	Remove and re-install existing steel gate including accessories	set	1 ✓		
2.37	Supply and install 610mm diameter RCP for drainage	l.m.	123 ✓		
2.38	Construct catch drain manhole including cover	no.	10 ✓		
2.39	Supply and place gravel bedding	cu.m.	113.00 ✓		
2.40	Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joint-1 including dowel bars	l.m.	141.00 ✓		
2.41	Remove and turn-over to authority existing fender	set	8.00 ✓		
2.42	Remove and turn-over to authority existing bollard	set	10.00 ✓		
2.43	Demolish and dispose existing concrete post	pc	1.00 ✓		
2.44	Demolish and dispose existing structure as shown in the plan	sq.m.	116.00 ✓		
2.45	Supply and install electrical works for port lighting	lot	1.00 ✓		
<b>TOTAL FOR BILL NO. 2</b>					

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO. 3</b>	<b>CONSTRUCTION OF PORT OPERATIONAL AREA ON PILES</b>				
3.01	Supply and deliver to site steel pipe piles (A252 Grade 2, 700mm Ø x 12mm thk.)	m.t.	1,234.00		
3.02	Application of polyurethane external coating and mastic filler for steel pipe piles (Polyurethane : 32-10 @ 1,500 microns dry film thickness or equivalent)	sq.m.	3,730.00		
3.03	Splice steel pipe piles as directed by the engineer	no.	118.00		
3.04	Supply and install 9mm thk. reinforcing band tip for steel pipe piles	no.	118.00		
3.05	Handle, pitch and drive steel pipe vertical piles (700mm x 12mm thk)	l.m.	3,774.00		
3.06	Handle, pitch and drive steel pipe batter piles (700mm x 12mm thk)	l.m.	2,288.00		
3.07	Extract clogged materials from steel pipe piles	cu.m.	253.00		
3.08	Supply and place 3,500 psi concrete filler for steel pipe piles	cu.m.	693.00		
3.09	Supply and install reinforcing steel cage for steel pipe piles	kg	153,490.00		
3.10	Cutting of driven steel pipe piles up to cut-off elevation including turn-over to authority of excess piles	no.	118.00		
3.11	Supply and place 3,500 psi concrete for superstructure	cu.m	806.00		

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
3.12	Supply and install steel reinforcements for superstructure	kg	137,757.00		
3.13	Supply and install hot-dipped galvanized BWT 100 x 12 bar for construction joint-2 including dowel bars	l.m.	102.00		
3.14	Existing RC curb to be chipped-off and smoothen with mortar	l.m.	30.00		
<b>TOTAL FOR BILL NO. 3</b>					

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>BILL NO.</b>	<b>4 RESTORATION OF EXISTING PORT OPERATIONAL AREA</b>				
4.01	Demolish and dispose existing concrete pavement	sq.m.	928.00		
4.02	Scrape/cut and dispose existing materials up to required elevation	cu.m.	528.00		
4.03	Subgrade preparation	sq.m.	758.00		
4.04	Existing retaining wall to be chipped-off to expose bar for built-up	l.m.	57.00		
4.05	Excavate, backfill and compaction of existing fill materials prior to installation of drainage system	cu.m.	730.00		
4.06	Supply, place and compact aggregate sub-base course	cu.m.	724.00		
4.07	Supply, spread and compact aggregate base course	cu.m.	114.00		
4.08	Construct concrete edging including steel reinforcement	sq.m.	166.00		
4.09	Supply, spread and compact 10% cement treated base course (150mm)	cu.m.	87.00		
4.10	Supply and spread leveling sand cushion (50mm thk.)	cu.m.	29.00		
4.11	Supply and install Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm)	sq.m.	579.00		
4.12	Supply and install 610mm diameter RCP for drainage	l.m.	48.00		

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

**BILL OF QUANTITIES**  
**MALALAG PORT EXPANSION AND RESTORATION PROJECT**  
Port of Malalag, Malalag, Davao del Sur

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
4.13	Construct catch drain manhole including cover	no.	4.00		
4.14	Supply and place gravel bedding	cu.m.	7.00		
4.15	Supply & place 3,500 psi. concrete for existing retaining wall built-up	cu.m.	26.00		
4.16	Supply & install steel reinforcement for existing retaining wall built-up	kg.	2,366.00		
<b>TOTAL FOR BILL NO. 4</b>					

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

## **BASIS OF PAYMENT FOR WORK ITEMS INCLUDED IN THE PROPOSAL**

The work items included in the proposal and the basis of payments are as follows:

### **BILL NO. 1**

#### **GENERAL EXPENSES**

**Item 1.01 Mobilization, demobilization and cleaning**

The quantity to be paid for shall be the minimum equipment requirement enumerated in the bid documents mobilized, demobilized and cleaning of the site and accepted by the Engineer. The contract lump sum price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to mobilize and demobilize all the minimum equipment requirement enumerated in the bid documents including cleaning of the site. Fifty percent (50%) of the total amount shall be payable after the mobilization activity while the remaining (50%) payable after demobilization and cleaning.

**Item 1.02 Rental of temporary site office and residence for the Engineer and staff**

The quantity to be paid for shall be the actual rental of site office and residence for the engineer and staff and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary for the provision of temporary site office and residence for the engineer and staff.

**Item 1.03 Maintain temporary site office and residence for the Engineer and staff**

The quantity to be paid for shall be the actual services rendered in maintaining the site office and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the maintenance of the temporary site office and residence as well as other expenses such as provision for electric power, telephone bill, potable water supply, janitorial and security services.

**Item 1.04 Provide construction safety and Health Program in the execution of the project**

The quantity to be paid for shall be the actual implementation of construction safety and health program and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the implementation of the Construction Safety and Health Program, as required and approved by the Department of Labor and Employment (DOLE).

## BILL NO. 2

### CONSTRUCTION OF PORT OPERATIONAL AREA ON FILL

**Item 2.01 Existing RC curb to be chipped-off and smoothen with mortar**

The quantity to be paid for shall be the actual length in linear meter existing RC curb to be chipped off and smoothened with mortar in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.02 Supply and deliver to site steel pipe sheet piles (A252 Grade 2, 900mm Ø x 13mm thk.) including welding of interlock connectors, sand blasting and other incidental works**

The quantity to be paid for shall be the actual weight in metric ton of steel pipe sheet piles (A252 Grade 2, 900mm Ø x 13mm thk.) including welding of interlock connectors, sand blasting and other incidental works, to be supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.03 Application of polyurethane external coating for steel pipe sheet piles (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent)**

The quantity to be paid for shall be the actual area in square meter of surfaces applied with polyurethane external coating for steel pipe sheet piles (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent) in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.04 Supply and install 9mm thick reinforcing band tip for steel pipe sheet piles**

The quantity to be paid for shall be the actual number of 9mm thick reinforcing band tip for steel pipe sheet piles to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.05 Handle, pitch and drive steel pipe sheet piles (900mm x 13mm thick)**

The quantity to be paid for shall be the actual length in linear meter of steel pipe sheet piles (900mm x 13mm thick) to be handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work

**Item 2.06      Cutting of driven steel pipe sheet piles up to cut-off elevation including turn-over to authority of excess piles**

The quantity to be paid for shall be the actual number of driven steel pipe sheet piles to be cut off up to required elevation including turn-over to authority of excess piles in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.07      Supply, fabricate and install steel channel wale including splice plates, bolts, washers and other accessories**

The quantity to be paid for shall be the actual weight in kilogram of steel channel wale including splice plates, bolts, washers and other accessories to be supplied, fabricated and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.08      Extract clogged materials from steel pipe sheet piles**

The quantity to be paid for shall be the actual volume in cubic meter of clogged materials extracted from steel pipe sheet piles in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.09      Supply and place sand filler for steel pipe sheet piles**

The quantity to be paid for shall be the actual volume in cubic meter sand filler for steel pipe sheet piles to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.10      Supply and place 3,500 psi concrete filler for steel pipe sheet piles**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete filler for steel pipe sheet piles to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.11      Supply and install reinforcing steel cage for steel pipe sheet piles**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel cage for steel pipe sheet piles to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.12 Supply and deliver to site 0. 35m x 0. 525m PSC sheet piles**

The quantity to be paid for shall be the actual length in linear meter of 0. 35m x 0. 525m PSC sheet piles to be supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.13 Supply and deliver to site RC corner sheet piles**

- a) RC Sheet corner pile no. 1
- b) RC Sheet corner pile no. 2

The quantity to be paid for shall be the actual length in linear meter of RC corner sheet piles of various sizes to be supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.14 Handle, pitch and drive 0.35m x 0.525m PSC sheet piles and RC corner sheet piles**

The quantity to be paid for shall be the actual length in linear meter of 0.35m x 0.525m PSC sheet piles and RC corner sheet piles to be handled, pitched and driven in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.15 Supply and install 60mmØ x 17m tie-rod including accessories**

The quantity to be paid for shall be the actual set of 60mmØ x 17m tie-rod including accessories to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.16 Supply and deliver to site 0. 45m x 0. 45m PSC anchor piles**

The quantity to be paid for shall be the actual length in linear meter of 0. 45m x 0. 45m PSC anchor piles to be supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.17 Handle, pitch and drive 0.45m x 0.45m PSC anchor piles**

The quantity to be paid for shall be the actual length in linear meter of 0.45m x 0.45m PSC anchor piles to be handled, pitched and driven in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.18 Chipping and cutting of driven concrete piles up to cut-off elevation including disposal of debris**

The quantity to be paid for shall be the actual number of concrete piles to be chipped off and cut off up to the required elevation including disposal of debris in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.19 Supply & place 3,500 psi. concrete for retaining walls, anchor block, rc curb, CHB column, lamp post foundation and pedestal post**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi. concrete to be supplied and set-in-place retaining walls, anchor block, rc curb, CHB column, lamp post foundation and pedestal post in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.20 Supply and install steel reinforcements for retaining walls, anchor block, rc curb, CHB column, lamp post foundation and pedestal post**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel bars to be supplied and installed for retaining walls, anchor block, rc curb, CHB column, lamp post foundation and pedestal post in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.21 Supply and place 1,000 kg. armour rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 1,000 kg. armour rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of armour rocks shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.22 Supply and place 50-100 kg. core rocks**

The quantity to be paid for shall be the actual volume in cubic meter of 50-100 kg. core rocks, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of core rocks shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.23 Supply and install geotextile fabric**

The quantity to be paid for shall be the actual area in square meter of geotextile fabric, supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.24 Supply and place sand and gravel fill**

The quantity to be paid for shall be the actual volume in cubic meter of sand and gravel fill, supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing of sand and gravel fill shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.25 Supply, place and compact aggregate subbase course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate subbase course to be supplied, set-in-place, and compacted in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after placing and compacting of aggregate subbase course rocks shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. Volume due to settlement as established using settlement plates shall also be considered for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.26 Supply, spread and compact aggregate base course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course to be supplied, spread, and compacted in accordance with the plans and specifications and accepted by the Engineer. Hydrographic/Topographic Surveys before and after spreading and compacting of aggregate subbase course rocks shall be made to determine the actual elevations along the cross sections and the actual quantities for payment. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.27 Supply and place Portland cement concrete pavement (PCCP, 300mm thick)**

The quantity to be paid for shall be the actual area in square meter of Portland cement concrete pavement (PCCP, 300mm thick), to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.28 Construct concrete edging including steel reinforcement**

The quantity to be paid for shall be the actual area in square meter of concrete edging including steel reinforcement, to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

- Item 2.29 Supply, spread and compact 10% cement treated base course (150mm)**
- The quantity to be paid for shall be the actual volume in cubic meter of 10% cement treated base course (150mm) to be supplied, spread, and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.
- Item 2.30 Supply and spread leveling sand cushion (50mm thk.)**
- The quantity to be paid for shall be the actual volume in cubic meter of leveling sand cushion (50mm thk.) to be supplied and spread in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.
- Item 2.31 Supply and install Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm)**
- The quantity to be paid for shall be the actual area in square meter of Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm), to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.
- Item 2.32 Construct CHB wall (150mm thk.) for perimeter fence including reinforcement**
- The quantity to be paid for shall be the actual area in square meter of CHB wall (150mm thk.) for perimeter fence including reinforcement, to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.
- Item 2.33 Supply and place plain cement plaster finish for CHB wall and column**
- The quantity to be paid for shall be the actual area in square meter of plain cement plaster finish, to be supplied and set-in-place for CHB wall and column in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.
- Item 2.34 Supply, fabricate and install various materials for cyclone wire mesh fence including barbed wire**
- The quantity to be paid for shall be the actual area in square meter of various materials for cyclone wire mesh fence including barbed wire to be supplied, fabricated, and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.35 Supply and apply paint for concrete surfaces (2-coats)**

The quantity to be paid for shall be the actual area in square meter of surfaces to be supplied and applied with 2 coats of paint for concrete surfaces in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.36 Remove and reinstall steel gate including accessories**

The quantity to be paid for shall be the actual set of steel gate including accessories to be removed and reinstalled in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.37 Supply and install 610mm diameter RCP for drainage**

The quantity to be paid for shall be the actual length in linear meter of 610mm diameter RCP supplied and installed for drainage in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.38 Construct catch drain manhole including cover**

The quantity to be paid for shall be the actual number of catch drain manhole including cover to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.39 Supply and place gravel bedding**

The quantity to be paid for shall be the actual volume in cubic meter of gravel bedding to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.40 Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joint-1 including dowel bars**

The quantity to be paid for shall be the actual length in linear meter of hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction joint-1 including dowel bars to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 2.41 Remove and turn-over to authority existing fender**

The quantity to be paid for shall be the actual set of existing fender to be removed and turned over to authority in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.42 Remove and turn-over to authority existing bollard**

The quantity to be paid for shall be the actual set of existing bollard to be removed and turned over to authority in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.43 Demolish and dispose existing concrete post**

The quantity to be paid for shall be the actual piece of existing concrete post to be demolished and properly disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.44 Demolish and dispose existing structure as shown in the plan**

The quantity to be paid for shall be the actual piece of existing structure as shown in the plan to be demolished and properly disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 2.45 Supply and install electrical works for port lighting**

The quantity to be paid for shall be the actual lot of electrical works for port lighting to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

### BILL NO. 3

#### CONSTRUCTION OF PORT OPERATIONAL AREA ON PILES

- Item 3.01 Supply and deliver to site steel pipe piles (A252 Grade 2, 700mm Ø x 12mm thk.)**
- The quantity to be paid for shall be the actual weight in metric ton of steel pipe piles (A252 Grade 2, 700mm Ø x 12mm thk.) to be supplied and delivered to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.
- Item 3.02 Application of polyurethane external coating and mastic filler for steel pipe piles (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent)**
- The quantity to be paid for shall be the actual area in square meter of surfaces applied with polyurethane external coating and mastic filler for steel pipe piles (Polyurethane: 32-10 @ 1,500 microns dry film thickness or equivalent) in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.
- Item 3.03 Splice steel pipe piles as directed by the engineer**
- The quantity to be paid for shall be the actual number of steel pipe piles to be spliced as directed by the engineer in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.
- Item 3.04 Supply and install 9mm thick reinforcing band tip for steel pipe piles**
- The quantity to be paid for shall be the actual number of 9mm thick reinforcing band tip for steel pipe piles to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.
- Item 3.05 Handle, pitch and drive steel pipe vertical piles (700mm x 12mm thick)**
- The quantity to be paid for shall be the actual length in linear meter of steel pipe vertical piles (700mm x 12mm thick) to be handled, pitched and driven in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work
- Item 3.06 Handle, pitch and drive steel pipe batter piles (700mm x 12mm thick)**
- The quantity to be paid for shall be the actual length in linear meter of steel pipe batter piles (700mm x 12mm thick) to be handled, pitched and driven in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.07 Extract clogged materials from steel pipe piles**

The quantity to be paid for shall be the actual volume in cubic meter of clogged materials extracted from steel pipe piles in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.08 Supply and place 3,500 psi concrete filler for steel pipe piles**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete filler for steel pipe piles to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.09 Supply and install reinforcing steel cage for steel pipe piles**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel cage for steel pipe piles to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.10 Cutting of driven steel pipe piles up to cut-off elevation including turn-over to authority of excess piles**

The quantity to be paid for shall be the actual number of driven steel pipe piles to be cut off up to required elevation including turn-over to authority of excess piles in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.11 Supply and place 3,500 psi concrete for structure**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete supplied and set-in-place for superstructure in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.12 Supply and install steel reinforcements for superstructure**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel bars to be supplied and installed for superstructure in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.13      Supply and install hot-dipped galvanized BWT 100 x 12 bar for construction joint-2 including dowel bars**

The quantity to be paid for shall be the actual length in linear meter of hot-dipped galvanized BWT 100 x 12 bar for construction joint-2 including dowel bars to be supplied and installed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 3.14      Existing RC curb to be chipped-off and smoothen with mortar**

The quantity to be paid for shall be the actual length in linear meter existing RC curb to be chipped off and smoothened with mortar in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

## BILL NO. 4

### RESTORATION OF EXISTING PORT OPERATIONAL AREA

**Item 4.01 Demolish and dispose existing concrete pavement**

The quantity to be paid for shall be the actual area in square meter of existing concrete pavement to be demolished and disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.02 Scrape/cut and dispose existing materials up to required elevation**

The quantity to be paid for shall be the actual volume in cubic meter of existing materials to be scraped/cut up to required elevation and properly disposed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.03 Subgrade preparation**

The quantity to be paid for shall be the actual area in square meter of subgrade prepared in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.04 Existing retaining wall to be chipped-off to expose bar for built-up**

The quantity to be paid for shall be the actual length in linear meter of existing retaining wall to be chipped-off to expose bar for built-up in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.05 Excavate, backfill and compaction of existing fill materials prior to installation of drainage system**

The quantity to be paid for shall be the actual volume in cubic meter of existing fill materials to be excavated, backfilled, and compacted prior to installation of drainage system in accordance with the plans and specifications, measured from the tip of piles to cut-off elevation and accepted by the Engineers. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.06 Supply, place and compact aggregate subbase course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate subbase course to be supplied, set-in-place, and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.07 Supply, spread and compact aggregate base course**

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course to be supplied, spread, and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.08 Construct concrete edging including steel reinforcement**

The quantity to be paid for shall be the actual area in square meter of concrete edging including steel reinforcement, to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.09 Supply, spread and compact 10% cement treated base course (150mm)**

The quantity to be paid for shall be the actual volume in cubic meter of 10% cement treated base course (150mm) to be supplied, spread, and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.10 Supply and spread leveling sand cushion (50mm thk.)**

The quantity to be paid for shall be the actual volume in cubic meter of leveling sand cushion (50mm thk.) to be supplied and spread in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.11 Supply and install Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm)**

The quantity to be paid for shall be the actual area in square meter of Interlocking Concrete Blocks Pavement (100mm x 200mm x 125mm), to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the work.

**Item 4.12 Supply and install 610mm diameter RCP for drainage**

The quantity to be paid for shall be the actual length in linear meter of 610mm diameter RCP supplied and installed for drainage in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.13 Construct catch drain manhole including cover**

The quantity to be paid for shall be the actual number of catch drain manhole including cover to be constructed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.14 Supply and place gravel bedding**

The quantity to be paid for shall be the actual volume in cubic meter of gravel bedding to be supplied and set-in-place in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.15 Supply and place 3,500 psi concrete for existing retaining wall built-up**

The quantity to be paid for shall be the actual volume in cubic meter of 3,500 psi concrete supplied and set-in-place for existing retaining wall built-up in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**Item 4.16 Supply and install steel reinforcements for existing retaining wall built-up**

The quantity to be paid for shall be the actual weight in kilogram of reinforcing steel bars to be supplied and installed for existing retaining wall built-up in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the work.

**FACILITIES TO BE PROVIDED FOR THE ENGINEER & HIS STAFF**

**RENTAL OF SITE OFFICE AND RESIDENCE FOR THE ENGINEER & STAFF**

The Contractor shall provide a temporary site office and residence (rental) with an area of at least 48 square meters for use of the Engineer and his staff for the whole duration of the project.

**MINIMUM MAJOR EQUIPMENT REQUIREMENTS**

1	unit/s	Air Compressor (250 cfm, minimum), owned ✓
1	unit/s	Backhoe (0.40 cu.m., 94.30hp, minimum), owned ✓
2	unit/s	Centrifugal Trash pumps, owned/leased ✓
1	unit/s	Clamshell, owned ✓
1	unit/s	Concrete cutter, owned ✓
2	unit/s	Concrete Mixer (1 bagger, minimum), owned ✓
2	unit/s	Concrete bucket, owned ✓
1	unit/s	Concrete Screeder, owned ✓
2	unit/s	Concrete Vibrator (3.5 hp, minimum), owned ✓
1	unit/s	Crane Barge (319 GW, minimum) with 60T crane, owned ✓
2	unit/s	Crawler Crane (30T, minimum), owned ✓
1	unit/s	Crawler Crane (20T, minimum), owned/leased ✓
1	unit/s	Pile Hammer (Diesel, 10,500 kg.m.), owned ✓
1	unit/s	Pile Hammer (Diesel, 7,500 kg.m.), owned/leased ✓
2	unit/s	Drop Hammer (2T, minimum), owned ✓
2	unit/s	Dump Truck (8 cu.m., minimum), owned ✓
2	unit/s	Bar Bender (electric, 25mm dia min.), owned ✓
2	unit/s	Bar Cutter (electric, 25mm dia min.), owned ✓
1	unit/s	Forklift (1.36T, minimum), owned/leased ✓
2	unit/s	Jackhammer, owned ✓
2	unit/s	Oxy/Acetylene cutting outfit, owned ✓
1	unit/s	Payloader (80 hp, minimum), owned ✓
2	unit/s	Plate Compactor (5 hp, minimum), owned ✓
1	unit/s	Road Grader (125 hp, minimum), owned ✓
1	unit/s	Road Roller (12.05T, vibratory, minimum), owned ✓
2	unit/s	Transit Mixer (5-6 cu.m. cap., minimum), owned/leased ✓
1	unit/s	Tugboat (500hp, minimum), owned/leased ✓
1	unit/s	Water Truck with pump (1,000 gal., minimum), owned ✓
2	unit/s	Welding Machine (400 amp., minimum), owned ✓
1	unit/s	Cargo Truck (5T, minimum), owned ✓

## CONSTRUCTION SAFETY AND HEALTH REQUIREMENT

The Contractor shall implement the construction safety and health program in accordance with the applicable provisions of the Occupational Safety and Health Standards (OSHS) of the Department of Labor and Employment (DOLE).

The Contractor, subject to the approval of the Engineer shall provide and maintain throughout the duration of the contract a medical room with at least 15 square meters together with all necessary supplies to be sited in the Contractor's main area.

The Contractor shall provide the following minimum requirements:

### LABOR

1	no.	Safety Engineer / Officer
1	no.	Nurse / Health Officer

### EQUIPMENT / MATERIALS

#### Personnel Protective Equipment

51	pcs.	Hard Hats
51	pairs	Gloves (rubberized)
51	pcs.	Safety Glasses/Goggles (clear)
102	pcs.	Long sleeve T-shirt
8	pc.	Aprons
4	pc.	Safety Belts
51	pairs	Safety Shoes
4	sets	Life Lines

#### Safety Devices

1	lot	Barricades
1	lot	Warning signs
2	unit/s	Fire extinguisher (10kg)

Medical and First Aid System	-	Twenty (20) mos.
Temporary shelter for workers	-	1 lot

### NOTE:

The Contractor shall provide the above-cited minimum construction safety and health requirements or as required by the Engineer.

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2016  
Attachment

Page 1 of 10

**REVISED SCHEDULE OF MINIMUM TEST REQUIREMENTS OF  
CONSTRUCTION MATERIALS FOR PPA INFRASTRUCTURE PROJECTS**

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
<b>I. Construction of Pier/Wharf, Platform and Ramp</b>		
Structural Concrete (SC)		
A Portland Cement	Quality Test	For every 2,000 bags (40kg) or fraction thereof
B Fine Aggregate	Quality Test for Grading, Elutriation (wash), Bulk Specific Gravity, Absorption, Mortar Strength, Soundness, Organic Impurities, Unit Weight, % Clay Lumps and Shale	For every 1,500 cubic meter or fraction thereof
C Coarse Aggregate	Quality Test for Grading, Bulk Specific Gravity, Absorption and Abrasion	For every 1,500 cubic meter or fraction thereof
D Water	Certificate from the Engineer or Quality Test for Density and Chloride Content	One per source
E Steel Bars	Mill Certificate and Quality Test for Chemical Composition and Mechanical Properties	For every 10,000 kg or fraction thereof
F Concrete	Compressive Strength on cylinder samples	1 set consisting of 3 concrete cylinder samples shall be taken from each day's pouring and to represent not more than 75 cu m of concrete or fraction thereof
	Slump Test	For every mix
G Admixture and Concrete Curing Materials	Quality Test	One per shipment
Piling (P)		
A Concrete Piles	Fabrication Report	One per fabrication
1 Concrete	Same test as for SC (F)	Same frequency as SC (F)
2 Steel Bars	Same test as for SC (E)	Same frequency as SC (E)
3 High Tension Strand	Test for Chemical Composition and Mechanical Properties	For every 20000kg or fraction thereof

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2016  
Attachment

Page 2 of 10

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
4 Coarse Aggregates	Same Test as for SC (C)	Same frequency as SC (C)
5 Fine Aggregates	Same Test as for SC (B)	Same frequency as SC (B)
B Steel Pipe Piles	Fabrication Report, Mill Certificate and Quality Test for Chemical and Mechanical properties	One per fabrication
1 Steel	Chemical Composition (refer below) <ul style="list-style-type: none"> <li>- Under 14" (355 60mm) Outside Diameter</li> <li>- 14" to 36" (355 6 to 914mm) Outside Dia</li> <li>- Over 36" (914mm) Outside Diameter</li> </ul>	2 from 200 pipe of fraction thereof 2 from 100 pipe or fraction thereof 2 from 3000ft (914m) or fraction thereof
	Mechanical/Tensile	One (1) tension test shall be made on one length or fraction thereof of each size, or one piece of skelp representing each lot of 200 lengths or fraction thereof of each size
2 Polyurethane Coating	Mill Certificate and Quality Test	One per fabrication
3 Concrete	Same test as for SC (F)	Same frequency as SC (F)
4 Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
5 Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
6 Steel Bars	Same Test as SC (E)	Same frequency as SC (E)
7 Water	Same Test as SC (D)	Same frequency as SC (D)
Rubber Dock Fenders (RDF)	Physical Test Performance Test for Energy Absorption and Reaction Force	All units All units
Accessories		
Washer and Fixing Bolt, Anchor Bolt	Physical Test Quality Test for Chemical Composition and Mechanical Properties	All units One per fabrication

PPA MEMORANDUM CIRCULAR  
 No. 02  
 Series of 2016  
 Attachment

Page 3 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
Mooring Bollard (MB) and Accessories (Hexagon Nuts, Plain Washer, Anchor Ring and Anchor Bolt)	Physical Test  Quality Test for Chemical Composition and Mechanical Properties	All Units  One per fabrication
<b>II. Construction of Back-Up Area, Causeway and Pavement</b>		
Sheet Piling (SP)		
A Concrete Sheet Piles		
1 Concrete	Same test as for SC (F)	Same frequency as SC (F)
2 Steel Bars	Same test as for SC (E)	Same frequency as SC (E)
3 High Tension Strands	Same test as for P (A 3)	Same frequency as P (A 3)
4 Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
5 Coarse Aggregates	Same Test as for SC (C)	Same frequency as SC (C)
B Steel Pipe Piles		
1 Steel	Same test as for P (B1)	Same frequency as P (B1)
2 Concrete	Same test as for SC (F)	Same frequency as SC (F)
3 Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
4 Steel Bars	Same test as for SC (E)	Same frequency as SC (E)

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2016  
Attachment

Page 4 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
Rocks	Test for Apparent Specific Gravity and Abrasion	For every 1,500 cubic meter or fraction thereof
Geotextile Filter	Physical and Mechanical Test Mill Certificate	One per batch One per batch
Sand and Gravel Fill	Quality Test for Organic Impurities and Grading	For every 1,500 cubic meter or fraction thereof
Selected Fill	Quality Test for Grading, Plasticity and Laboratory Compaction Test  Laboratory California Bearing Ratio (CBR)  Field Density Test	For every 1,500 cubic meter or fraction thereof  For every 2,500 cubic meter or fraction thereof  For every layer of 150mm of compacted depth at least one group of three In-situ density test for every 500 sq m or fraction thereof
Aggregate Base Course	Quality Test for Grading and Plasticity  Quality Test for Grading, Plasticity, Abrasion and Laboratory Compaction Test  Laboratory California Bearing Ratio (CBR)  Field Density Test	For every 300 cubic meter or fraction thereof  For every 1,500 cubic meter or fraction thereof  Same frequency as Selected Fill  Same frequency as Selected Fill
Portland Cement Concrete Pavement (PCCP)		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Steel Bars (Dowels)	Same test as for SC (E)	Same frequency as SC (E)
F Joint Filler	Quality Test	One (1) per shipment

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2016  
Attachment

Page 5 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
G Admixture and Concrete Curing Material	Same test as for SC (G)	Same frequency as SC (G)
H Concrete	Same test as for SC (F)  Flexural Test	Same frequency as SC (F)  3 beam samples for every 330 sq m or fraction thereof
I Completed Pavement	Core Test	1 set (3 specimen) for every 2,500 sq m and fraction thereof
<b>Interlocking Concrete Blocks</b>		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregate	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Admixture & Concrete Curing Materials	Same test as for SC (G)	Same frequency as SC (G)
F Completed Blocks	Physical Test and Compressive Strength	6 blocks per day of fabrication
<b>Cement Treated Base Course (CTB)</b>		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine & Coarse Aggregates	Quality Test for Grading, Abrasion and Soundness	For every 1,500 cubic meter or fraction thereof
C Water	Same test as for SC (D)	Same frequency as SC (D)
D Completed CTB	Field Density Test	For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof
<b>Retaining Wall/Coping Wall/RC Curb/RC Ditch/Shear Key/Concrete Blocks/Lean Concrete</b>		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregate	Same test as for SC (B)	Same frequency as SC (B)

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2018  
Attachment

Page 6 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Steel Bars	Same test as for SC (E)	Same frequency as SC (E)
F Admixture and Concrete Curing	Same test as for SC (G)	Same frequency as SC (G)
G Concrete	Same test as for SC (F)	Same frequency as SC (F)
<b>Tie Rod</b>		
A Steel	Same test as for SC (E)	One per batch
B Assembly	Performance Test (Tension)	One per batch
<b>Tie Bars and Dowels</b>	Same test as for SC (E)	For every 10,000 kg or fraction thereof per Tie bars and Dowels
<b>Pipe Culverts and Storm Drains</b>		
A Pipes	Test for Strength, Absorption and Physical	For every 50 pieces
B Mortar or Joint	Same Test as for SC (A,B and D) Alternative Test Same test as for SC (F) and Inspection Report	For every 25 pieces
<b>Concrete Hollow Blocks</b>		
A Portland Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Water	Same test as for SC (D)	Same frequency as SC (C)
D Concrete	Same test as for SC (F)	Same frequency as SC (F)
E Completed CHB	Quality Test	One for every 500 pieces or fraction thereof
<b>Construction Joints (CJ)</b>		
A Angle Bars	Test for Physical and Mechanical Properties	One per batch
B Steel Bars	Same test as for SC (E)	One per batch
C Zinc (Hot Dip Galvanizing) Coatings	Physical Test for Appearance, Stripping, Weighing, Adherence and Adhesion  Coating Thickness Magnetic Thickness Measurement	All units  1 set (3 specimen) for every 100,000 sq mm or fraction thereof

PPA MEMORANDUM CIRCULAR  
No. 02  
Series of 2016  
Attachment

Page 7 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
<b>Sacked Concrete</b>		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Concrete	Same test as for SC (F)	Same frequency as SC (F)
F Sack (jute)	Physical Test	One for every 50 pieces
<b>Rubble Concrete</b>		
A Cement	Same test as for SC (A)	Same frequency as SC (A)
B Fine Aggregates	Same test as for SC (B)	Same frequency as SC (B)
C Coarse Aggregates	Same test as for SC (C)	Same frequency as SC (C)
D Water	Same test as for SC (D)	Same frequency as SC (D)
E Concrete	Same test as for SC (F)	Same frequency as SC (F)
F Rocks	Same test as for ROCKS	Same frequency as ROCKS
<b>Earthworks</b>		
A Sub-grade preparation	Grading Test Plasticity Test (LL, PL, PI) Laboratory Compaction Test  Density Test	For every 1,500 cubic meter or fraction thereof  For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof
B Structure Excavation	If excavated materials shall be used as Backfill Grading Test Plasticity Test (LL, PL, PI) Laboratory Compaction Test  Density Test	For every 1,500 cubic meter or fraction thereof  For every layer of 150mm of compacted depth at least one group of three in-situ density test every 500 sq m or fraction thereof

*TAC*

PPA MEMORANDUM CIRCULAR  
 No. 02  
 Series of 2016  
 Attachment

Page 8 of 10

<b>Materials/Items of Work</b>	<b>Required Tests</b>	<b>Minimum Incremental Frequency of Tests</b>
<b>III Port Operations Building/Passenger Terminal Building/Transit Shed/Warehouse</b>		
<b>STRUCTURAL WORKS</b> Refer to Structural Concrete (SC) and Piling Works (P)		
<b>ARCHITECTURAL WORKS</b>		
Ceramic – Filled Liquid Membrane / Water Proofing, Hydrophobic Poreblocking Ingredients with Superplasticizer	Physical Property, Mechanical and Chemical Property, Leak Test / Flood Test	One per shipment
Paint	Quality Test	One 4-L can for every 100 cans or fraction thereof
Ceramic Tile	Inspection and Evaluation Report from the Engineer	One per shipment
Stainless Steel	Inspection and Evaluation Report from the Engineer	One per shipment
Roofing Materials	Inspection and Evaluation Report from the Engineer	One per shipment
Ceiling Materials	Inspection and Evaluation Report from the Engineer	One per shipment
<b>ELECTRICAL AND MECHANICAL WORKS</b>		
Wires / Cables	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment
Electrical Devices	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment
Fire Alarm System	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per item
Wiring Devices	Inspection and Evaluation Report from the Engineer Testing and Commissioning	One per shipment

PPA MEMORANDUM CIRCULAR  
 No. 02  
 Series of 2016  
 Attachment

Page 9 of 10

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Protective Devices	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per shipment
Telephone System	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
CCTV System	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
CATV System	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
Background Music and Paging System	Inspection and Evaluation Report from the Engineer, Testing and Commissioning	One per item
Air Conditioning Units & Ventilation	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
Conduit Pipes	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
Lighting Fixtures	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
<b>PLUMBING WORKS</b>		
Pipes	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item

UAC


PPA MEMORANDUM CIRCULAR  
 No. 02  
 Series of 2016  
 Attachment


Page 10 of 10

Materials/Items of Work	Required Tests	Minimum Incremental Frequency of Tests
Fixtures	Inspection and Evaluation Report from the Engineer  Testing and Commissioning	One per item
Pipe Culverts	Compression Strength  Inspection and Evaluation Report from the Engineer	For every size not more than 25 pipes cast in the field
<b>IV Miscellaneous Materials</b> Fencing A Barbed Wire, Cyclone Wire Mesh, Chain Link  B Concrete Post	Physical Test (Dimensions and Coatings)  Refer to Superstructure (SC)	One per Batch  Refer to Superstructure (SC)
Lamp Post A Structural Steel  B Zinc (Hot Dip Galvanizing) Coatings	Physical Test (Dimensions) Same test as for SC (E)  Same test as for CJ (C)	All units  One per batch
Drainage Steel Grating	Same test as for SC (E)  Inspection Report	One (1) batch
Metal Pipe (Cast Iron Galvanized, etc )	Physical Test (Dimensions and Coatings)	1 per delivery
Welding Works	Destructive and Non Destructive Test	One (1) per lot

- NOTES**
1. Testing of RDF shall be performed only by an independent Testing Laboratory duly accredited by BRS, DOST and PPA
  2. Testing of other materials shall be performed only by an independent Testing Laboratory duly accredited by BRS and PPA.
  3. All other issuances which are otherwise inconsistent herewith are hereby revoked or otherwise amended.

Approved

  
**RAUL T. SANTOS**  
 Officer-In-Charge,  
 Office of the General Manager



*SECTION IX*

*CHECKLIST OF TECHNICAL  
AND FINANCIAL DOCUMENTS*

# Checklist of Technical and Financial Documents

## I. TECHNICAL COMPONENT ENVELOPE

### *Class "A" Documents*

#### Legal Documents

- (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages)

#### Technical Documents

- (b) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid; **and**
- (c) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided under the rules; **and**
- (d) Special PCAB License in case of Joint Ventures; **and** registration for the type and cost of the contract to be bid; **and**
- (e) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission;  
**or**  
Original copy of Notarized Bid Securing Declaration; **and**
- (f) Project Requirements, which shall include the following:
  - a. Organizational chart for the contract to be bid;
  - b. List of contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen), to be assigned to the contract to be bid, with their complete qualification and experience data;
  - c. List of contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership or certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be; **and**
- (g) Original duly signed Omnibus Sworn Statement (OSS); **and** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Financial Documents

- (h) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC).

**Class "B" Documents**

- (i) If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence;  
or  
duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

**II. FINANCIAL COMPONENT ENVELOPE**

- (j) Original of duly signed and accomplished Financial Bid Form; **and**

*Other documentary requirements under RA No. 9184*

- (k) Original of duly signed Bid Prices in the Bill of Quantities; **and**
- (l) Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid; **and**
- (m) Cash Flow by Quarter.

*SECTION X*  
*BIDDING FORM*

## Bid Form for the Procurement of Infrastructure Projects

*[shall be submitted with the Bid]*

---

### BID FORM

Date : \_\_\_\_\_  
Project Identification No. : \_\_\_\_\_

To: **Philippine Ports Authority**  
PPA Building, Bonifacio Drive,  
South Harbor, Port Area, Manila

Having examined the Philippine Bidding Documents (PBDs) including the Supplemental or Bid Bulletin Numbers \_\_\_\_\_, the receipt of which is hereby duly acknowledged, we, the undersigned, declare that:

- a. We have no reservation to the PBDs, including the Supplemental or Bid Bulletins, for the Procurement Project: **Malalag Port Expansion and Restoration Project, Port of Malalag, Malalag, Davao del Sur;**
- b. We offer to execute the Works for this Contract in accordance with the PBDs;
- c. The total price of our Bid in words and figures, excluding any discounts offered below is: \_\_\_\_\_;
- d. The discounts offered and the methodology for their application are: \_\_\_\_\_;
- e. The total bid price includes the cost of all taxes, such as, but not limited to: *[specify the applicable taxes, e.g. (i) value added tax (VAT), (ii) income tax, (iii) local taxes, and (iv) other fiscal levies and duties]*, which are itemized herein and reflected in the detailed estimates,
- f. Our Bid shall be valid within the period stated in the PBDs, and it shall remain binding upon us at any time before the expiration of that period;
- g. If our Bid is accepted, we commit to obtain a Performance Security in the amount of \_\_\_\_\_ percent of the Contract Price for the due performance of the Contract, or a Performance Securing Declaration in lieu of the the allowable forms of Performance Security, subject to the terms and conditions of issued GPPB guidelines<sup>1</sup> for this purpose;
- h. We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;
- i. We understand that this Bid, together with your written acceptance thereof

---

<sup>1</sup> currently based on GPPB Resolution No. 09-2020

included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and

- j. We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.
  
- k. We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the **Malalag Port Expansion and Restoration Project, Port of Malalag, Malalag, Davao del Sur of the Philippine Ports Authority.**
  
- l. We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: \_\_\_\_\_

Legal Capacity: \_\_\_\_\_

Signature: \_\_\_\_\_

Duly authorized to sign the Bid for and behalf of: \_\_\_\_\_

Date: \_\_\_\_\_

**STATEMENT OF THE BIDDER'S ALL ONGOING GOVERNMENT AND PRIVATE CONTRACTS, INCLUDING CONTRACTS AWARDED BUT NOT YET STARTED**

I hereby declare that all ongoing contracts, including awarded contracts yet to be started coinciding with the contract to be bid are listed below:

Name of outstanding Contracts 1]	Owner's Name and Address	Scope of Work 2]	Contractor's Role and Percentage of Participation 3]	Total Contract Amount or Value 4]	Date of Contract and NOA 5]	Value of Outstanding Works 6]	Accomplishment (in percentage, %) 7]		Contract Duration 8]	
							Planned	Actual	Start of Project	Estimated Completion Date
A) Government Contracts i. On-going ii. Awarded but not yet started										
B) Private Contracts i. On-going ii. Awarded but not yet started										

**NOTE:**

- 1] As appearing in the contract executed by the parties.
- 2] With special reference to the Scope of Works of the Project as described/enumerated in the Contract.
- 3] Indicate the percentage of participation and whether as Sole Contractor, Sub-Contractor or Member in a Joint Venture / Consortium.
- 4] Indicate the FOREX used if Contract Value is expressed in a currency other than the Philippine Peso.
- 5] As appearing in the Contract and Notice of Award (NOA).
- 6] Amount or value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started coinciding with the contract to be bid.
- 7] Percentage of Accomplishment as of the preceding month which should not be earlier than two (2) months from the date of bid submission.
- 8] As appearing in the Notice to Proceed and Contract.

This Statement shall be supported by:

- a) Notice of Award
- b) Notice to Proceed and Contract

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

\_\_\_\_\_  
Date

Revised: September 2021

**STATEMENT OF THE BIDDER'S SINGLE LARGEST COMPLETED CONTRACT (SLCC) SIMILAR TO THE CONTRACT TO BE BID**

Name of the completed Contract 1]	Owner's Name and Address	Scope of Work 2]	Contractor's Role and Percentage of Participation 3]	Total Contract Value At 4]			Date of Award 5]	Contract Duration 6]	
				Award	Completion	Escalated Value to Present Prices		Start	Completed

**NOTE :**

- 1] As appearing in the contract executed by the parties.
- 2] With special reference to the Scope of Works of the Project as described/enumerated in the Contract.
- 3] Indicate the percentage of participation and whether as Sole Contractor, Sub-Contractor or Member in a Joint Venture / Consortium.
- 4] Indicate the FOREX used if Contract Value is expressed in a currency other than the Philippine Peso. Attached the computation for the escalated contract value.
- 5] As appearing in the Notice of Award.
- 6] As appearing in the Notice to proceed and Certificate of Completion.

- A. The bidder must have an experience of having completed a SLCC that is similar to the contract to be bid equivalent to at least fifty percent (50%) of the ABC, adjusted if necessary, by the Bidder to current prices using the PSA consumer price indices. A contract is considered to be "similar" to the contract to be bid if it has the same Major Categories of Work as stated in the Bid Data Sheet (BDS).
- B. This Statement shall be supported by:
  - a. Notice of Award, Notice to Proceed and Contract.
  - b. Project Owner's Certificate of Final Acceptance issued by the owner and/ or Constructors Performance Evaluation System (CPES) Final Rating, which must be at least Satisfactory. The said Certificate of Acceptance shall contain the following: 1) Name of project owner that issued the certificate, 2) Name of Contractor/ Constructor, 3) Name of Contract, and 4) Contract Duration.
  - c. Recapitulation or Final Bill of Quantities.

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

\_\_\_\_\_  
Date

Revised: September 2021

**STATEMENT OF THE BIDDER'S EXPERIENCE ON MAJOR CATEGORIES OF WORK OF THE SLCC INCLUDING OTHER COMPLETED CONTRACTS  
SIMILAR TO THE CONTRACT TO BE BID**

Major Categories of Work 1]	Unit of Measure 1]	Quantity 1]	SLCC similar to the contract to be bid 2]	Other completed contracts similar to the contract to be bid 2]				Unit of Measure 2]	Quantity 2]
			Name of the contract	Name of the contract	Name of the contract	Name of the contract			
1. Pile Driving Works	l.m.	5,371							
2. Reinforced Concrete Works	cu.m.	1,065							
3. Rockworks (50 to 1,000 kg/pc.)	cu.m.	1,664							
4. Placing of Fill Materials	cu.m.	5,700							
5. Construction of Portland Cement Concrete Pavement	sq.m.	48							
6. Installation of interlocking concrete paving blocks	sq.m.	1,921							

**NOTE:**

1] As stated in the Bid Data Sheet.

2] As appearing in the Recapitulation and/ or Final Bill of Quantities.

This statement shall be supported by:

- a. Notice of Award, Notice to Proceed and Contract.
- b. Project Owner's Certificate of Final Acceptance issued by the owner and/ or Constructors Performance Evaluation System (CPES) Final Rating, of at least satisfactory. The said Certificate of Acceptance shall contain the following: 1) Name of project owner that issued the certificate, 2) Name of Contractor/Constructor, 3) Name of Contract, and 4) Contract Duration.
- c. Recapitulation and/ or Final Bill of Quantities.

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
Signatory's Legal Capacity

\_\_\_\_\_  
Date

Revised: September 2021

## FINANCIAL DATA

- A. The prospective bidder's audited Financial Statements, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "RECEIVED" by the Bureau of Internal Revenue (BIR), or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than two (2) years from the date of bid submission.

	Year
1. Total Assets	
2. Current Assets	
3. Total Liabilities	
4. Current Liabilities	
5. Net worth (1-3)	
6. Net Working Capital (2-4)	

- B. The computation of the bidders Net Financial Contracting Capacity (NFCC) must be at least equal to the ABC to be bid, as follows:

NFCC = [ (Current assets minus current liabilities) (15) ] minus the value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started coinciding with the contract to be bid.

NFCC = \_\_\_\_\_

Attached herewith are certified true copies of the audited financial statements stamped received by the BIR or BIR authorized collecting agent for the latest/immediately preceding calendar year.

\_\_\_\_\_  
Name of Firm/Applicant

\_\_\_\_\_  
Authorized Signing Official

Date: \_\_\_\_\_

**NOTES:**

If Partnership or Joint Venture, each Partner or Member Firm of Joint venture shall submit separate financial statements.

**STATEMENT OF THE BIDDER'S KEY PERSONNEL PLEDGED FOR THE CONTRACT TO BE BID**

I hereby declare that the following key personnel are qualified and available for the duration of the contract to be bid:

Position of Key Personnel 1]	Name	No. of Key Personnel	Similar Experience in the Position (Years) 2]	Total Experience in the Position (Years)	Attachment(s)	Annex(es)
Project Manager					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "
Project Engineer					PRC License (CE Preferred) Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "
Materials Engineer II					PRC License (CE Preferred) Submit Valid and Renewed DPWH Certificate of Accreditation Submit Accreditation Identification Card as Materials Engineer Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "
Construction Safety and Health Officer					Certificate of Safety and Health Construction Related Course issued by DOLE Accredited Trainings Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "
Foreman					Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "
Other Position(s)					Complete Qualification and Experience Data Certificate of Commitment	Annex " _ "

**NOTE:** 1] As stated in the Bid Data Sheet

2] The number of years of experience of the key personnel shall be as indicated in the qualification and experience data or curriculum vitae.

Minimum qualification requirements: The key personnel must have a work experience that is similar in nature and complexity to the contract to be bid.

Project Manager - Five (5) years

Materials Engineer – One (1) year

Project Engineer - Three (3) years

Materials Engineer I – for projects costing up to 100M

Foreman - Five (5) years

Materials Engineer II – for projects costing more than 100M

Construction Safety and Health Officer – One (1) year

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

\_\_\_\_\_  
Date

Revised: September 2021

**STATEMENT OF THE BIDDER'S EQUIPMENT PLEDGED FOR THE CONTRACT TO BE BID**

I hereby declare that the following equipment are in good operating condition and available for the duration of the contract to be bid:

DESCRIPTION (Type, Model, Make)	No. of Unit(s)	Capacity/ Output  1]	Owned, Leased, and/or under purchased agreement 2]	Proof of Ownership/ Leased/ Under Purchase Agreement (Mark as Annex "A.....Z") 3]	OTHER INFORMATION (As Applicable)				
					Manufacturer	Engine Serial No.	Chassis No./ Name of Vessel	Location	Status

**NOTE:**

- 1] The unit of capacity of the pledged equipment shall be as indicated in the Proof of Ownership, i.e. GW (for crane barge), DWT (for deck barge and hopper barge), Ton (for crane, road roller and drop hammer), kg.-m/blow (for diesel hammer), cu.m. (for dump truck), hp (for tugboat, road grader, bulldozer and concrete vibrator), cfm (for compressor), gal (for water truck with pump), amp (for welding machine), bagger (for concrete mixer). If the capacity of the pledged equipment is not indicated in the Proof of Ownership/Leased Contract/Purchased Agreement, submit other proof of capacity such as specifications, brochures or other verifiable printouts indicating the model name, model number and other details of the equipment.
- 2] Indicate if the pledged equipment are owned, leased or under purchase agreement.
- 3] If the pledged equipment is owned, it should be in the name of the bidder. Submit proof of ownership, i.e. deed of sale, sales invoice, official receipt; For owned Water Truck, Dump Truck and Transit Mixer submit LTO Certificate of Registration and valid Official Receipt; For owned barge/tugboat, submit Marina Certificate of Ownership and valid Cargo Ship Safety Certificate.

If the pledged equipment is leased/under purchased agreement, submit certification of availability of equipment from the equipment lessor/vendor for the duration of the project, and duly Notarized copy of leased contract/purchased agreement.

If the pledged barge/tugboat is leased/under purchase agreement, submit certification of availability of barge/tugboat from the equipment lessor/vendor for the duration of the project, and duly Notarized copy of leased contract/purchased agreement together with a copy of the Marina Certificate of Ownership and valid Cargo Ship Safety Certificate.

The Minimum Major Equipment Requirements are listed in Section 8, Annex 3.

\_\_\_\_\_  
Name of Firm

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

\_\_\_\_\_  
Date

Revised: September 2021

**Omnibus Sworn Statement for Sole Proprietorship**  
*[shall be submitted with the Bid]*

REPUBLIC OF THE PHILIPPINES )  
CITY/MUNICIPALITY OF \_\_\_\_\_ ) S.S.

**AFFIDAVIT**

I, \_\_\_\_\_, of legal age, [Civil Status], [Nationality], and residing at \_\_\_\_\_, after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the sole proprietor or authorized representative of \_\_\_\_\_ with office address at \_\_\_\_\_;
2. As the owner and sole proprietor, or authorized representative of \_\_\_\_\_, I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for **Malalag Port Expansion and Restoration Project, Port of Malalag, Malalag, Davao del Sur** of the **Philippine Ports Authority**, as shown in the attached duly notarized Special Power of Attorney;
3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, **by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;**
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
6. The owner or sole proprietor is not related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. [Name of Bidder] complies with existing labor laws and standards; and
8. [Name of Bidder] is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
  - a. Carefully examining all of the Bidding Documents;
  - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
  - c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the [Name of the Project].

9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.
10. **In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.**

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_ day of \_\_, 20\_\_ at \_\_\_\_\_,  
Philippines.

---

Name of Bidder/ Authorized Representative  
(Signatory's Legal Capacity)  
AFFIANT

**[Jurat]**  
*[Format shall be based on the latest Rules on Notarial Practice]*

**Omnibus Sworn Statement for Partnership or Cooperative**  
*[shall be submitted with the Bid]*

---

REPUBLIC OF THE PHILIPPINES )  
CITY/MUNICIPALITY OF \_\_\_\_\_ ) S.S.

**AFFIDAVIT**

I, \_\_\_\_\_, of legal age, [Civil Status], [Nationality], and residing at \_\_\_\_\_, after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of \_\_\_\_\_ with office address at \_\_\_\_\_;
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for **Malalag Port Expansion and Restoration Project, Port of Malalag, Malalag, Davao del Sur** of the **Philippine Ports Authority**, as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)];
3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, **by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;**
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers and members of [Name of Bidder] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. [Name of Bidder] complies with existing labor laws and standards; and
8. [Name of Bidder] is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
  - a. Carefully examining all of the Bidding Documents;
  - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
  - c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the [Name of the Project].

9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.
10. **In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.**

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_ day of \_\_, 20\_\_ at \_\_\_\_\_, Philippines.

---

Name of Bidder/ Authorized Representative  
(Signatory's Legal Capacity)  
AFFIANT

**[Jurat]**

*[Format shall be based on the latest Rules on Notarial Practice]*

**Omnibus Sworn Statement for Corporation or Joint Venture***[shall be submitted with the Bid]*

REPUBLIC OF THE PHILIPPINES )  
CITY/MUNICIPALITY OF \_\_\_\_\_ ) S.S.

**AFFIDAVIT**

I, \_\_\_\_\_, of legal age, [Civil Status], [Nationality], and residing at \_\_\_\_\_, after having been duly sworn in accordance with law, do hereby depose and state that:

1. I am the duly authorized and designated representative of \_\_\_\_\_ with office address at \_\_\_\_\_;
2. I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for **Malalag Port Expansion and Restoration Project, Port of Malalag, Malalag, Davao del Sur**, as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)];
3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, **by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;**
4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;
5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;
6. None of the officers, directors, and controlling stockholders of [Name of Bidder] is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;
7. [Name of Bidder] complies with existing labor laws and standards; and
8. [Name of Bidder] is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:
  - a. Carefully examining all of the Bidding Documents;
  - b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
  - c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
  - d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the [Name of the Project].
9. [Name of Bidder] did not give or pay directly or indirectly, any commission, amount, fee, or any

form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

10. **In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.**

IN WITNESS WHEREOF, I have hereunto set my hand this \_\_ day of \_\_, 20\_\_ at \_\_\_\_\_, Philippines.

\_\_\_\_\_  
Name of Bidder/ Authorized Representative  
(Signatory's Legal Capacity)  
AFFIANT

**[Jurat]**

*[Format shall be based on the latest Rules on Notarial Practice]*

**Bid Securing Declaration Form**  
*[shall be submitted with the Bid if bidder opts to provide this form of bid security]*

---

REPUBLIC OF THE PHILIPPINES)  
CITY OF \_\_\_\_\_) S.S.

**BID SECURING DECLARATION**  
**Project Identification No.:** \_\_\_\_\_

To: **Philippine Ports Authority**  
PPA Building, Bonifacio Drive,  
South Harbor, Port Area, Manila

I/We, the undersigned, declare that:

1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any procurement contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1(b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA No. 9184; without prejudice to other legal action the government may undertake.
3. I/We understand that this Bid Securing Declaration shall cease to be valid on the following circumstances:
  - a. Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
  - b. I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right; and
  - c. I am/we are declared the bidder with the Lowest Calculated Responsive Bid, and I/we have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this \_\_\_\_ day of [month] [year] at [place of execution].

---

Name of Bidder/ Authorized Representative  
(Signatory's Legal Capacity)  
AFFIANT

**[Jurat]**  
*[Format shall be based on the latest Rules on Notarial Practice]*

## CONSTRUCTION METHODOLOGY

Name of Project : \_\_\_\_\_  
Project Description : \_\_\_\_\_  
Location : \_\_\_\_\_

### MINIMUM SCOPE OF CONSTRUCTION METHODOLOGY

#### A. CONSTRUCTION OF PORT OPERATIONAL AREA ON FILL

Area = 3,562.52 sq.m.

1. Supply and drive A252 Grade 2, 900mmØ x 13mm thk. Steel Pipe Sheet Piles (624 m.t equivalent to 2,054 l.m.), including application of polyurethane external coating (2,010 sq.m.), supply and place sand filler (474 cu.m.), concrete filler (190 cu.m.), installation of reinforcing steel cage bar (24,069 kg of various sizes), extraction of clogged materials (301 cu.m.), cutting of steel pipe sheet piles up to cut-off elevation and installation of reinforcing band tip (79 pcs)
2. Supply and drive of concrete piles (0.35m x 0.525m x 25 m psc sheet piles - 1,225 l.m., rc corner sheet piles - 100 l.m. and 0.45m x 0.45m x 25m PSC anchor piles - 1,300 l.m.), including chipping and cutting of newly driven piles up to required elevation (105 pcs)
3. Supply and installation of steel channel wale (5,917 kg), tie rod (52 pcs - 60mmØ x 17m), geotextile fabric (1,833 sq.m.) and various materials for port lighting system
4. Construction of rock bulkhead (3,327 cu.m.), fill materials (10,676 cu.m), reinforced concrete for retaining wall, anchor block, rc curb, chb column, lamp post foundation and pedestal post (414 cu.m. of concrete and 30, 357 kg of reinforcing steel bars of various sizes)
5. Construction of CHB wall (128 sq.m.), including plastering with painting (290 sq.m.), and installation of various materials for cyclone wire mesh (191 sq.m.)
6. Construction of interlocking concrete block pavement (3,262 sq.m.) and PCCP (300mm thk., 96 sq.m.), including aggregate base course (544 cu.m.), cement treated base course (489 cu.m.), sand cushion (163 cu.m.) and concrete edging (245 sq.m.)
7. Construction of catch drain manhole (10 sets) and reinforced concrete pipe (610mmØ 123 l.m.), including gravel bedding (113 cu.m.)
8. Remove and turn-over to authority existing mooring bollard (10 sets), existing RDF (8 sets), demolish and dispose existing fish landing structure (116 sq.m.)

#### B. CONSTRUCTION OF PORT OPERATIONAL AREA ON PILES

Area = 1,493.54 sq.m.

1. Supply and drive A252 Grade 2, 700mmØ x 12mm thk. Steel Pipe Piles ( 1,234 m.t equivalent to 6,062 l.m.), including application of polyurethane external coating (3,730 sq.m.), supply and place concrete filler (693 cu.m.), installation of reinforcing steel cage bar (153,490 kg of various sizes), extraction of clogged materials (253 cu.m.), splicing, cutting of steel pipe piles up to cut-off elevation and installation of reinforcing band tip (118 pcs)
2. Supply and place 3,500 psi concrete (806 cu.m.) and reinforcing steel bars (137,757 kg of various sizes for superstructure

**C. RESTORATION OF EXISTING PORT OPERATIONAL AREA**

**Area = 757.53 sq.m.**

1. Excavate/backfill and compaction of existing fill materials (730 cu.m.), scraping/cutting of existing materials (528 cu.m.) including subgrade preparation (758 sq.m.), demolition of existing concrete pavement (928 sq.m.) and chipping of existing retaining wall (57 l.n.)
2. Construction of interlocking concrete block pavement (579 sq.m.), including aggregate base course (114 cu.m.), cement treated base course (87 cu.m.), sand cushion (29 cu.m.) and concrete edging (166 sq.m.)
3. Construction of catch drain manhole (4 sets) and reinforced concrete pipe (610mmØ - 48 l.m.), including gravel bedding (7 cu.m.)
4. Supply and place 3,500 psi concrete (26 cu.m.) and reinforcing steel bars (2,366 kg of various sizes for retaining wall built-up

**NOTES:**

The narrative construction method will guide and familiarize the contractor and the PPA on how the project shall be carried out in accordance with the highest standard of workmanship.

The construction method shall be consistent with the Bar Chart / S-Curve Schedule, Equipment Schedule and Manpower Schedule.

---

Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

Revised: September 2021

## MANPOWER SCHEDULE

Name of Project : \_\_\_\_\_

Project Description : \_\_\_\_\_

Location : \_\_\_\_\_

<b>MANPOWER (Minimum)</b>	<b>CONTRACT DURATION ( _____ Calendar Days)</b>																											
	<b>M O N T H L Y</b>																											
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
Project Manager																												
Project Engineer																												
Materials Engineer II																												
Construction Safety and Health Officer																												
Foreman																												
<b>Specify other applicable positions, ie.:</b>																												
- Carpenter																												
- Steelman																												
- Mason																												
- Electrician																												
- Rigger																												
- Others																												

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

Revised: September 2021



## CASHFLOW BY QUARTER AND PAYMENT SCHEDULE

Name of Project: : \_\_\_\_\_

Project Description : \_\_\_\_\_

Location : \_\_\_\_\_

Project Duration (days or months)	Payment Schedule (Monthly, in Pesos)	Cash flow (Quarterly, in Pesos)
<b>TOTAL</b>		

**NOTES**

- The cash flow by quarter and payment schedule should be consistent with the Bar Chart and S-curb.
- Payment schedule shall not be more than once a month.

\_\_\_\_\_  
Name of Bidder/Authorized Representative  
(Signatory's Legal Capacity)

Revised: September 2021

**Contract Agreement Form for the  
Procurement of Infrastructure Projects (Revised)**

*[not required to be submitted with the Bid, but it shall be submitted within ten (10) days after receiving the Notice of Award]*

---

**CONTRACT AGREEMENT**

THIS AGREEMENT, made this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_ between **Philippine Ports Authority** with principal office at PPA Building, Bonifacio Drive, South Harbor, Port Area, Manila (hereinafter called the "Entity") and **[name and address of Contractor]** (hereinafter called the "Contractor").

WHEREAS, the Entity is desirous that the Contractor execute **[name and identification number of contract]** (hereinafter called "the Works") and the Entity has accepted the Bid for **[contract price in words and figures in specified currency]** by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents as required by the 2016 revised Implementing Rules and Regulations of Republic Act No. 9184 shall be deemed to form and be read and construed as part of this Agreement, viz.:
  - a. Philippine Bidding Documents (PBDs);
    - i. Drawings/Plans;
    - ii. Specifications;
    - iii. Bill of Quantities;
    - iv. General and Special Conditions of Contract;
    - v. Supplemental or Bid Bulletins, if any;
  - b. Winning bidder's bid, including the Eligibility requirements, Technical and Financial Proposals, and all other documents or statements submitted;  
  
Bid form, including all the documents/statements contained in the Bidder's bidding envelopes, as annexes, and all other documents submitted (e.g., Bidder's response to request for clarifications on the bid), including corrections to the bid, if any, resulting from the Procuring Entity's bid evaluation;
  - c. Performance Security;
  - d. Notice of Award of Contract and the Bidder's conforme thereto; and

- e. Other contract documents that may be required by existing laws and/or the Procuring Entity concerned in the PBDs. **Winning bidder agrees that additional contract documents or information prescribed by the GPPB that are subsequently required for submission after the contract execution, such as the Notice to Proceed, Variation Orders, and Warranty Security, shall likewise form part of the Contract.**
3. In consideration for the sum of [total contract price in words and figures] or such other sums as may be ascertained, [Named of the bidder] agrees to [state the object of the contract] in accordance with his/her/its Bid.
4. The **Philippine Ports Authority** agrees to pay the above-mentioned sum in accordance with the terms of the Bidding.

IN WITNESS whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

**JAY DANIEL R. SANTIAGO**  
General Manager

**Name of Bidder/ Authorized  
Representative**  
(Signatory's Legal Capacity)

for:

for:

**Philippine Ports Authority**

**Contractor**

**Acknowledgment**

*[Format shall be based on the latest Rules on Notarial Practice]*