

PROJECT FEATURE

PROJECT TITLE	:	ABRA DE ILOG PORT EXPANSION PROJECT	
LOCATION	:	Port of Abra De Ilog, Occidental Mindoro	
SCOPE OF WORK	:	A. DEMOLITION, EXCAVATION AND REMOVAL WORKS <ol style="list-style-type: none"> 1 Chipping & disposal of existing R.C. Curb (148 l.m.) 2 Demolition & disposal of existing Roro Ramp deck (99 sq.m.) 3 Excavation of existing seabed & fill materials (5,868 cu.m.) 4 Removal of existing Mooring Bollard (12 sets) 5 Extraction/removal of existing concrete structure (696 cu.m.) B. PORT OPERATIONAL AREA <ol style="list-style-type: none"> 1 Supply, delivery & driving of PSC Piles & RC Corner Piles (3,682 l.m.) 2 Supply, delivery & driving of 800mm dia. Steel Pipe Piles (567 m.t.) 3 Supply & placing of sand filler (206 cu.m.) 4 Supply & placing of 3,500 psi concrete for SPP & superstructure (1,544 cu.m.) 5 Supply & installation of steel reinforcement for SPP & superstructure (161 m.t.) 6 Supply & placing of core rocks & armour rocks (15,172 cu.m.) 7 Supply & installation of fabricated Concrete blocks (10 sets) 8 Supply & installation of Tie-rod of various sizes (157 sets) 9 Supply & placing of fill materials (121,095 cu.m.) 10 Construction of PCC Pavement including Agg. Base Course (22,467 sq.m.) 11 Supply & installation of Mooring bollard (4 sets) 12 Construction of Security Fence (236 l.m.) 13 Supply & installation of Portlighting system (3 sets) C. R.C. PIER & RO-RO RAMP <ol style="list-style-type: none"> 1 Supply, delivery & driving of PSC Test Pile (2 units) 2 Supply, delivery & driving of PSC Piles (2,997 l.m.) 3 Supply & placing of 3,500 psi concrete for Superstructure (522 cu.m.) 4 Supply & installation of steel reinforcement for Superstructure (80.60 m.t.) 5 Supply & installation of construction joints (98 l.m.) 6 Supply & installation of Rubber dock fenders (22 sets) 7 Supply & installation of Mooring bollards (16 sets) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	523,060,025.32 /
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	591,057,828.61 /
PROJECT DURATION	:	660 Calendar Days	/

9

Wf