

**PROJECT FEATURE**

<b>PROJECT TITLE</b>	:	<b>BORAC PORT DEVELOPMENT PROJECT</b>	
<b>LOCATION</b>	:	<b>Brgy. Borac, Coron, Palawan</b>	
<b>SCOPE OF WORK</b>	:	<b>A. BACK-UP AREA</b> <ol style="list-style-type: none"> <li>1 Supply &amp; driving of steel pipe sheet piles (3,111.00 l.m.)</li> <li>2 Supply &amp; installation of steel waling (13,387 kg.)</li> <li>3 Cutting of steel pipe piles (183 no.)</li> <li>4 Removal/extraction of clogged material inside the the SPP (220 cu.m.)</li> <li>5 Supply &amp; placing of sand &amp; concrete inde the SPP (880)</li> <li>6 Excavation and bacfilling works (1,610 cu.m.)</li> <li>7 Supply &amp; placing of 3,500 psi concrete (1,686 cu.m.)</li> <li>8 Supply &amp; installation of reinforcing steel bars (109,200 kg.)</li> <li>9 Supply &amp; installation of geotextile fabric (3,905 sq.m.)</li> <li>10 Supply &amp; placing of 50 to 2,000 kg. rocks (11,061 cu.m.)</li> <li>11 Supply &amp; installation of Tie-rods of various sizes (72 sets)</li> <li>12 Supply &amp; placing of fill materials (30,880 cu.m.)</li> <li>13 Construction of concrete pavement (9,314 sq.m.)</li> <li>14 Supply &amp; installation of trench grate for lateral drainage (172 sets)</li> <li>15 Supply &amp; installation of trench grate for catch drain (3 sets)</li> <li>16 Supply &amp; installation of Lamp Post with integrated solar street light (8 sets)</li> </ol> <b>B. MOORING AND FENDER SYSTEM</b> <ol style="list-style-type: none"> <li>1 Supply &amp; installation of Rubber dock fenders (6 sets)</li> <li>2 Supply &amp; installation of mooring bollards (4 sets)</li> </ol>	
<b>APPROVED BUDGET FOR THE CONTRACT</b>	:	<b>Php</b>	<b>321,616,766.20</b>
<b>SOURCES OF FUNDING</b>	:	<b>PPA Corporate Fund</b>	
<b>TOTAL PROJECT COST</b>	:	<b>Php</b>	<b>363,426,945.80</b>
<b>PROJECT DURATION</b>	:	<b>540 Calendar Days</b>	



