

PROJECT FEATURE

PROJECT TITLE : **PROPOSED CODON PORT DEVELOPMENT PROJECT**

LOCATION : **Port of Codon, Brgy. Codon, San Andres, Catanduanes**

SCOPE OF WORK

A. CONSTRUCTION OF BACK-UP AREA / PIER APPROACH
(Area = 104.28 sq.m.)

1. Demolish and dispose existing rc curb (7 l.m.)
2. Construction of rock bulkhead (423 cu.m.), fill materials(177 cu.m), reinforced concrete for rc curb and retaining wall (57 cu.m. of concrete and 5,927 kg of reinforcing steel bars of various sizes)
3. Construction of portland cement concrete pavement (PCCP, 250mm thk. - 99 sq.m.), including aggregate base course (19 cu.m.).
4. Supply and install of geotextile fabric (81sq.m.)

B. CONSTRUCTION OF RC PIER
(Area = 243 sq.m.)

1. Supply and drive 0.40m x 0.40m PSC piles (954 l.m.), supply and place 3,500 psi reinforced concrete (109 cu.m) and steel bars (16,254 kg) for superstructure
2. Supply and install mooring bollards, 15 tons, T-head (5 sets) and Rubber Dock Fender (V-type 250H x 1500L) (18 sets)

APPROVED BUDGET FOR THE CONTRACT : P **18,079,620.13**
Sources of Funding : **General Appropriation Act (GAA)**

TOTAL PROJECT COST : P **20,000,000.00**

PROJECT DURATION : **210 C.D.**



