

**PROJECT FEATURE**

|   |   |   |                      |
|---|---|---|----------------------|
| <b>PROJECT TITLE</b>                    | : | <b>VIGA PORT DEVELOPMENT PROJECT</b>  |                      |
| <b>LOCATION</b>                         | : | <b>Brgy. Tambongon, Viga Catanduanes</b>  |                      |
| <b>SCOPE OF WORK</b>                    | : | <b>A. CONSTRUCTION OF ROCK CAUSEWAY</b><br>a. Demolition/disposal of existing concrete pavement (138 sq.m.)<br>b. Supply & placing of 3,500 psi concrete (106 cu.m.)<br>c. Supply & installation of reinforcing steel bars (13,342 kg.)<br>d. Supply & placing of 2-3 tons rocks (568 cu.m.)<br>e. Supply & placing of 5-20 kg. rocks (637 cu.m.)<br>f. Supply and placing of geotextile fabric (441 sq.m.)<br>g. Supply and placing of gravel base course (53 sq.m.)<br>h. Construction of Portland Cement Concrete pavement (267 sq.m.)<br>i. Supply & installation of mooring cleat (6 sets) |                      |
| <b>APPROVED BUDGET FOR THE CONTRACT</b> | : | <b>Php</b>  | <b>8,908,101.74</b>  |
| <b>SOURCES OF FUNDING</b>               | : | <b>General Appropriation Act (GAA)</b>  |                      |
| <b>TOTAL PROJECT COST</b>               | : | <b>Php</b>  | <b>9,977,073.95</b>  |
|   |   | <b>Say</b>  | <b>10,000,000.00</b> |
| <b>PROJECT DURATION</b>                 | : | <b>150 Calendar Days</b>  |                      |