

PROJECT FEATURE

PROJECT TITLE	: RESTORATION OF ROCKBULKHEAD, PASSENGER TERMINAL BUILDING, TMO BUILDING, AND PORT LIGHTING SYSTEM DUE TO TYPHOON KARDING AT PORT OF DINGALAN, AURORA	
LOCATION	: Port of Dingalan, Aurora	NRP-BNA-01-23
SCOPE OF WORK	<p>1.0 General expenses</p> <p>1.01 Mobilization and Demobilization Cost / Clean-up</p> <p>1.02 Provide Construction Safety & Health Program in the execution of the project</p> <p>2.0 Removal and Disposal Works</p> <p>2.01 Removal and Disposal of debris at Port of Dingalan</p> <p>3.0 RESTORATION OF MAIN GATE, MOVABLE FENCE AND SLOPE PROTECTION INCLUDING ROCKBULKHEAD</p> <p>3.01 Supply and place 60-100kg core rocks</p> <p>3.02 Supply and place 1,000-2,000kg armour rocks</p> <p>3.03 Supply and place 3,500 psi concrete for pile cap/wave deflector, armour cap, strap beam, deadman block and gate column</p> <p>3.04 Supply and install steel reinforcement for pile cap/wave deflector, armour cap, strap beam, deadman block and gate column</p> <p>3.05 Supply, fabricate and install stainless steel gate at Main Entrance Gate including accessories</p> <p>3.06 Supply, fabricate and install movable steel fence along the deflector wall</p> <p>4.0 RESTORATION OF TERMINAL MANAGEMENT OFFICE BUILDING</p> <p>4.01 Supply and install Rib-type roofs and ridged roll incl. removal works</p> <p>4.02 Supply and install Ceiling at the TMO-Building</p> <p>5.0 RESTORATION OF PASSENGER TERMINAL BUILDING AND GUARD HOUSE</p> <p>5.01 Replacement of damaged doors, windows, including accessories of the Passenger Terminal Building and Guard House</p> <p>6.0 Installation of New Port Lighting and Electrical System</p> <p>6.01 Supply and install Solar Integrated 80W LED, 8500lm, daylight, 12.8V Aluminum Steel Light SSL-Pro</p> <p>6.02 Supply and install 1-70W, 6.650lm, daylight 24V LED Street Lights, 2x100W Solar panels.</p> <p>6.03 Supply and install 1-70W, 5.500lm, daylight 12V LED Street Lights</p> <p>6.04 Replacement of damaged wires (3-30mm² THHN Cu wire) and rusted panel board/circuit breakers of TMO Building</p> <p>6.05 Replacement of damaged wires (3-80mm² THHN Cu + 1-30mm² THHN Cu) including accessories from PTB Panel Board to Genset Room</p> <p>6.06 Replacement of damaged wires (3-100mm² THHN Cu + 1-30mm² THHN Cu) including accessories from Genset Room to KWHR Pull Box at Main Gate</p> <p>7.0 Painting Works</p> <p>7.01 Supply and apply various paint materials on concrete surfaces for repainting of concrete fence and curb</p> <p>7.02 Supply and apply various paint materials on steel surfaces for painting of movable steel fence</p> <p>7.03 Supply and apply various paint material for repainting of ceiling at the TMO Building (2 coats)</p>	
APPROVED BUDGET FOR THE CONTRACT	: Php 13,017,772.30	
SOURCE OF FUNDING	: PPA Corporate Fund	
TOTAL PROJECT COST	: Php 14,514,816.11	
PROJECT DURATION	: 146 Calendar Days	