

**PROJECT FEATURE**

**PROJECT TITLE** : CONSTRUCTION OF RORO RAMP, PLATFORM AND PIER EXTENSION

**LOCATION** : Port of Bulan, Bulan, Sorsogon

**SCOPE OF WORK** A. CONSTRUCTION OF RC PLATFORM, RORO RAMP AND RC PIER

1. Removal of existing roro ramp RC deck including turning over of materials with value to PPA (99 sq.m.)
2. Supply and drive 400mm x 400mm x 29m PSC test pile (2 units)
3. Supply and drive 400mm x 400mm regular PSC piles (9,510 l.m.) including chipping of pile up to required elevation (348 units)
4. Supply and place 3,500 psi concrete (1,004 cu.m.) including steel reinforcements (178,002 kg)
5. Supply and install hot-dipped galvanized 100mm x 100mm x 10mm angle bar for construction and expansion joints including dowel bars (168 l.m.)
6. Supply and install fendering (V-type rubber dock fenders, 26 sets -V400H x 2000L and 3 sets - V500H x 1500L ) and mooring system (28 sets - 35 ton T-head mooring bollard)

**APPROVED BUDGET FOR THE CONTRACT** : P 120,383,257.51

**Sources of Funding** : PPA Corporate Fund

**TOTAL PROJECT COST** : P 136,033,080.99

**PROJECT DURATION** : 540 C.D.