

PROJECT FEATURE

PROJECT TITLE	:	BRGY. U-OG PORT DEVELOPMENT PROJECT	
LOCATION	:	Brgy. U-og, Inabanga, Bohol	
SCOPE OF WORK	:	A. BACK-UP AREA AND CAUSEWAY <ol style="list-style-type: none">1 Removal/ demolition of concrete structures along existing causeway (21 cu.m.)2 Removal/ demolition and disposal of existing passenger shed incl. foundation (15 sq.m.)3 Excavation of existing seabed along the containment of stairlandings (529 cu.m.)4 Supply, deliver & drive PVC sheet piles and corner piles, 458mm width (3,262 l.m.)5 Supply and place 10-100 kg . core rocks (161 cu.m.)6 Supply and install geotextile fabric (840 sq.m.)7 Supply and place sand and gravel fill (5,704 cu.m.)8 Supply, spread and compact selected fill (1,996 cu.m.)9 Supply, place and compact gravel bedding for retaining wall, stairlanding, RC tie-beam and mooring block (22 cu.m.)10 Supply and place 3,500 psi. concrete for retaining wall, stairlanding, RC tie-beam, mooring block, concrete facing and RC curb (675 cu.m.)11 Supply and install steel reinforcement for retaining wall, stairlanding, RC tie-beam, mooring block, concrete facing and RC curb (38,805 kg.)12 Supply and install Dia. 32mm tie-rod including accessories (23 set)13 Supply, spread and compact gravel base course (369 cu.m.)14 Construct portland cement concrete pavement (230mm thk.) including asphalt sealer and dowel bars for construction joint (1,847 sq.m.)15 Supply and install mooring cleat including accessories (21 no.) B. PORT LIGHTING SYSTEM <ol style="list-style-type: none">1 Supply, deliver and install 6 meters steel tapered lamp post in hot dip galvanized including lighting devices and accessories (5 no.) C. CONSTRUCTION OF PASSENGER SHED <ol style="list-style-type: none">1 Construction of 1-storey Passenger Shed Building (50 pax, 250 sq.m.)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	45,355,694.70
SOURCES OF FUNDING	:	GAA	
TOTAL PROJECT COST	:	Php	49,891,264.17
PROJECT DURATION	:	360 Calendar Days	

