

Philippine Ports Authority
PORT MANAGEMENT OFFICE-NCR NORTH

PROJECT FEATURE

PROJECT TITLE : Restoration/Improvement and Repainting of VTMS Radar Station 2 Facility

LOCATION : Corregidor Island, Cavite

SCOPE OF WORK :

Bill No. 1 - GENERAL EXPENSES

1. Mobilization, demobilization & clean-up cost. 1 Lot
2. Provide environmental safety and health program in the execution of the project. 1 Lot

Bill No. 2 - RESTORATION AND REPAINTING OF 35-M CYLINDRICAL R.C. RADAR TOWER

1. Replacement of Dilapidated/Corroded Spiral Steel Stair Riser Steps and Railings. 1 lot
2. Repainting of Spiral Steel Stairs, Railings and Handrails. 1 lot
3. Repainting of Cylindrical Concrete Tower. 1 lot

Bill No. 3 - RESTORATION/IMPROVEMENT AND REPAINTING OF 3-STOREY 'RADAR STATION BUILDING

1. Replacement of Dilapidated/Defective Aluminum Sliding windows. 1 lot
2. Repainting Works. 1 lot
3. Replacement of Defective PVC Door at Second Floor Comfort Room. 1 set
4. Waterproofing of Roofdeck. 1 lot
5. Installation of Steel Round Hatch Door at Roofdeck. 1 set

Bill No. 4 - INSTALLATION OF ROOF EAVE PROTECTION FOR THE GENSET/GENSET DIESEL

1. Supply, fabricate and install structural roof truss framing including C-purlins and associated builder's and painted with 1-coat epoxy primer paint as indicated in the plan. 1 lot
2. Supply and install pre-painted corrugated roofing sheet as indicated in the plan. 1 lot

Bill No. 5 - TRANSPORTATION OF SALVAGE SCRAP MATERIALS AND OTHER UNSERVICEABLE MATERIALS

1. Transport and deliver project steel/aluminum/glass scrap materials to include the existing scrap/unserviceable materials from the Project Site to PPA, PMO-NCR North Compound in Manila. 1 lot

APPROVED BUDGET FOR THE CONTRACT : Php 1,353,759.62

SOURCES OF FUNDING PPA Corporate Fund

TOTAL PROJECT COST : Php 1,489,136.00

PROJECT DURATION : 90 Calendar Days