

PROJECT FEATURE

PROJECT TITLE	:	TABLAS (POCTOY) PORT EXPANSION PROJECT
LOCATION	:	Port of Tablas (Poctoy), Odiongan, Romblon
SCOPE OF WORK	:	<p>A. DEMOLITION AND REMOVAL WORKS</p> <ol style="list-style-type: none">1 Demolish and dispose existing RC Deck (1,637 sq.m.)2 Removal of existing mooring bollard (12 sets)3 Removal of existing rubber dock fenders (13 sets)4 Chip-off existing piles up to pile cap elevation (63 no.)5 Chip-off existing piles up to elevation 0.00 (MLLW) (180 no.)6 Chip-off existing piles up to required elev. for mooring/anchor block (22 no.)7 Excavation of existing seabed (2,171 cu.m.)8 Excavation of fill material for installation of RCPC (25 cu.m.)9 Clearing and removal of underwater debris prior to driving of piles (75 sq.m.) <p>B. RC PIER REHABILITATION AND EXTENSION</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of PSC square piles (1,220 l.m.)2 Supply & placing of concrete for the superstructure (353 cum.)3 Supply & installation of steel reinforcement for the superstructure (48,778 kg.)4 Supply & installation of construction joints (27 l.m.)5 Supply & installation of mooring bollard (16 sets)6 Supply & installation of Rubber dock fenders (16 sets) <p>C. CONSTRUCTION OF BACK-UP AREA</p> <ol style="list-style-type: none">1 Supply, driving, & chipping of PSC sheet piles & corner piles (3,625 l.m.)2 Supply and install tie-rods (86 sets)3 Supply & placing of gravel bedding (14 cu.m.)4 Supply & placing of concrete (550 cu.m.)5 Supply & installation of steel reinforcement (47,338 kg.)6 Supply & placing of rocks (5,076 cu.m.)7 Supply & placing of geotextile fabric (2,295 sq.m.)8 Supply & placing of fill materials (14,673 u.m.)9 Supply & placing of aggregate base course (595 cu.m.)10 Construction of Portland Cement Concrete Pavement (2,976 sq.m.)11 Supply & installation of mooring bollard (11 sets)12 Supply & installation of Rubber dock fenders (20 sets)13 Supply & laying of reinforced concrete pipe (14 l.m.)
APPROVED BUDGET FOR THE CONTRACT	:	Php 149,513,733.91
SOURCES OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	Php 168,950,519.32
PROJECT DURATION	:	450 Calendar days