

**PROJECT FEATURE**

<b>PROJECT TITLE</b>	: <b>RESTORATION OF ROCKBULKHEAD, PASSENGER TERMINAL BUILDING, TMO BUILDING, AND PORT LIGHTING SYSTEM DUE TO TYPHOON KARDING AT PORT OF DINGALAN, AURORA</b>
<b>LOCATION</b>	: <b>Port of Dingalan, Aurora</b>
<b>SCOPE OF WORK</b>	: <b>1.0 General expenses</b> 1.01 Mobilization and Demobilization Cost / Clean-up 1.02 Provide Construction Safety & Health Program in the execution of the project  <b>2.0 Removal and Disposal Works</b> 2.01 Removal and Disposal of debris at Port of Dingalan  <b>3.0 RESTORATION OF MAIN GATE, MOVABLE FENCE AND SLOPE PROTECTION INCLUDING ROCKBULKHEAD</b> 3.01 Supply and place 50-100kg core rocks 3.02 Supply and place 1,000-2,000kg armour rocks 3.03 Supply and place 3 500 psi concrete for pile cap/wave deflector, armour cap, strap beam, deadman block and gate column 3.04 Supply and install steel reinforcement for pile cap/wave deflector, armour cap, strap beam, deadman block and gate column 3.05 Supply, fabricate and install stainless steel gate at Main Entrance Gate including accessories 3.06 Supply, fabricate and install movable steel fence along the deflector wall  <b>4.0 RESTORATION OF TERMINAL MANAGEMENT OFFICE BUILDING</b> 4.01 Supply and install Rib-type roofs and ridged roll incl. removal works 4.02 Supply and install Ceiling at the TMO-Building  <b>5.0 RESTORATION OF PASSENGER TERMINAL BUILDING AND GUARD HOUSE</b> 5.01 Replacement of damaged doors, windows, including accessories of the Passenger Terminal Building and Guard House  <b>6.0 Installation of New Port Lighting and Electrical System</b> 6.01 Supply and Install Solar Integrated 80W LED, 8500lm, daylight, 12.8V Aluminum Street Light SSL-Pro 6.02 Supply and install 1-70W, 6.650lm, daylight 24V LED Street Lights, 2x100W Solar panels. 6.03 Supply and install 1-70W, 5.500lm, daylight 12V LED Street Lights 6.04 Replacement of damaged wires (3-30mm <sup>2</sup> THHN Cu wire) and rusted panel board/circuit breakers of TMO Building 6.05 Replacement of damaged wires (3-80mm <sup>2</sup> THHN Cu + 1-30mm <sup>2</sup> THHN Cu) including accessories from PTB Panel Board to Genset Room 6.06 Replacement of damaged wires (3-100mm <sup>2</sup> THHN Cu + 1-30mm <sup>2</sup> THHN Cu) including accessories from Genset Room to KWHR Pull Box at Main Gate  <b>7.0 Painting Works</b> 7.01 Supply and apply various paint materials on concrete surfaces for repainting of concrete fence and curb 7.02 Supply and apply various paint materials on steel surfaces for painting of movable steel fence 7.03 Supply and apply various paint material for repainting of ceiling at the TMO Building (2 coats)
<b>APPROVED BUDGET FOR THE CONTRACT</b>	: <b>Php 13,017,772.30</b>
<b>SOURCE OF FUNDING</b>	: <b>PPA Corporate Fund</b>
<b>TOTAL PROJECT COST</b>	: <b>Php 14,514,816.11</b>
<b>PROJECT DURATION</b>	: <b>146 Calendar Days</b>