

PROJECT FEATURE**PROJECT TITLE****CONSTRUCTION OF PORT OPERATIONAL AREA WITH CONTINUOUS RORO RAMP AND FASTCRAFT BERTH****LOCATION****Port of Getafe, Bohol****: A. PORT OPERATIONAL AREA, CONTINUOUS RAMP AND FASTCRAFT BERTH**

- 1 Chip-off existing slotted RC curb and smoothen with mortar (38 l.m.)
- 2 Remove existing covered walk and turn-over to Authority (33 l.m.)
- 3 Remove existing mooring bollard and turn-over to Authority (1 set)
- 4 Excavation of existing seabed (22,166 cu.m.)
- 5 Supply and drive 0.35m x 0.60m PSC sheet piles & RC corner piles (7,829 l.m.)
- 6 Chip/cut and dispose portion of newly driven PSC Piles and RC corner piles up to required elevation (355 no.)
- 7 Supply and drive 0.40m x 0.40m PSC piles (5,125 l.m.)
- 8 Chip/cut and dispose portion of newly driven PSC square piles up to required elevation (197 no.)
- 9 Supply and placing of 3,500 psi concrete (859 cu.m.)
- 10 Supply and installation of steel reinforcement (67,323 kg.)
- 11 Supply and installation of pre-cast concrete blocks (15 no.)
- 12 Supply and placing of 50 to 1,000 kg/pc rocks (18,383 cu.m.)
- 13 Supply and installation of Tie-rods (104 sets)
- 14 Supply and placing of geotextile fabric filter (5,001 sq.m.)
- 15 Supply and placing of fill materials (71,756 cu.m.)
- 16 Supply, spread and compact aggregate base course (1,681 cu.m.)
- 17 Excavation of fill materials for lamp post foundation, floodlight foundation, duct bank and handhole (37 cu.m)
- 18 Supply, place and compact gravel bedding for retaining wall, anchor wall, RC ditch, lateral drain, catch drain manhole and handhole (52 cu.m.)
- 19 Supply, spread and compact cement treated base course (1,227 cu.m.)
- 20 Supply, spread and compact levelling course sand cushion (409 cu.m.)
- 21 Supply and installation of Interlocking Concrete Paving Blocks (8,183 sq.m.)
- 22 Construct portland cement concrete pavement (300mm thk) including dowel bars and construction joint (2,090 sq.m.)
- 23 Construct security fence with barbed wire including accessories (92 l.m.)
- 24 Supply and installation of RDF, V500H x 1,500L (20 set)
- 25 Supply and installation of RDF, V300H x 2,500L (10 set)
- 26 Supply and installation of mooring bollard, 35 Tons, T-head (6 set)
- 27 Supply and installation of mooring bollard, 15 Tons, T-head (5 set)
- 28 Supply and installation of mooring cleats (5 set)
- 29 Construct covered walkway (1 lot)
- 30 Construct CHB fence with Ga. cyclone wire and barbed wire including accessories (92 l.m.)
- 31 Supply, fabricate and install Dia. 50mm stainless steel railings (75 l.m.)
- 32 Construct port lighting system including all appurtenances (1 lot)

APPROVED BUDGET FOR THE CONTRACT :**Php****465,079,912.22****SOURCES OF FUNDING :****PPA Corporate Fund****TOTAL PROJECT COST :****Php****525,540,300.81****PROJECT DURATION :****660 Calendar Days**