

PROJECT FEATURE

PROJECT TITLE	:	PROPOSED RC PIER EXTENSION
LOCATION	:	Port of San Jose, Caminawit, San Jose, Occidental Mindoro
SCOPE OF WORK	:	A. RC PIER EXTENSION (Area = 75m x 12m = 900 sq.m.) <ol style="list-style-type: none"> 1 Chip-off portion of existing RC curb (12 l.m.) 2 Supply and drive A252 Grade 2, 500mmØ x 10mm thk. Steel Pipe Piles (404 m.t.- 3,346 l.m.) including application of polyurethane external coating (1,786 sq.m.), installation of reinforcing band tip (94 pcs), splicing (94 pcs) and cutting (94 pcs) 3 Supply and place 3,500 psi concrete filler (240 cu.m.) and reinforcing steel cage (68,523 kgs of various sizes) for steel pipe piles including extraction of clogged materials (51 cu.m.) 4 Supply and place 3,500 psi concrete (471 cu.m.) and reinforcing steel bars (71,131 kg of various sizes) for superstructure 5 Supply and install construction joints 100mm x 100mm x 10mm angle bar (12 l.m.) and BWT 175x38 (12 l.m.) 6 Supply and install of Rubber Dock Fenders (V500 x 1500L - 18 sets) and Mooring Bollard, (35-Tons, T-head - 18 sets)
APPROVED BUDGET FOR THE CONTRACT	:	Php 86,869,006.29
SOURCES OF FUNDING	:	PPA Corporate Fund
TOTAL PROJECT COST	:	Php 98,161,977.11
PROJECT DURATION	:	360 Calendar Days

