

PROJECT FEATURE

PROJECT TITLE	:	IMPROVEMENT OF EXISTING ROCK CAUSEWAY	
LOCATION	:	Port of San Roque, Daram, Samar	
SCOPE OF WORK	:	A. ROCK CAUSEWAY WITH STAIRLANDING <ol style="list-style-type: none">1 Removal of existing electrical steel post (2 cu.m.)2 Removal and disposal of existing pavement (20 sq.m.)3 Excavation of existing seabed along the containment of stairlandings (3 cu.m.)4 Supply and place 500 kg./pc. armour rocks (858 cu.m.)5 Supply and place 50-100 kg./pc. core rocks (648 cu.m.)6 Supply and install geotextile fabric (208 sq.m.)7 Supply, spread and compact selected fill (29 cu.m.)8 Supply and place 3,500 psi. concrete for retaining wall, stairlanding, mooring lock, and RC curb (89 cu.m.)9 Supply and install steel reinforcement for retaining wall, stairlanding, mooring block, and RC curb (4,866 kg.)10 Supply, spread and compact gravel base course (26 cu.m.)11 Construct portland cement concrete pavement (230mm thk.) including asphalt sealer and dowel bars for construction joint (185 sq.m.)12 Supply and install mooring cleat including accessories (6 no.)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	9,230,982.40
SOURCES OF FUNDING	:	GAA	
TOTAL PROJECT COST	:	Php	9,969,460.99
PROJECT DURATION	:	180 Calendar Days	