

PROJECT FEATURE

PROJECT TITLE : **CONSTRUCTION OF BACK-UP AREA**

LOCATION : **Port of Getafe, Bohol**

SCOPE OF WORK : **A. BACK-UP AREA**

- 1 Demolition & disposal of existing concrete pavement (299 sq.m)
- 2 Excavation of existing seabed (11,568 cu.m.)
- 3 Excavation of existing fill materials (60 cu.m.)
- 4 Supply & placing of concrete (541 cu.m.)
- 5 Supply & installation of steel reinforcement (56,864 kg.)
- 6 Supply & installation of concrete blocks (229 cu.m.)
- 7 Supply, driving & chipping of PSC Sheet piles & corner piles (6,594 l.m.)
- 9 Supply & installation of core rocks (11,178 cu.m.)
- 10 Supply & placing of fill materials (21,674 cu.m.)
- 11 Supply & placing of aggregate base course (61 cu.m.)
- 12 Construction of Portland Cement Concrete Pavement (299 sq.m.)
- 13 Supply & installation of Tie-rods (90 sets)
- 14 Supply & installation of rubber dock fenders & mooring bollards (21 sets)
- 15 Construction of Security Fence (45 l.m.)

APPROVED BUDGET FOR THE CONTRACT	:	Php	163,296,490.50
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	184,525,034.27
PROJECT DURATION	:	360 Calendar Days	