

PROJECT FEATURE

PROJECT TITLE : **JORDAN PORT EXPANSION PROJECT**

LOCATION : **Port of Jordan, Brgy. Hoskyn, Jordan, Guimaras**

SCOPE OF WORK :

- A. REMOVAL AND EXCAVATION WORKS**
 - 1 Chipping and disposal of existing R.C. Curb
 - 2 Removal of existing mooring bollard
 - 3 Removal and disposal of existing RC deck
 - 4 Removal and disposal of existing CHB fence
 - 5 Chipping and disposal of existing PSC Piles
 - 6 Excavation and backfilling of existing fill materials
 - 7 Excavation of existing seabed
 - 8 Removal and re-installation of existing floodlight and solar lamp post
- B. CONSTRUCTION OF PORT OPERATIONAL AREA**
 - 1 Supply & driving of Z-type Steel sheet pile
 - 2 Supply & installation of dowel bars for Steel sheet piles
 - 3 Handling, pitching & driving of Steel Sheet piles
 - 4 Supply & installation of steel waling and splice plate
 - 5 Cutting & disposal of newly driven Steel sheet piles
 - 6 Supply & driving of Steel Pipe pile
 - 7 Handling, pitching & driving of Steel Pipe piles
 - 8 Supply, fabricate & install band tip for the steel pipe piles
 - 9 Cutting & disposal of newly driven Steel Pipe piles
 - 10 Extraction of clogged materials inside the SPP
 - 11 Supply & placing of sand filler for SPP
 - 12 Supply & placing of concrete filler for SPP
 - 13 Supply & installation of reinforcing steel cage for SPP
 - 14 Supply & placing of 3,500 psi concrete
 - 15 Supply & installation of reinforcing steel bars
 - 16 Supply & placing of gravel bedding
 - 17 Supply & placing of 50 to 1,000 kg. rocks
 - 18 Supply & placing of Sacked concrete
 - 19 Supply & placing of leveling rocks
 - 20 Supply & placing of Concrete blocks
 - 21 Supply & installation of Tie-rod
 - 22 Supply & installation of geotextile fabric
 - 23 Supply & placing of fill materials
 - 24 Construction of PCC Pavement including Agg. Base Course
 - 25 Construction of security fence
 - 26 Portlighting system
 - 27 Drainage system
 - 28 Supply & installation of Rubber dock fenders
 - 29 Supply & installation of mooring bollards
- C. CONSTRUCTION / UPGRADING OF R.C. WHARF & RORO RAMP**
 - 1 Supply & driving of Steel Pipe pile
 - 2 Handling, pitching & driving of Steel Pipe piles
 - 3 Supply, fabricate and install band tip for the steel pipe piles
 - 4 Cutting & disposal of newly driven Steel Pipe piles
 - 5 Extraction of clogged materials inside the SPP
 - 6 Supply & placing of concrete filler for SPP
 - 7 Supply & installation of reinforcing steel cage for SPP
 - 8 Supply & placing of 3,500 psi. concrete for the superstructure
 - 9 Supply & installation of reinf. steel bar for the superstructure
 - 10 Supply & installation of construction joints
 - 11 Supply & installation of Rubber dock fenders
 - 12 Supply & installation of mooring bollards
- 5 CONSTRUCTION OF PASSENGER SHED**
 - 1 Supply, delivery & installation of PTFE Fabric membrane, including framings, columns, electrical materials, foundation & other accessories

APPROVED BUDGET FOR THE CONTRACT : **Php 360,801,962.62** ✓

SOURCES OF FUNDING : **PPA Corporate Fund**

TOTAL PROJECT COST : **Php 407,706,217.76** ✓

PROJECT DURATION : **660 Calendar Days**