

PROJECT FEATURE

PROJECT TITLE	:	CAWAYAN PORT IMPROVEMENT PROJECT	
LOCATION	:	Port of Cawayan, Masbate	
SCOPE OF WORK	:	<p>A. DEMOLITION & REMOVAL WORKS</p> <ol style="list-style-type: none">1 Demolition & disposal of existing wooden structures (10 sq.m.)2 Removal of existin mooring cleats (4 sets)3 Chipping portion of existing RC curb (58 l.m.)4 Chipping existing Deflector wall (204 l.m.)5 Demolition & disposal of existing concrte pavement (867 sq.m.) <p>B. BACK-UP AREA & CAUSEWAY</p> <ol style="list-style-type: none">1 Sub-grade preparation (1,007 sq.m.)2 Scrapping of existing gravel materials (3,086 cu.m.)3 Excavation of existing seabed (103 cu.m.)4 Supply & placing of 3,500 psi concrete (473 cu.m.)5 Supply & installation of steel reinforcement (24,115 kg.)6 Supply & placing of 50 to 2,000 kg/pc rocks (10,883 cu.m.)7 Supply & installation of Tie-rods (4 sets)8 Suppy & placing of Geotextile fabric filter (3,403 s.m.)9 Supply & placing of fill materials (16.986 cu.m.)10 Construction of Portland cement concrete pavement (6.999 sq.m.)11 Re-installation of old mooring cleats (4 sets)12 Construction of Perimeter security fence & gate (147 l.m.) <p>C. PORT OPERATIONS BUILDING, PUMPHOUSE & GUARDHOUSE</p> <ol style="list-style-type: none">1 Supply and driving of 450 x 450mm PSC foundation piles (270 l.m.)2 Construction of 1-storey Port Operations Building, (672.54 sq.m.) complete3 Construction of Pumphouse & apurtenances (12.24 sq.m.)4 Construction of Guardhouse & apurtenances (5.33 sq.m.)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	149,138,830.31
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	168,526,878.25
PROJECT DURATION	:	450 Calendar Days	