

PROJECT FEATURE

PROJECT TITLE	:	CONST. OF PORT OPERATIONS BUILDING & RORO RAMP	
LOCATION	:	Port of Maasin, Southern Leyte	
SCOPE OF WORK	:	A. DEMOLITION & REMOVAL WORKS 1 Demolition and disposal of existing concrete pavement (1,046 sq.m.) 2 Chipping and disposal of existing R.C. Curb (11 l.m.) 3 Scraping of existing gravel base materials (1,046 cu.m.) B. CONST. OF PORT OPERATIONS BUILDING 1 Supply and driving of 400 x 400mm PSC foundation piles (360 l.m.) 2 Construction of 1-storey Port Operations Building (625 sq.m., 250 pax) 3 Construction of Pumphouse (12.24 sq.m.) 4 Construction of 300mm thk. Concrete Pavement (421 sq.m.) 5 Construction of R.C. Ductbank, handhole & pedestal (33 cu.m.) 6 Supply, delivery, installation of gang chairs (1 lot) C. CONST. OF RORO RAMP 1 Supply, driving and chipping of 400 x 400mm PSC foundation piles (558 l.m.) 2 Supply and placing of 3500 psi concrete (68 cu.m.) 3 Supply and installation of steel reinforcement bar (15,609 kgs.) 4 Supply and installation of rubber dock fender (V-type) (3 sets.)	
APPROVED BUDGET FOR THE CONTRACT	:	Php	48,544,352.27
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	54,855,118.07
PROJECT DURATION	:	420 Calendar Days	

9/6/12

8

15