



PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Iloilo Clustered Project I
ICPC, Fort San Pedro, Ports of Dumangas, Iloilo and
Jordan, Guimaras

LOCATION : Province of Iloilo and Guimaras

MAJOR SCOPE OF WORK : 1) Dredging along berths and maneuvering areas of the
Ports to a designed depth below Mean Lower Low
Water (MLLW) as follows:
12.50m, 10.50m and 5.00m. for ICPC
7.00 m for Fort San Pedro
6.00 m for Dumangas Port
6.00m and 4.50m for Jordan Port

2) Total Volume to be Dredged : 190,000 cu.m.
(55,000 cu.m., 20,000 cu.m., 60,000 cu.m. and 55,000 cu.m.
for ICPC, Fort San Pedro, Ports of Dumangas and Jordan,
respectively) of soft to highly dense (compacted) clayish
sand/mud, silt, sand, pebbles and possible hard materials.

3) Disposal of dredged soil materials 16.00 kms
away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 99,481,556.20

TOTAL PROJECT COST : P 101,968,595.11

PROJECT (DREDGING) UNIT COST : P 495.41 per cubic meter
(Dredging Works Only, excluding General Expenses
and Re-imbursable Items)

PROJECT DURATION : 274 calendar days
(inclusive of Sundays / Holidays and unworkable
condition)