

PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Ports of Brooke's Point, Balabac and Cuyo, Palawan

LOCATION : Municipalities of Brooke's Point, Balabac and Cuyo, Palawan

MAJOR SCOPE OF WORK : 1) Dredging along berths and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:  
6.00 m. for Brooke's Point Port  
4.50 m for Balabac Port  
6.00 m. for Cuyo Port

2) Total Volume to be Dredged : 187,000 cu.m. (72,000 cu.m., 30,000 cu.m. and 85,000 cu.m., respectively) of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials such as pulverized and granulized corals, gravel and rocks.

3) Disposal of dredged soil materials 16.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 99,710,499.03

TOTAL PROJECT COST : P 102,203,261.50

PROJECT (DREDGING) UNIT COST : P 496.79 per cubic meter  
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 276 calendar days  
(inclusive of Sundays / Holidays and unworkable condition)