



PROJECT FEATURE

PROJECT TITLE : Proposed Dredging of Pulupandan and Himamaylan Ports

LOCATION : Negros Occidental

MAJOR SCOPE OF WORK :

- 1) Dredging along berths, approaches and maneuvering areas of the Ports to a designed depth below Mean Lower Low Water (MLLW) as follows:
6.0, 9.0 and 12.0 meter @ Pulupandan Port
5.0 meter @ Himamaylan Port
- 2) Total Volume to be Dredged : 543,000 cu.m.
(425,000 cu.m. and 118,000 cu.m. for Pulupandan and Himamaylan Ports, respectively of loose to medium dense clayish soil, mud, silt and sand with possible compacted/hard materials
- 3) Disposal of dredged soil materials 15.00 kms away from the project site

APPROVED BUDGET FOR THE CONTRACT : P 255,077,828.21

TOTAL PROJECT COST : P 261,454,773.92

PROJECT (DREDGING) UNIT COST : P 453.88 per cubic meter
(Dredging Works Only, excluding General Expenses and Re-Imbursable Items)

PROJECT DURATION : 681 calendar days
(inclusive of Sundays / Holidays and unworkable condition)