



## PROJECT FEATURE

**PROJECT TITLE** : Proposed Dredging of Tacloban Port  
(From Berth to Approach)

**LOCATION** : Tacloban City, Leyte

**MAJOR SCOPE OF WORK** :

- 1) Dredging along berths, maneuvering areas and approach of the port to respective designed depth of 10.00 meter below Mean Lower Low Water (MLLW)
- 2) Total Volume to be Dredged : 443,000 cu.m. of soft to medium dense clayish soil, mud, silt and sand
- 3) Disposal of dredged soil materials 15.00 kms away from the project site

**APPROVED BUDGET FOR THE CONTRACT** : P 208,606,050.19

**TOTAL PROJECT COST** : P 213,821,201.44

**PROJECT (DREDGING) UNIT COST** : P 453.22 per cubic meter  
(Dredging Works Only, excluding General Expenses and Re-imbursable Items)

**PROJECT DURATION** : 562 calendar days  
(inclusive of Sundays / Holidays and unworkable condition)