

PROJECT FEATURE

PROJECT TITLE	:	IMPROVEMENT/EXPANSION OF EXISTING PORT OPERATIONAL AREA AND CONSTRUCTION OF TERMINAL MANAGEMENT OFFICE, PASSENGER SHED, PUMPHOUSE, POWERHOUSE AND GUARD HOUSE	
LOCATION	:	Port of San Juan, San Juan, Southern Leyte	
	:	A. IMPROVEMENT/EXPANSION OF EXISTING PORT OPERATIONAL AREA Area = 1,303.06 sq.m. <ol style="list-style-type: none"> Scrape/cut and dispose existing materials including subgrade preparation (502 sq.m.) Demolition, chipping, removal & disposal works: <ol style="list-style-type: none"> Existing R.C. Curb (33 l.m.) Existing concrete pavement(502 sq.m..) Existing rc deck (231 sq.m.) Chipping/cutting of existing concrete piles (25 pcs.) Existing mooring bollard to be removed and turn-over to authority(1 pc.) Supply, delivery, driving, cutting of PSC sheet piles including corner piles (1,272 l.m.) Supply and installation of 50mm dia. tie rod of various length (29 sets) Supply & placing of 3,500 psi concrete for retaining walls, etc. (212 cu.m.) Supply & installation of steel reinforcement for retaining walls, etc. (21,320 kg.) Supply & placing of Rocks (2,534 cu.m.) Supply & installation of geotextile fabric (877 sq.m.) Supply, placing and compaction of sand and gravel fill, agg. sub-base, base course and gravel bedding (4,083 cu.m.) Construction of portland cement concrete pavement (1,303 sq.m.) Construction of chb fence including various materials (86 sq.m.) Supply, delivery and installation of mooring bollard (1 pc) Supply, delivery and erection of floodlight pole for port lighting system (1 pc) 	
	:	B. CONSTRUCTION OF TERMINAL MANAGEMENT OFFICE, PASSENGER SHED, PUMPHOUSE, POWERHOUSE AND GUARD HOUSE Area = 202.52 sq.m. <ol style="list-style-type: none"> Construction of Terminal Management Office (40.53 sq.m.) Construction of Passenger Shed (74.61 sq.m.) Construction of Pumphouse & appurtenances (21.16 sq.m.) Construction of Powerhouse (60.81 sq.m.) Construction of Guard House (5.41 sq.m.) Supply & installation of PPA logo (1 lot) Supply, fabrication and installation of steel gate including accessories (1 lot) Supply, delivery & installation of distribution Transformer & accessories (1 lot) 	
APPROVED BUDGET FOR THE CONTRACT	:	Php	51,256,030.95
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	57,919,314.97
PROJECT DURATION	:	300 Calendar Days	


