

PROJECT FEATURE

PROJECT TITLE	:	CONSTRUCTION OF PORT OPERATIONAL AREA WITH RORO RAMP ✓	
LOCATION	:	Port of Tablas (Poctoy), Odiongan, Romblon ✓	
SCOPE OF WORK	:	A. DEMOLITION, EXCAVATION AND REMOVAL WORKS ✓ 1 Chipping & disposal of existing R.C. Curb (43 l.m.) ✓ 2 Demolition & disposal of existing Roro Ramp & breasting dolphin (207 sq.m.) ✓ 3 Cutting & disposal of existing piles (24 units) ✓ 4 Excavation of existing seabed & fill materials (2,668 cu.m.) ✓ 5 Removal of existing mooring bollard & rubber dock fenders (3 sets) ✓ 6 Demolition & disposal of existing fence (34 l.m.) ✓ 7 Removal of existing lamp post (1 unit) ✓ B. PORT OPERATIONAL AREA WITH RORO RAMP ✓ 1 Supply, delivery & driving of PSC Piles & RC Corner Piles (5,775 l.m.) ✓ 2 Chipping & cutting of newly Driven piles (385 units) ✓ 3 Supply & placing of 3,500 psi concrete for retaining wall, etc. (809 cu.m.) ✓ 4 Supply & installation of steel reinforcement for retaining wall, etc. (82,481 kg.) ✓ 5 Supply & placing of core rocks & armour rocks (8,377 cu.m.) ✓ 6 Supply & installation of Tie-rod of various sizes (148 sets) ✓ 7 Supply & placing of fill materials (38,005 cu.m.) ✓ 8 Construction of PCC Pavement including Agg. Base Course (7,579 sq.m.) ✓ 9 Supply & installation of rubber dock fenders (28 sets) ✓ 10 Supply & installation of Mooring bollard (22 sets) ✓ 11 Construction of Security Fence & gate (1 lot) ✓ 12 Supply & installation of Portlighting system (4 sets) ✓	
APPROVED BUDGET FOR THE CONTRACT	:	Php	247,980,005.98 ✓
SOURCES OF FUNDING	:	PPA Corporate Fund	
TOTAL PROJECT COST	:	Php	280,217,406.76 ✓
PROJECT DURATION	:	540 Calendar Days ✓	

90

mf

8