BASIS OF PAYMENT FOR WORK ITEMS INCLUDED IN THE PROPOSAL

The work items included in the proposal including the basis of payment for each item are as follows:

BILL NO. I-GENERAL EXPENSES

Item 1.01 Mobilization, Demobilization and Cleaning

The quantity to be paid for shall be the actual number of minimum equipment requirement enumerated in the bid documents mobilized and demobilized. The contract lump sum price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to mobilize and demobilize all the minimum equipment requirement enumerated in the bid documents. Fifty percent (50%) of the total amount shall be payable after the mobilization activity while the remaining (50%) payable after demobilization.

Item 1.02 Rental of Temporary Site Office and Residence for the Engineer and Staff

The quantity to be paid for shall be the actual rental of temporary site office and residence for the engineer and staff. The contract unit price shall be full compensation for the provision of site office and residence for the engineer and staff within the duration of the project.

Item 1.03 Maintain Temporary Site Office and Residence for the Engineer and Staff

The quantity to be paid for shall be the actual maintenance cost of rented temporary site office and residence for the engineer and staff. The contract unit price shall be full compensation for the provision of maintenance of the temporary site office and residence of engineer and staff.

Item 1.04 Provide Construction Safety and Health Program in the Execution of the Project

The quantity to be paid for shall be the actual implementation of construction safety and health program and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the implementation of the Construction Safety and Health Program, as required and approved by the Department of Labor and Employment (DOLE).

BILL NO. II – ROCK CAUSEWAY (9M X9M)

Item 2.01 Excavation of Exist Seabed Prior to Construction/Laying of Concrete Block Footing

The quantity to be paid for shall be the actual volume in cubic meter of excavation of exist seabed to be supplied and laying of concrete block for footing in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.02 Supply and Place Concrete Block for Footing

The quantity to be paid for shall be the actual volume in cubic meter of concrete block to be supplied and placed for footing in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.03 Supply and Install Steel Reinforcement for Item 2.02

The quantity to be paid for shall be the actual weight in kilograms of supplied and installed reinforcing bars for Item 2.02 in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.04 Supply, Spread and Compact Selected Granular Fill

The quantity to be paid for shall be the actual volume in cubic meter of selected granular fill to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.05 Supply, Spread and Compact Aggregate Sub-Base Course 20MM Thick

The quantity to be paid for shall be the actual volume in cubic meter of aggregate to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.06 Supply, Spread & Compact Aggregate Base Course (20mm thick)

The quantity to be paid for shall be the actual volume in cubic meter of aggregate base course (20mm thick) to be supplied, spread and compacted in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.07 Supply and Place 3,500 PSI Concrete Pavement (25mm Thick) Including Approach

The quantity to be paid for shall be the actual volume in cubic meter of supplied and placed (3,500 psi) concrete pavement (25mm thick) and including approach in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.08 Supply and Install Steel Reinforcement for Item 2.07

The quantity to be paid for shall be the actual weight in kilograms of supplied and installed reinforcing bars for Item 2.07 in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.09 Supply and Place 3,500 PSI Concrete Slope Protection, R.C. Curb Wave Deflector and Stair Landing

The quantity to be paid for shall be the actual weight in cubic meter of supplied and place (3,500 PSI) Concrete slope protection in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.10 Supply and Install Steel Reinforcement for Item 2.09

The quantity to be paid for shall be the actual weight in kilograms of supplied and installed reinforcing bars for item 2.09 in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.11 Supply and Deliver to Site Mooring Cleats (5T) Including Accessories

The quantity to be paid for shall be the actual number/set of supplied and delivered to site mooring cleats (5T) including accessories in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.12 Install Mooring Cleats (5T) Including Accessories

The quantity to be paid for shall be the actual number/set of installed mooring cleats (5T) including accessories in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

BILL NO. III – BOX CULVERT

Item 3.01 Excavation of Existing Seabed prior to the Construction of Retaining Wall

The quantity to be paid for shall be the actual volume in cubic meter of existing seabed to be excavated prior to the construction of retaining wall in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 3.02 Supply and Install Reinforcement for Retaining Wall

The quantity to be paid for shall be the actual weight in kilograms of supplied and installed reinforcing bars for retaining wall in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 3.03 Supply and Place 3,500 PSI Concrete for RC Columns, Beams and Slab

The quantity to be paid for shall be the actual volume in cubic meter of supplied and placed (3,500 psi) concrete for RC columns, beams and slab in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.