BASIS OF PAYMENT FOR WORK ITEMS INCLUDED IN THE PROPOSAL

The work items included in the proposal including the basis of payment for each item are as follows:

BILL NO. 1 – GENERAL EXPENSES

Item 1.01 Mobilization and Demobilization

The quantity to be paid for shall be the actual number of minimum equipment requirement enumerated in the bid documents mobilized and demobilized. The contract lump sum price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to mobilize and demobilize all the minimum equipment requirement enumerated in the bid documents. Fifty percent (50%) of the total amount shall be payable after the mobilization activity while the remaining (50%) payable after demobilization.

Item 1.02 Provide Safety and Health Programs in the Execution of the Project

The quantity to be paid for shall be the actual implementation of safety and health program and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals necessary to complete the implementation of the Construction Safety and Health Program, as required and approved by the Department of Labor and Employment (DOLE).

BILL NO. II – FENDERING SYSTEM

Item 2.01 Removal of Damaged Rubber Dock Fenders

The quantity to be paid for shall be the actual number/set of damaged Rubber Dock Fenders to be removed in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.02 Supply of Rubber Dock Fenders V-Type 400 x 1000L including Accessories

The quantity to be paid for shall be the actual number/set of Rubber Dock Fenders V-Type 400 x 1000L including accessories to be supplied to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.

Item 2.02 Install Rubber Dock Fenders V-Type 400 x 1000L including Accessories

The quantity to be paid for shall be the actual number/set of Rubber Dock Fenders V-Type 400 x 1000L including accessories to be installed to site in accordance with the plans and specifications and accepted by the Engineer. The contract unit price shall be full compensation for furnishing all materials, labor, equipment, tools and incidentals expenses necessary to complete the work.