BILL OF QUANTITIES

Project Title : UNDER DECK REPAIR (RETROFITTING) OF ICPC (NORTHERN END)

Project Location : Iloilo Commercial Port Complex, Iloilo City

Item No.	DECSRIPTION	UNIT	QUANTITY	UNIT COST	AMOUNT
1.00	Mobilization/Demobilization	lot	1.00		
2.00	General Expenses	lot	1.00		
3.00	Chipping Works	Sq.m.	957.22		
4.00	Removal/Treatment of Spalled Concrete				
4.01	Supply and Apply Epoxy Mortar including Placing of Cement Plaster to Replace Spalled/Damaged Concrete	Gal.set	358.00		
4.02	Supply and Apply Structural Epoxy on Cracked and Slightly Damaged/Spalled Concrete	Gal.set	314.00		
4.03	Supply and Apply Epoxy Bonding Agent (Concrete Adhesive) to Damaged/Spalled Concrete and Exposed Rebars	Sq.m.	159.63		
4.04	Supply and Replace Severely Damaged Concrete (Scheme 2)	Cu.m.	53.33		
5.00	Treatment of Steel Surfaces	Sq.m.	957.22		
6.00	Removal/Replacement of Damaged/Exposed Steel Reinforcements	Kgs	9,065.92		
7.00	Retrofitting Works (Supply and Apply Two Layers of Glass Fiber with Saturated Epoxy to Surfaces Above Water)	Sq.m.	6,170.69		
8.00	Painting Works	Sq.m.	2,828.00		
TOTAL					