

Project: **Repair of Safety & Security Signages**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	Safety and Security Signages with Street Stand	90.00	sets		
	Work Description				
	Repair and Fabrication of Signage Steel Stand				
	Materials				
	2"Ø x 6.0m G.I. Pipe (2.6mm)	23.00	lhs.		
	2" x 2" x 6m Angle Bar	54.00	lhs.		
	1" x 1" x 6m Angle Bar	75.00	lhs.		
	1/4" x 2" x 6m Flat Bar	13.00	lhs.		
	0.9m x 1.2m Ga.22 Plain G.I. Sheet	23.00	shts.		
	Red Oxide Primer	6.00	gal		
	Aluminum Paint	6.00	gal		
	Welding Rod	71.00	kgs.		
	Hacksaw Blade	30.00	pcs.		
	Rugby cement	5.00	gal		
	Tarpuline (2":x3")	90.00	sets		
	Paint thinner	1.00	gal		
	Paint Brush	8.00	pcs.		
	Equipment				
	2 Welding Machime	23.00	days		
	2 Electric Grinder	23.00	days		
	Manpower				
	2 Welder	23.00	days		
	1 Painter	23.00	days		
	2 Helper	23.00	days		
	ESTIMATED DIRECT COST			P	
	ESTIMATED INDIRECT COST			P	
	TOTAL COST OF WORK ITEM I.			P	

2.0 **Lighted Panaflex Signages for Port Gates** 43.79 sq.m.

Work Description
Work includes the repair/fabrication/installation of port signages frames, removal of old panaflex and supply including installation of new lighted panaflex.

Materials

LIGHTED PANAFLEX SIGNAGE (with frame) :

1.22m x 6.26 Panaflex (Gate 1A), Single face	1.00	sets	
1.22m x 3.66 Panaflex (Gate 1B), Single face	1.00	sets	
1.22m x 3.66 Panaflex (Gate 1C), Single face	1.00	sets	
1.20m x 3.00 Panaflex (Gate 2), Single face	1.00	sets	
1.33m x 2.00 Panaflex (Gate 3), Double face	1.00	sets	
1.00m x 4.50 Panaflex (Gate 4 ACC), Single face	1.00	sets	
1.22m x 3.66 Panaflex (Gate 5), Single face	1.00	sets	
3.00m x 4.00 Tarpaulin signage w/ double framing and cut-out stickers letters	1.00	sets	

Equipment
Manpower

1 Installer	5.00 days	<div></div>	<div></div>
2 Helper	5.00 days	<div></div>	<div></div>

ESTIMATED DIRECT COST	P	<div></div>
ESTIMATED INDIRECT COST	P	<div></div>
TOTAL COST OF WORK ITEM II.	P	<div></div>

AMOUNT IN WORDS :

TOTAL PROJECT COSTP