

Republic of the Philippines
PHILIPPINE PORTS AUTHORITY
 PORT MANAGEMENT OFFICE – SURIGAO
 Port Area, Surigao City

INVITATION TO BID

The Philippine Ports Authority (PPA), Port Management Office of Surigao, through its Bids and Awards Committee (BAC) for Procurement of Goods and Consultancy Services and for Engineering Projects, invites contractors registered with and classified by the Philippine Contractors Accreditation Board (PCAB) to bid for the hereunder contract:

- A. Name of Contract : **REPAIR OF GATE NO. 5 ALONG P. REYES STREET**
 B. Project Code : NRP-SUR-01-19
 C. Location : Port of Surigao, Surigao City
 D. Brief Description :

1. GENERAL EXPENSES

- 1.1 Mobilization / Demobilization - 1.00 l.s.
 1.2 Provide Safety and Health Program - 6.00 mos.

2. DEMOLITION / REMOVAL WORKS

- 2.1 Remove and Store Electronic Barrier - 2.00 units
 2.2 Remove and Store CCTV Electronics - 1.00 lot
 2.3 Demolish, Remove and Dispose Existing Dilapidated Gate 5 - 1.00 lot
 2.4 Demolish and Dispose Existing Dilapidated Concrete Perimeter Fence - 1.00 lot
 2.5 Remove and Store Existing Manhole Steel Cover And Reinforced Concrete Drainage Cover - 1.00 lot
 2.6 Demolish, Remove & Dispose Existing Concrete Pavement - 403.99 sq.m.
 2.7 Remove and Relocate Solar Light Post - 3.00 units

3. SUPPLY, SPREAD AND COMPACT FILLER MATERIAL

- 40.00 cu.m.

4. PORTLAND CEMENT CONCRETE PAVEMENT

- 403.99sq.m.

5. SUPPLY AND INSTALL TIE BARS AND DOWEL BARS

- 1,083.15 kgs.

6. REPAIR OF GATE 5

- 6.1 Concreting Works
 6.1.1 Reinforced Concrete - 77.93 cu.m.
 6.1.2 Supply & Install Reinforcements - 9,450.32 kgs.
 6.2 Carpentry Works
 6.2.1 Ceiling - 13.11 sq.m.
 6.2.2 Wooden Cabinets - 3.00 units
 6.3 Masonry Works
 6.3.1 150mm thk CHB - 50.47 sq.m.
 6.3.2 Plastering - 75.41 sq.m.
 6.4 Formworks and Falsework - 1 lot
 6.5 Welding Works - 80.50 sq.m.
 6.6 Roofing Works - 98.55 sq.m.
 6.7 Doors & Windows
 6.7.1 Supply and Install Door 1 (D1) - 1.00 unit
 6.7.2 Supply and Install Door 2 (D2) - 1.00 unit
 6.7.3 Supply and Install Window 1 (W1) - 2.00 units
 6.7.4 Supply and Install Window 2 (W2) - 4.43 sq.m.
 6.7.5 Supply and Install Window 3 (W3) - 1.50 sq.m.
 6.8 Finishes
 6.8.1 Supply and Install 400mm x 400mm Ceramic Unglazed Floor Tiles - 15.34 sq.m.
 6.8.2 Supply and Install 76mm x 260mm Standard Bricks - 42.84 sq.m.
 6.8.3 Supply and Install 400m x 400mm Decorative Tiles (False Column) - 36.22 sq.m.
 6.8.4 Supply and Install 400mm x 400mm Wall Tiles - 12.32 sq.m.
 6.8.5 Supply, Fabricate and Install 4.5mm thk. Hot-dipped Cut-off Metal Sheet - 1.00 lot

Republic of the Philippines
PHILIPPINE PORTS AUTHORITY
 PORT MANAGEMENT OFFICE – SURIGAO
 Port Area, Surigao City

6.8.6 Supply, Fabricate and Install Decorative Signages	-	2.00 units
6.9 Supply, Fabricate and Install Steel Door Gate	-	2.00 units
6.10 Supply and Install Electronic Barrier w/ complete Accessories	-	2.00 units
6.11 Plumbing Works		
6.11.1 Wall Mounted Lavatory Sink	-	1.00 assy.
6.11.2 Standard Urinal Set	-	1.00 assy.
6.11.3 Stainless Strainer	-	1.00 set
6.11.4 Water Supply Line	-	45.00 l.m.
6.11.5 Sanitary / Sewerage Line	-	68.00 l.m.
6.12 Electrical Works		
6.12.1 Supply and Install Electrical Wirings		
6.12.1.1 2.0 sq.mm THW Stranded Wire	-	180.00 l.m.
6.12.1.2 5.5 sq.mm THW Stranded Wire	-	350.00 l.m.
6.12.1.3 8.0 sq.mm THW Stranded Wire	-	150.00 l.m.
6.12.2 Supply and Install Conduit Pipes		
6.12.2.1 ½"dia. Corrugated Flexible U-PVC Electrical Pipe	-	180.00 l.m.
6.12.2.2 ½"dia. U-PVC Electrical Pipe	-	350.00 l.m.
6.12.2.3 2"dia. U-PVC Electrical Pipe	-	150.00 l.m.
6.12.3 Supply and Install Wiring Devices		
6.12.3.1 2" x 4" U-PVC Utility Box w/ cover	-	10.00 pcs.
6.12.3.2 4" x 4" U-PVC Junction Box w/ cover	-	15.00 pcs.
6.12.3.3 Two Gang Flush Type Switch	-	4.00 sets
6.12.3.4 One Gang Flush Type Switch	-	1.00 sets
6.12.3.5 Two Gang Flush type Convenience Outlet	-	5.00 sets
6.12.4 Supply and Install Lighting Fixtures		
6.12.4.1 23 watts, 4"dia. Pin Light	-	3.00 assy.
6.12.4.2 20 watts, Led Spot Light	-	4.00 assy.
6.12.4.3 20 watts Led Wall Lamp	-	6.00 sets
6.12.4.4 100 watts Led Flood Light	-	2.00 sets
6.12.5 Supply and Install Panel Board		
6.12.5.1 Six Branches Center-Head Main Circuit Breaker Panel Board, 2P	-	1.00 set
6.13 Painting Works		
6.13.1 Metal Surfaces Aluminum Paint Finish	-	80.50 sq.m.
6.13.2 Masonry / Concrete Surfaces	-	378.54 sq.m.
6.13.3 Wooden Surfaces	-	1.00 lot
7. CONSTRUCTION OF PERIMETER FENCE		
7.1 Concreting Works		
7.1.1 Reinforced Concrete (Foundation / Slab / Columns / Beams)	-	27.29 cu.m.
7.1.2 Supply and Install Reinforcements	-	3,631.44 kgs.
7.2 Masonry Works		
7.2.1 100mm thk. CHB wall	-	103.84 sq.m.
7.2.2 150mm thk. CHB wall	-	123.52 sq.m.
7.2.3 Plastering / Cornering / Moulding	-	471.54 sq.m.
7.2.4 Lean Concrete	-	1.25 cu.m.
7.2.5 Sacaffolding Works (Perimeter Fence)	-	350.00 bd.ft.
7.3 Supply, Fabricate and Install Steel Pipe Post Pedestal	-	26.00 units
7.4 Supply and Install 18watts Globe Light	-	16.00 units
7.5 Painting Works (Masonry / Concrete Surfaces)	-	565.20 sq.m.
8. SUPPLY AND INSTALL CABLE PROTECTION		
8.1 ½"dia. Corrugated Flexible U-PVC Electrical Pipe	-	350.00 m.
9. REPAIR OF DRAINAGE CANAL		
9.1 Concreting Works		
9.1.1 Reinforced Concrete (Box Culvert)	-	2.50 cu.m.
9.1.2 Supply and Install Reinforcements	-	2,420.96 kgs.

Republic of the Philippines
PHILIPPINE PORTS AUTHORITY
 PORT MANAGEMENT OFFICE – SURIGAO
 Port Area, Surigao City

10. LANDSCAPING WORKS

10.1 Supply and Spread Garden Soil	-	3.00 cu.m.
10.2 Supply and Place Ornamental Plants	-	1.00 lot

E. Required Equipment:

1 – unit	Backhoe with Breaker (owned)
1 – unit	Concrete Saw Gasoline Self Propelled (owned)
1 – unit	Backhoe (90 hp Capacity) (owned)
1 – unit	Dumptruck (10.0 cu.m.) (owned)
1 – unit	Oxy-Acetylene Cutting Outfit (owned)
1 – unit	Boomtruck (3 tons capacity) (owned)
1 – unit	Mini Dumptruck (owned)
1 – unit	Road Roller (owned)
2 – units	Plate Compactor (owned)
1 – unit	Transit Mixer (5.0 cu.m. capacity) (owned)
2 – units	Concrete Vibrator (Owned)
1- Unit	Vibratory Screed (owned)
1- Unit	Bar/Shear Cutter (owned)
2- Units	One-bagger Concrete Mixer
1- Unit	Welding Machine Electric Driven (owned)
1- Unit	Electric Grinder (owned)
1- Unit	Electric Cutting Wheel (owned)

F. Approved Budget for the Contract (ABC):	Php7,822,476.00
G. Source of Fund :	PPA R/M Funds
H. Contract Duration :	180 Calendar Days
I. Required PCAB Registration :	Small “B” – Port, Harbor and Offshore Engineering

Interested bidders **must present Original Copy of Special Power of Attorney (SPA)** from the owner if done by a representative for the **entire procurement activities**. A complete set of Bidding Documents may be purchased by interested Bidders from the address below upon payment of a non-refundable fee of Ten Thousand Pesos (**P 10,000.00**) inclusive of VAT.

Prospective bidders should possess a valid PCAB License and registration particulars applicable to the type and cost of the contract to be bid, have key personnel and equipment exclusively available for the prosecution of the contract as listed in Item E above, and must have completed a similar contract and with the same major categories of work as the contract to be bid and receipt of bids with a value of at least 50% of the approved budget for the contract to be bid, updated to current prices using the NSO price indices, and must meet the other eligibility, technical/project, and financial requirements and other requirements stated in the Eligibility Statement Form and the Bidding Documents.

Bidding will be conducted through open competitive bidding procedures using non-discretionary “pass/fail” criteria as specified in the IRR of RA 9184, otherwise known as the “Government Procurement Reform Act”.

Bidding is restricted to Filipino citizens/sole proprietorships, partnerships or organizations with at least 75% interest or outstanding capital stock belonging to citizens of the Philippines.

The schedule of procurement activities is as follows:

Procurement Activities	Schedule		
	Time	Date	Venue
Advertisement and Issuance of Bidding Documents		Aug. 14, 2019 to Sept. 2, 2019	PPA, PMO-Surigao, Port Area, Surigao City
Pre-Bid Conference	10:00 AM	Aug. 20, 2019	PPA, PMO–Surigao Conf. Rm, Port Area, Surigao City

Republic of the Philippines
PHILIPPINE PORTS AUTHORITY
PORT MANAGEMENT OFFICE – SURIGAO
Port Area, Surigao City

Deadline of submission and receipt of Bids	9:00AM	Sept. 2, 2019	PPA,PMO–Surigao Conf. Rm, Port Area, Surigao City
Opening & Examination of Bids	9:30AM	Sept. 2, 2019	PPA,PMO–Surigao Conf. Rm, Port Area, Surigao City

Bidders must submit their bids on the date, time and place specified in the above schedule. Late bid/s will not be accepted. All bids must be accompanied by a bid security in any of the forms and corresponding amount stated in the Bidding Documents. Bids received in excess of the ABC shall be automatically rejected at bid opening.


The PPA, PMO-Surigao reserves the right to accept or reject any Bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without thereby incurring any liability to the affected bidder or bidders. Similarly, the PPA PMO-Surigao assumes no responsibility, whatsoever, to compensate or indemnify the bidders of any expenses incurred in the preparation of their bids.

Further information, please refer to:

BAC Secretariat

PHILIPPINE PORTS AUTHORITY, PMO-Surigao
Port Area, 8400 Surigao City, Philippines
Tel./Fax Nos.: (086)8262015 & 8265233 Local 115,114/(086)8262016
E-mail Add. : pmosurigao@ppa.com.ph ; crlisondra@ppa.com.ph;
Website Add: www.ppa.com.ph

Recommending Approval:


ENGR. LAWRENCE LYLE E. CAGAS
BAC Vice-Chairperson

Approved:


FROILAN U. CATURLA
Acting Port Manager

Period of Posting in the PhilGEPS, PPA Website and PMO Bulletin Board: Aug. 14, 2019 to Aug. 20, 2019.