

PROJECT FEATURE

Project Title	ZAM 07-2017 (NRP-ZBO-06-17) Proposed Repair of Damaged Interlocking Concrete Paving Blocks Open Storage Area and Drainage System, Port of Pagadian, Zamboanga del Sur
Duration	193 Calendar Days
Approved Budget for the Contract	Php28,537,549.00 inclusive of 12% VAT
Scope of work	I. Mobilization/Demobilization - 1.00 lot; II. Removal of Existing Interlocking Paving Block - 1,362.65 sq.m; III. Filling Materials (Sub-Base Course) - 2,576.73 cu.m; IV. Sub-Base Preparation - 5,601.59 sqm; V. Graded Crush Stone - 966.27 cu.m; VI. Cement Treated Base Course - 5,601.59 sq.m; VII. Sand Cushion - 280.08 cu.m; VIII. Supply, Install & place ICBP 100mm x 200mm x 125mm – 5,601.59 sq.m; IX. Repair of Drainage System - 63.67 lm (a. Excavation & Disposal - 91.68 cu.m, b. Reinforcing Steel Bars (Item 404c) - 4,710.09 kgs, c. Gravel Bedding - 8.33 cu.m, d. Concrete - Item 405 - 25.79 cu.m, e. Provision of Twisted Steel Grating Drainage Cover – 56.67 lm, f. Provision of Twisted Steel Grating Manhole Cover – 7.00 units); X. Repair & Build-up Concrete Curb & Roro Ramp – 76.30 cu.m (a. Chipping of Concrete to expose bars - 9.19 cu.m, b. Reinforcing Steel Bars (Item 404c) - 4,774.30 kgs, c. Concrete - Item 405 - 76.30 cu.m); XI. Construction Health and Safety Program - 193.00 c.d.
Minimum Equipment Requirements (1-unit each)	1. Dump Truck (10-Wheeler), 2. Payloader (1.50 cum cap), 3. Road Roller (10 mt), 4. Road Grader, 185 Hp, 5. Water Truck (1,000 gal), 6. Forklift 5-Tons Cap, 7. One Bagger Concrete Mixer, 8. Backhoe (0.80 cu.m).

