



REQUEST FOR QUOTATION
(Small Value Procurement)

Name of Project : **Supply, Delivery and Installation of 3 Toner Floor Standing Inverter Air-conditioning Unit for the Collapsible Tent**

Approved Budget for the Contract : **P 500,000.00**

Deadline for Submission : **December 18, 2019**

Please quote your best quotation in line with the attached specifications. Suppliers are required to submit their valid and current Mayor's/Business Permit, PhilGeps Registration Number, Omnibus Sworn Statement and Secretary Certificate/Special Power of Attorney.

Quotations shall be submitted in person to the Manager, Administrative Services Department, PPA Corporate Bldg., Bonifacio Drive, South Harbor, Port Area, Manila. Quotations/documents sent to any other department/s or email address will not be considered.

For further information, please refer to:

The BAC Secretariat, Philippine Ports Authority
5th Floor, PPA Bldg., Bonifacio Drive
South Harbor, Port Area, Manila
Telephone/Fax No. 527-4735
954-88-00 loc. 539
PPA Website: www.ppa.com.ph

Very Truly Yours,

MARK JON S. PALOMAR
Chairperson, Bids and Awards Committee
Procurement of Goods and Consultancy Services

**Supply, Delivery and Installation of 3 Toner Floor Standing Inverter
Air-conditioning Unit for the Collapsible Tent**

BAC-PGCS-269-2019

Qty	Unit	Description
1	lot	<p>3 Toner Floor Mounted Air-conditioning Unit Inverter Type For Collapsible Utility Tent, size: 10m x 15m, height is adjustable to 8.8 ft. maximum</p> <p>Quantity: 4 units</p> <p>Includes:</p> <ol style="list-style-type: none"> 1. Installation and Materials (brand new) for four (4) units. 2. NEMA 3R with Breaker for each unit. Total of four (4) sets. 3. Mobilization <p>Scope of Work:</p> <ol style="list-style-type: none"> 1. Supply and Installation of Refrigerant Piping and its accessories (expose piping only). 2. Supply and Installation of Signal Control Wire from FCU to ACCU. 3. Supply and Installation of Supply Wire from FCU to ACCU. 4. Supply and Installation of NEMA 3R with Breaker. 5. Supply and Installation of Condensate Drain and its accessories to provide tapping point. 6. Supply & Installation of Support, Brackets and Hangers (L-BAR outdoor). 7. Perform Leak Test, Balancing, Vacuum and Flushing. 8. Testing and Commissioning.
Warranty:		One (1) year on Parts and Services. Five (5) years on Compressor.
Delivery:		Shall be completed within fifteen (15) working days from receipt of Purchase Order.