


Date : 6/10/2019  
 Quotation No. : \_\_\_\_\_

Company Name : \_\_\_\_\_  
 Address : \_\_\_\_\_

Please quote your lowest price on the item/s listed below, subject to the General Conditions on these last page, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than \_\_\_\_\_ in the return envelope attached herewith.

  
 \_\_\_\_\_  
 CARMEN MAET GABE  
 Acting Procurement Officer

- NOTE:
1. ALL ENTRIES MUST BE TYPEWRITTEN
  2. DELIVERY PERIOD WITHIN \_\_\_\_\_ CALENDAR DAYS
  3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY.
  4. PRICE VALIDITY SHALL BE FOR A PERIOD OF \_\_\_\_\_ CALENDAR DAYS
  5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
  6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED.

| Item No. | ITEM & DESCRIPTION                        | UNIT | QTY | UNIT PRICE | AMOUNT |
|----------|---|------|-----|------------|--------|
|          |   |      |     |            |        |
|          | Repair of Van Office for the Port of Opol | LOT  | 1   |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |
|          |   |      |     |            |        |

Brand & Model : \_\_\_\_\_  
 Delivery Period : \_\_\_\_\_  
 Warranty : \_\_\_\_\_  
 Price Validity : \_\_\_\_\_

After having carefully read and accepted your General Conditions, I/We quote you on the Item at prices noted above.

\_\_\_\_\_  
 Printed Name/Signature

Tel No./Cellphone No. \_\_\_\_\_  
 e-mail address \_\_\_\_\_  
 Vat No, \_\_\_\_\_  
 Non-Vat No \_\_\_\_\_

Project: **Repair of Van Office for the Port of Opol**  
 Location: Port of Opol

| ITEM                                 | DESCRIPTION   | QUANTITY | UNIT  | UNIT COST                   | AMOUNT  |
|--------------------------------------|---|----------|-------|-----------------------------|---------|
| <b>1.0 Transfer of Container Van</b> |   | 1.00     | LOT   |                             |         |
| Work Description                     | Work includes the hauling/transfer of 20 footer container Van from Baseport Cagayan de Oro to Port of Opol  |          |       |                             |         |
| Materials                            |   |          |       |                             |         |
| Equipment                            |   |          |       |                             |         |
| 1 Boom truck (5 tons capacity)       |   | 1.00     | day   | _____                       | _____   |
| Manpower                             |   |          |       |                             |         |
| 1 Truck helper                       |   | 1.00     | day   | _____                       | _____   |
|                                      |   |          |       | ESTIMATED DIRECT COST       | P _____ |
|                                      |   |          |       | ESTIMATED INDIRECT COST     | P _____ |
|                                      |   |          |       | TOTAL COST OF WORK ITEM I.  | P _____ |
| <b>2.0 Repair of Container Van</b>   |   | 1.00     | UNIT  |                             |         |
| Work Description                     | clearing, installation of double walls including insulations and fabrication of partitions, overhead cabinets, counters, vinyl tiles and store room |          |       |                             |         |
| Materials                            |   |          |       |                             |         |
| 20 footers Container Van (existing)  |   | 1.00     | set   | _____                       | _____   |
| Double furring (Light Metal Furring) |   | 60.00    | lhs.  | _____                       | _____   |
| 12mm Fiber Cement Board              |   | 14.00    | shts. | _____                       | _____   |
| 6mm thk. Fiber Cement Board          |   | 28.00    | shts. | _____                       | _____   |
| Blind Rivets 1"                      |   | 1,500.00 | pcs.  | _____                       | _____   |
| P.E. foam Insulation (10mm)          |   | 68.00    | l.m.  | _____                       | _____   |
| Ga.#16 G.I. Tie Wire                 |   | 4.00     | kgs.  | _____                       | _____   |
| Vinyl Floor Tiles (0.30x0.30m)       |   | 164.00   | pcs.  | _____                       | _____   |
| Rubber Cement                        |   | 1.00     | gal.  | _____                       | _____   |
| 3/4" thk. Plyboard                   |   | 5.00     | shts. | _____                       | _____   |
| High strength Adhesive               |   | 10.00    | tubes | _____                       | _____   |
| Equipment                            |   |          |       |                             |         |
| Manpower                             |   |          |       |                             |         |
| 1 Foreman                            |   | 8.00     | days  | _____                       | _____   |
| 2 Plumber                            |   | 8.00     | days  | _____                       | _____   |
| 2 Laborer                            |   | 8.00     | days  | _____                       | _____   |
|                                      |   |          |       | ESTIMATED DIRECT COST       | P _____ |
|                                      |   |          |       | ESTIMATED INDIRECT COST     | P _____ |
|                                      |   |          |       | TOTAL COST OF WORK ITEM II. | P _____ |

3.0 Repainting of VanOffice and Installation of Doors and Windows

35.04 SQ.M.

Work Description

Removal of Existing Paints and Repainting of 1-unit Container Van incl. Installation of Doors, Windows and Glass wall w/ aluminum frames

Materials

|  |      |       |       |       |
|--|------|-------|-------|-------|
| Paint Remover  | 3.00 | gals. | _____ | _____ |
| Rust Coverter  | 3.00 | gals. | _____ | _____ |
| Red Oxide  | 3.00 | gals. | _____ | _____ |
| Paint Roller   | 4.00 | pcs.  | _____ | _____ |
| Paint Tray   | 2.00 | pcs.  | _____ | _____ |
| 2" Paint Brush   | 4.00 | pcs.  | _____ | _____ |
| Automotive Primer White  | 4.00 | gals. | _____ | _____ |
| Automotive Lacquer Putty   | 2.00 | gals. | _____ | _____ |
| Automotive Lacquer White   | 4.00 | gals. | _____ | _____ |
| D1 0.802x2.10m: 9mm thk. Glass Door with Aluminum frame (Analok) & Door Closer | 1.00 | set   | _____ | _____ |
| D2 0.60x2.10m PVC Door with PVC Door Jamb                                      | 1.00 | set   | _____ | _____ |
| D3 0.60x1.40m Steel Door W/ Steel Door Jamb(Emergency Exit)                    | 1.00 | set   | _____ | _____ |
| W1 1.00x1.20m 9mm thk. Glass w/ Alum. Frame (Analok-Casement Window)           | 4.00 | set   | _____ | _____ |
| W2 0.60x0.60m 9mm thk. Glass w/ Alum. Frame (Analok-Casement Window)           | 2.00 | set   | _____ | _____ |
| 9mm thk. Fixed Glass wall w/ Aluminum frame                                    | 1.00 | set   | _____ | _____ |
| 12mmØ Square bar grilles (1.0x1.2 & 0.60x0.60)                                 | 6.00 | set   | _____ | _____ |
| Equipment  |      |       |       |       |
| Manpower   |      |       |       |       |
| 1 Foreman  | 7.00 | days  | _____ | _____ |
| 1 Glass Installer  | 2.00 | days  | _____ | _____ |
| 2 Painter  | 7.00 | days  | _____ | _____ |
| 2 Helper   | 7.00 | days  | _____ | _____ |

ESTIMATED DIRECT COST P \_\_\_\_\_  
 ESTIMATED INDIRECT COST P \_\_\_\_\_  
 TOTAL COST OF WORK ITEM III. P \_\_\_\_\_

4.0 Electrical Works

Work Description

Work includes installation of electrical wirings, switches panel board and light fixtures including electrical outlets

Materials

|   |       |       |       |       |
|---|-------|-------|-------|-------|
| Panel board: 50Amps Main Protection, 1-30Amp, 2-15Amp | 1     | units | _____ | _____ |
| Jnction box   | 6     | pcs.  | _____ | _____ |
| Utility box (2'x4')                                   | 6     | pcs.  | _____ | _____ |
| Convenience Outlet (4-gang)                           | 3     | pcs.  | _____ | _____ |
| Lighting Fixtures (Florescent Lamp with casing)       | 4.00  | pcs.  | _____ | _____ |
| 5.5mm2 THN cu. Wire                                   | 14.00 | l.m.  | _____ | _____ |
| 3.5mm2 THN cu. Wire                                   | 54.00 | l.m.  | _____ | _____ |

|                              |       |      |                             |         |
|------------------------------|-------|------|-----------------------------|---------|
| Switch (single gangs switch) | 3.00  | pcs. | _____                       | _____   |
| 3/4"Ø PVC Electrical Pipe    | 31.00 | lhs. | _____                       | _____   |
| PVC Solvent Cement (200cc)   | 2.00  | qrt  | _____                       | _____   |
| Electrical Tape              | 6.00  | pcs. | _____                       | _____   |
| Equipment                    |       |      | _____                       | _____   |
| Manpower                     |       |      |                             |         |
| 1 Foreman                    | 1.00  | days | _____                       | _____   |
| 1 Electrician                | 1.00  | days | _____                       | _____   |
| 1 Helper                     | 1.00  | days | _____                       | _____   |
|                              |       |      |                             |         |
|                              |       |      | ESTIMATED DIRECT COST       | P _____ |
|                              |       |      | ESTIMATED INDIRECT COST     | P _____ |
|                              |       |      | TOTAL COST OF WORK ITEM IV. | P _____ |

5 Plumbing Works and Toilet

Work Description  
Work includes installation of Plumbing Works and Fixtures

Materials

|  |      |       |                            |         |
|--|------|-------|----------------------------|---------|
| Portland cement  | 6.00 | bags  | _____                      | _____   |
| Washed sand  | 0.30 | cu.m. | _____                      | _____   |
| Crushed Gravel (3/4")  | 0.60 | cu.m. | _____                      | _____   |
| 4"Ø PVC Pipe   | 2.00 | lhs.  | _____                      | _____   |
| 4"Ø PVC Elbow 90   | 5.00 | pcs.  | _____                      | _____   |
| 4"Ø PVC P-trap   | 2.00 | pcs.  | _____                      | _____   |
| 4"Ø PVC Tee  | 8.00 | pcs.  | _____                      | _____   |
| 4"Ø PVC Clean-out with plug                                      | 7.00 | lhs.  | _____                      | _____   |
| 1/2"Ø G.I. Pipe  | 4.00 | pcs.  | _____                      | _____   |
| 1/2"Ø G.I. Elbow   | 5.00 | pcs.  | _____                      | _____   |
| 1/2"Ø G.I. Tee   | 3.00 | pcs.  | _____                      | _____   |
| 1/2"Ø G.I. Plug  | 2.00 | pcs.  | _____                      | _____   |
| 1/2"Ø Gate Valve   | 3.00 | pcs.  | _____                      | _____   |
| Water closet w/ accessories (tank acc., flexible hose, GV, etc.) | 1.00 | set   | _____                      | _____   |
| Lavatory w/ accessories (flexible hose, GV, teflon tape, etc.)   | 1.00 | set   | _____                      | _____   |
| Faucet & Shower set  | 1.00 | set   | _____                      | _____   |
| Solvent Cement   | 3.00 | qrt.  | _____                      | _____   |
| Teflon Tape  | 4.00 | pcs.  | _____                      | _____   |
| Equipment  |      |       |                            |         |
| Manpower   |      |       |                            |         |
| 1 Foreman  | 4.00 | days  | _____                      | _____   |
| 1 Plumber  | 4.00 | days  | _____                      | _____   |
| 2 Helper   | 4.00 | days  | _____                      | _____   |
|  |      |       |                            |         |
|  |      |       | ESTIMATED DIRECT COST      | P _____ |
|  |      |       | ESTIMATED INDIRECT COST    | P _____ |
|  |      |       | TOTAL COST OF WORK ITEM V. | P _____ |