

Project: **Repair of Security Barricades**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.	Repair of Security Barricades	1.00	LOT		
	Work Description				
	Supply of labor, equipment and materials for the repair of 25-units security barricades				
	Materials				
	#8 50x50mm Steel matting (welded wire mesh) 4' x 8'	25.00	shts		
	2" dia. G.I. pipe Sch. 40	38.00	lhs		
	3mm x 25mm Flat Bar x 20'	60.00	lhs		
	16mm dia. Plain Round Bar	4.00	lhs		
	1/2" dia. G.I. Pipe Sch. 40	3.00	lhs		
	1/8" dia. Welding Rod	25.00	kgs.		
	Hack Saw Blade	30.00	pcs.		
	Epoxy Primer	4.00	gals		
	Automotive Enamel	7.00	gals		
	Lacquer Thinner	15.00	bot		
	Paint Brush #2	11.00	pcs.		
	Equipment				
	2 units - Welding machine	8.00	days		
	1 units - Portable Grinder	5.00	days		
	Manpower				
	1 - Foreman	8.00	days		
	2 - Welder	8.00	days		
	2 - Helper/Laborer	8.00	days		
	ESTIMATED DIRECT COST			P	
	ESTIMATED INDIRECT COST			P	
	TOTAL COST OF WORK ITEM 1.			P	
	TOTAL BID AMOUNT :			P	

BID AMOUNT IN WORDS :