

PORT MANAGEMENT OFFICE - WESTERN LEYTE / BILIRAN

LOT 2, BLOCK 13, DOÑA FELIZA MEJIA SUBD., D. VELOSO ST., ORMOC CITY, 6541
TEL. NO. (053) 561 4664, FAX NO. (053) 561 4663
Email Address: pmowlb_opm@yahoo.com.ph

SUPPLEMENTAL/BID BULLETIN NO. 1

SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF ONE(1) UNIT 150 KVA GENERATOR SET INCL. AUTOMATIC TRANSFER SWITCH AND THREE (3) 50 KVA TRANSFORMERS AT THE PORT OF ORMOC, & FIVE(5) UNITS 75 KVA GENERATOR SETS WITH AUTOMATIC TRANSFER SWITCH AND FIVE (5) 75 KVA TRANSFORMERS AT THE PORTS OF MAASIN, HILONGOS, BAYBAY, NAVAL & PALOMPON (PMO-WLB-GS-2017-001)

TO

All Prospective Bidders Members BAC, PMO-WLB

Others Concerned

Relative to the above project which was posted in the PhilGEPS, PPA website and in conspicuous places on 14 December 2017, please be informed of the following changes:

A. Terms of Reference:

Genset Minimum Specifications and Accessories

2.) Five (5) Units of 75kVA Generator Sets for TMOs of Maasin, Hilongos, Baybay, Naval & Palompon

From: Number of Cylinders: 6

Prime Rating Power (kW/kVA): 52kW/65kVA Standby Rating Power (kW/kVA): 75kW/75kVA Fuel consumption at 100% load (L/H) – Diesel 20L/H

To: Number of Cylinders: 4

Prime Rating Power (kW/kVA): 60kW/75kVA Standby Rating Power (kW/kVA): 66kW/83kVA

Fuel consumption at 100% load (L/H) - Diesel 18.6L/H

Technical Specifications of Automatic Transfer Switch

For 75 KVA Generator Set

From: Rated Voltage: 220 -240V, 3-Phase To: Rated Voltage: 220 -240V, Single Phase

Vision

By 2020, PPA shall have provided port services of global standards.

Mission

^{1 .} Provide reliable and responsive services in ports, sustain development of communities and the environment, and be a model corporate agency of the

government.

2. Establish a mutually beneficial, equitable, and fair relationship with partners and service providers.

Establish a mutually benchmark employment while creating a nurturing environment that promotes continuous learning and improvement.
 Establish a world-class port operation that is globally competitive adding value to the country's image and reputation

Bidder's Support Services

Bidder/ Supplier Requirements

From: Preferably with 5years industry experience in the supply of

generators set.

To: Preferably with 10years industry experience in the supply of

generators set.

B. Schedule of Requirements

From:

Item No.	Description	Unit of Measure	Quantity	Total	Delivered, Weeks Months
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	18	18	Proceed (NTP)
	Eye Terminal 200mm	Pc	2	2	
	PVC Pipe, 3" dia.	Length	2	2	
•	PVC Elbow, 3" dia.	Pc	3	3	
2	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Maasin, So. Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	65	65	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	11	11	
	PVC Elbow, 3" dia.	Pc	6	6	
3	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	50	50	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	10	10	
	PVC Elbow, 3" dia.	Pc	8	8	
4	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	50	50	Proceed (NTP)
-	PVC Pipe, 3" dia.	Length	10	10	,,,,,
-	PVC Elbow, 3" dia.	Pc	8	8	
5	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	Lot	1	1	Two (2) months after the effectivity of Notice to
_	Stranded Wire 200mm	Meter	50	50	Proceed (NTP)
-	PVC Pipe, 3" dia.	Length	9	9	7/
	PVC Elbow, 3" dia.	Pc	6	6	
	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
-	Stranded Wire 200mm	Meter	140	140	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	21	21	
	PVC Elbow, 3" dia.	Pc	8	8	

Item No.	Description	Unit of Measure	Quantity	Total	Delivered, Weeks/ Months
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	36	36	Proceed (NTP)
	Eye Terminal 200mm	Pc	3	3	-
	PVC Pipe, 3" dia.	Length	4	4	
	PVC Elbow, 3" dia.	Pc	6	6	
2	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Maasin, So. Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	85	85	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	15	15	
	PVC Elbow, 3" dia.	Pc	8	8	
3	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	Lot	1	1	Two (2) months after the effectivit of Notice to
	Stranded Wire 200mm	Meter	65	65	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	13	13	
	PVC Elbow, 3" dia.	Pc	11	11	
4	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	65	65	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	13	13	
	PVC Elbow, 3" dia.	Pc	11	11	
5	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	65	65	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	12	12	
	PVC Elbow, 3" dia.	Pc	8	8	
6	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	Lot	1	1	Two (2) months after the effectivity of Notice to
	Stranded Wire 200mm	Meter	182	182	Proceed (NTP)
	PVC Pipe, 3" dia.	Length	28	28	V. Santara V.
	PVC Elbow, 3" dia.	Pc	11	11	

C. Bill of Quantities (Annex E)

From:

Item No.	Description	Unit of Measure	Quantity	Unit Cost	Total
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	Lot	1	Cost	
	Stranded Wire 200mm	Meter	18		
	Eye Terminal 200mm	Pc	2		
	PVC Pipe, 3" dia.	Length	2		237
	PVC Elbow, 3" dia.	Pc	3		
2	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Maasin, So. Leyte	Lot	1		
	Stranded Wire 200mm	Meter	65		
	PVC Pipe, 3" dia.	Length	11		
	PVC Elbow, 3" dia.	Pc	6		
3	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	50		
	PVC Pipe, 3" dia.	Length	10		
	PVC Elbow, 3" dia.	Pc	8		
4	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	50		
-	PVC Pipe, 3" dia.	Length	10		
_	PVC Elbow, 3" dia.	Pc	8		
5	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	Lot	1		
	Stranded Wire 200mm	Meter	50		T. T. 110-110-110-110-110-110-110-110-110-110
-	PVC Pipe, 3" dia.	Length	9		
_	PVC Elbow, 3" dia.	Pc	6		
	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	140		
	PVC Pipe, 3" dia.	Length	21		
	PVC Elbow, 3" dia.	Pc	8		

Item No.	Description	Unit of Measure	Quantity	Unit Cost	Total
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	Lot	1	3331	
	Stranded Wire 200mm	Meter	36		
	Eye Terminal 200mm	Pc	3		
	PVC Pipe, 3" dia.	Length	4		
	PVC Elbow, 3" dia.	Pc	6		
2	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Maasin, So. Leyte	Lot	1		
	Stranded Wire 200mm	Meter	85		
	PVC Pipe, 3" dia.	Length	15		",
	PVC Elbow, 3" dia.	Pc	8		
3	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	65		
	PVC Pipe, 3" dia.	Length	13		
	PVC Elbow, 3" dia.	Pc	11		
4	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	65		
	PVC Pipe, 3" dia.	Length	13		
	PVC Elbow, 3" dia.	Pc	11		
5	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	Lot	1		
	Stranded Wire 200mm	Meter	65		
	PVC Pipe, 3" dia.	Length	12		
	PVC Elbow, 3" dia.	Pc	8		
	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	Lot	1		
	Stranded Wire 200mm	Meter	182		
	PVC Pipe, 3" dia.	Length	28		
	PVC Elbow, 3" dia.	Pc	11		

Issued this 3rd day of January 2018.

THE BIDS AND AWARDS COMMITTEE:

GERRY D. LIQUIDO Chairman BAC PPA, PMO - WLB



TERMS OF REFERENCE (Amended)

SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF ONE(1) UNIT 150 KVA GENERATOR SET INCL. AUTOMATIC TRANSFER SWITCH AND THREE (3) 50 KVA TRANSFORMERS AT THE PORT OF ORMOC, & FIVE(5) UNITS 75 KVA GENERATOR SETS WITH AUTOMATIC TRANSFER SWITCH AND FIVE (5) 75 KVA TRANSFORMERS AT THE PORTS OF MAASIN, HILONGOS, BAYBAY, NAVAL & PALOMPON

OBJECTIVE

To provide generator sets at the PMO's & TMO's Offices to ensure the continuous supply of power in the areas during brown-outs/power outage from local power service provider.

SCOPE OF WORK

The work to be executed and completed and the equipment to be deployed by the Supplier in areas identified by the PPA, PMO-Western Leyte/ Biliran shall include the following:

- Mobilization of manpower, materials, tools, equipment and technical supervisions.
- 2. Supply, installation, testing and commissioning of the brand new generator sets and all ancillary equipment required for installation and operation.
- 3. Supply and Installation of Cable wires from Generator sets to ATS and Main Distribution Panel.
- 4. Installation of appropriate safety measures at the project site.
- 5. Actual Load testing in every site before final acceptance.
- 6. Conduct at least one (1) day training for the end-user operator for operation system, commissioning and preventive maintenance procedure.



AREA OF DEPLOYMENT

Area	Power Rating	Quantity
	150KVA with ATS and soundproof enclosure	1
BASEPORT ORMOC	Transformer, 50 KVA, 3-Phase	3
TMO-MAASIN	75KVA with ATS and soundproof enclosure	1
	Transformer,75 KVA, 1-Phase	1
TMO-HILONGOS	75KVA with ATS and soundproof enclosure	1
	Transformer,75 KVA, 1-Phase	1
TMO-BAYBAY	75KVA with ATS and soundproof enclosure	1
	Transformer,75 KVA, 1-Phase	1
TMO-NAVAL	75KVA with ATS and soundproof enclosure	1
	Transformer,75 KVA, 1-Phase	1
TMO-PALOMPON	75KVA with ATS and soundproof enclosure	1
	Transformer,75 KVA, 1-Phase	1



GENSET MINIMUM SPECIFICATIONS AND ACCESSORIES

1. One (1) Unit of 150kVA Generator Sets for Baseport Ormoc

Generator Set Specification					
Number of cylinders	6				
Cylinder arrangement	In-Line				
Aspiration	Turbocharged after-water cooling				
Prime Rating Power (kW/kVA)	109kW/136kVA				
Standby Rating Power (kW/kVA)	120kW/150kVA				
Control Panel	Digital				
Speed governor	Electronic				
Cooling system	Water Cooling Cycle				
Phase	3				
Rpm	1800				
Volts	220V				
Frequency	60hZ				
Power Factor	0.8				
Fuel consumption (L/H) at 100% load	Diesel – 20 L/H				
Insulation	Class H				
Starter motor	24V				
Exciter type	Single bearing, Brushless Type				



Five (5) Units of 75kVA Generator Sets for TMOs of Maasin, Hilongos, Baybay, Naval & Palompon

Generator Set Specification					
Number of cylinders	4				
Cylinder arrangement	In-Line				
Aspiration	Turbocharged after-water cooling				
Prime Rating Power (kW/kVA)	60kW/75kVA				
Standby Rating Power (kW/kVA)	66kW/83kVA				
Control Panel	Digital				
Speed governor	Electronic				
Cooling system	Water Cooling Cycle				
Phase	Single				
Rpm	1500				
Volts	220Vac				
Frequency	50hZ				
Power Factor	0.8				
Fuel consumption at 100% load (L/H)	Diesel – 18.6 L/H				
Insulation	Class H				
Starter motor	24V				
Exciter type	Single bearing, Brushless Type				



TECHNICAL SPECIFICATIONS OF AUTOMATIC TRANSFER SWITCH

For 150 KVA Generator Set:

- 220-480 volts, 3 phase, wall-mounted/free standing with NEMA enclosure equal to the capacity of the generator set.
- Frequency: 60 Hz
- 2 x Molded Case Circuit Breaker with motor operated switching mechanism, Busbars, timers and relays and internal wiring as required. Front fascia mounted mains on load (green)/ Generator on load (red) indicator lights

For 75KVA Generator Set:

- > Rated Voltage: 220V- 240V, Single Phase
- Frequency: 60 Hz
- NEMA Enclosure all mounted with powder coating
- 2 x Molded Case Circuit Breaker with motor operated switching mechanism, Busbars, timers and relays and internal wiring as required. Front fascia mounted mains on load (green)/ Generator on load (red) indicator lights

Standard Accessories per Generator Set

- · Heavy duty steel fabricated base frame
- Unit mounted radiator
- · Fuel, oil and air filters
- 1 set of Tool Box
- 1 set of Replacement Gasket
- 12 vdc starting system and battery charging alternator
- 12 vdc lead acid battery
- 8 hours capacity base mounted fuel tank with supply and return lines, level gauge, drain plug exhaust muffler with flexible connection
- Unit mounted auto/manual start control panel with metering voltage, current, frequency, oil pressure, water temperature, engine rpm, dc voltage, engine operating hours counter
- Engine shutdown protection against low oil pressure, high water temperature, over speed, under speed, charging system failure, over crank (failure to start)
- · Duly rated circuit breaker factory wired
- Engine and alternator instruction manual

Soundproof/Weatherproof Enclosure

- With lifting Gussets
- Multiple swing doors
- Powdered coat finish
- 1.5 mm thick Cold Rolled Steel
- With panel viewing glass
- Fire retardant foam insulation

TECHNICAL SPECIFICATIONS OF TRANSFORMER

- 1. Transformer, 3-Phase, 50 KVA
- 2. Transformer, 1-Phase, 75 KVA



After Sales Service and Support during the warranty period, all reported defects shall be completely/satisfactorily repaired/replaced by the winning bidder/supplier within 72 hours after receipt of a verbal and/or written notice from the procuring entity.

OTHER TERMS AND CONDITIONS

- 1. Manufacturer Quality Standard: ISO 9001 and ISO 14001.
- 2. Ensure that the delivery/ies of the equipment should be checked and inspected by the PPA, PMO-WL/B authorized representative.
- 3. Provide Operational Manuals (schematic diagrams, maintenance checklists and schedules)
- The bidders must inspect the PMOs & TMOs /sites indicated & must be able to provide Inspection Certificate to be attached in the technical bid documents.

OTHER DOCUMENTARY REQUIREMENTS

- 1. Certificate of ISO 9001 & 14001
- Certificate of Origin
- 3. Suppliers EXCLUSIVE/AUTHORIZED DISTRIBUTORSHIP from the Manufacturer
- 4. Suppliers must have authorized SERVICE CENTERS in the following REGIONS (REGION 7 & 8) for Quick Response of Repair & Troubleshooting
- 5. Warranty Certificate for One (1) year

Payment Terms

The payment shall be done within twenty-one (21) working days upon submission of complete documents including, delivery, installation, testing, commissioning and acceptance of the unit by the authorized/designated representatives of PPA, PMO-WL/B subject to performance security retention, if any.

APPROVED:

FOR THE

Supply, Delivery, Installation and Commissioning of One(1) unit 150 KVA Generator Set incl. Automatic Transfer Switch and Three (3) 50 KVA Transformers at the Port of Ormoc, & Five(5) units 75 KVA Generator Sets with Automatic Transfer Switch and Five (5) 75 KVA Transformers at the Ports of Maasin, Hilongos, Baybay, Naval & Palompon

> The Bids and Awards Committee (BAC)

ARVINS. ELAGO Provisional Member

JUDY ANN M. S Member

JENAVENTURA

MONTESCLAROS

Provisional Member

LORD TYRONÉ L. AGATON

Vice-Chairperson

GERRY D. LIQUIDO Chairperson

CONFORME:

Name & Signature of Bidder's Authorized Representative



STATEMENT OF COMPLIANCE

Bidders must state either "Comply" or "Not Comply" against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered. Statements of "Comply" or "Not Comply" must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of manufacturer's un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidders statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution subject to the provisions of ITB Clause 3.1(a)(ii) and/or GCC Clause 2.1(a)(ii).

Item	Specification	Statement of Compliance Bidders must state here either "Comply" or "Not Comply"
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Set	
	Number of Cylinders: 6	
	Cylinder Arrangement: In-line	
	Aspiration : Turbocharged after water cooling	
	Prime Rating Power (kW/kVA): 180kW/ 135kVA	
	Standby Rating Power (kW/kVA): 120kW/150kVA	
5.00	Control Panel: Digital	
	Speed Governor: Electronic	
	Cooling System: Water Cooling Cycle	
	Phase: 3	
	Rpm: 1800	
	Volts: 220V	
	Frequency: 60hZ	
	Power Factor: 0.8	
	Fuel Consumption at 100% load (L/H): Diesel – 20L/H	
	Insulation: Class H	
	Starter Motor: 24V	
_	Exciter Type: Single Bearing, Brushless Type	
2;3;4; 5; & 6	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set	
	Number of Cylinders: 4	
	Cylinder Arrangement: In-line	
	Aspiration : Turbocharged after water Cooling	
	Prime Rating Power (kW/kVA): 60kW/ 75kVA	
	Standby Rating Power (kW/ kVA): 66kW/ 83kVA	
	Control Panel: Digital	
	Speed Governor: Electronic	
	Cooling System: Water Cooling Cycle	



Rpm: 1500 Volts: 220V Frequency: 50hZ Power Factor: 0.8 Fuel Consumption at 100% load (L/H): Diesel — 18.6L/H Insulation: Class H Starter Motor: 24V Exciter Type: Single Bearing, Brushless Type Las Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220–480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 3.a; 3.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 4.b; 5.b; 8.6.b Phase: 1 Capacity: 75 KVA		Phase: 1	
Frequency: 50hZ Power Factor: 0.8 Fuel Consumption at 100% load (L/H): Diesel — 18.6L/H Insulation: Class H Starter Motor: 24V Exciter Type: Single Bearing, Brushless Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60HZ NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set Volts: 220-240 Phase: 1 Frequency: 60HZ NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x NeMa enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1 x Molded Case Circuit Breaker wit		Rpm: 1500	
Power Factor: 0.8 Fuel Consumption at 100% load (L/H): Diesel – 18.6L/H Insulation: Class H Starter Motor: 24V Exciter Type: Single Bearing, Brushless Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA		Volts: 220V	
Power Factor: 0.8 Fuel Consumption at 100% load (L/H): Diesel – 18.6L/H Insulation: Class H Starter Motor: 24V Exciter Type: Single Bearing, Brushless Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA	_	Frequency: 50hZ	
Diesel - 18.6L/H			
Starter Motor: 24V Exciter Type: Single Bearing, Brushless Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 3.a; 4.a; 4.a; 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; 8.6.b Phase: 1			
Exciter Type: Single Bearing, Brushless Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set 8.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer Phase: 1 Fransformer Phase: 1		Insulation: Class H	
Type 1.a Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA		Starter Motor: 24V	
Automatic Transfer Switch for 150 KVA Generator Set Volts: 220-480 Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a.; Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set Sa; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA		100	
Phase: 3 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1	1.a	Automatic Transfer Switch for 150 KVA	
Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer Phase: 1 Phase: 1		Volts: 220-480	
NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		Phase: 3	
powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		Frequency: 60Hz	
2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; Supply, Delivery and Installation of Automatic Transfer Switch for 75 KVA Generator Set 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		NEMA enclosure: mounted with	
motor operated switching mechanism, busbars, timers and relays and internal wiring 2.a; 3.a; 4.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		powder coating	
busbars, timers and relays and internal wiring 2.a; 3.a; 4.a; 5.a; & Generator Set Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1			
wiring 2.a; 3.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1			
2.a; 3.a; 4.a; 4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		The Control of the control of the state of the state of the state of the control	
3.a; 4.a; 5.a; & Generator Set Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1	20		
4.a; 5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1			
5.a; & 6.a Volts: 220-240 Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		A SECTION OF THE PROPERTY OF T	
Volts: 220-240	- 20	Generator Sec	
Phase: 1 Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1	12-20 Miles (C. 1992-1)		
Frequency: 60Hz NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		Volts: 220-240	
NEMA enclosure: mounted with powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		Phase: 1	
powder coating 2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		Frequency: 60Hz	
2 x Molded Case Circuit Breaker with motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; 3.b; 4.b; 5.b; & 6.b Phase: 1		1.00 (40) May 1.00 (40) (40) (40) (40) (40) (40) (40) (4	
motor operated switching mechanism, busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1			
busbars, timers and relays and internal wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1			
wiring 1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1			
1.b Supply, Delivery and Installation of Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1			
Transformer Phase: 3 Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1	31.12	TO SECURE A SECURE ASSESSMENT ASS	
Capacity: 50 KVA 2.b; Supply, Delivery and Installation of Transformer 4.b; 5.b; & 6.b Phase: 1	1.0	Transformer	
2.b; Supply, Delivery and Installation of 3.b; Transformer 4.b; 5.b; & 6.b Phase: 1			
3.b; Transformer 4.b; 5.b; & 6.b Phase: 1		Capacity: 50 KVA	
3.b; Transformer 4.b; 5.b; & 6.b Phase: 1			
4.b; 5.b; & 6.b Phase: 1			
5.b; & 6.b Phase: 1	The state of the s	1 ransformer	
& 6.b Phase: 1			
	3.50		
Capacity:75 KVA		Phase: 1	
		Capacity:75 KVA	

I hereby certify to comply with all the above specifications.

Name of Company/Bidder	Signature Over Printed Name of	Date
	Representative	

Breakdown of Materials (Minimum Requirement)

Item No.	Description	Unit of Measure	Quantity	Total	Delivered, Weeks/ Month	
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	lot	1	1		
	Stranded Wire 400mm	meter	36	36	Two (2) months after the	
	Eye Terminal 400mm	рс	3	3	effectivity of Notice to	
	PVC Pipe, 3" dia.	length	4	4	Proceed (NTP)	
	PVC Elbow, 3" dia.	pc	6	6		
	The state of the s	ро				
1.a	Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set at the Port of Ormoc	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)	
1.b	Supply, Delivery and Installation of Transformer 50 KVA, 3 Phase at Baseport Ormoc	lot	3	3	Two (2) months after the effectivity of Notice to Proceed (NTP)	
	Supply, Delivery, Installation, Testing and Commissioning					
2	of 75 KVA Generator Set Single Phase at the Port of Maasin, So. Leyte	lot	1	1		
	Stranded Wire 200mm	meter	85	85		
	PVC Pipe, 3" dia.	length	15	15		
	PVC Elbow, 3" dia.	рс	8	8		
	Panel Board 10 Branches with breakers:	set	1	1	Two (2) months after	
	- 1 pc Circuit Breaker, 400 A		· ·			
	- 2 pcs Circuit Breaker, 100 A				effectivity of Notice to	
	- 6 pcs Circuit Breaker, 40 A				Proceed (NTP)	
	Eye Terminal 200mm	рс	2	2		
	Circuit Breaker 400 A with pole box	set	1	1		
	Electrical Tape	рс	2	2		
	Rubber Tape	рс	2	2		
	Circuit Breaker 100 A	рс	4	4		
2.a	Supply, Delivery of Installation Automatic Transfer Switch for 75 KVA Generator Set at the Port of Maasin, So. Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)	
2.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Maasin, So. Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)	
3	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	lot	1	1		
	Stranded Wire 200mm	meter	65	65		
	PVC Pipe, 3" dia.	length	13	13		
	PVC Elbow, 3" dia.	рс	11	11		
	Circuit Breaker, 250 A	рс	1	1	Two (2) months after the	
	Stranded Wire 60mm	meter	48	48	effectivity of Notice to	
	Eye Terminal 200mm	рс	10	10	Proceed (NTP)	
	Panel Board 10 Branches with breakers:	set	1	1		
	- 1 pc Circuit Breaker, 300 A					
	- 4 pcs Circuit Breaker, 100 A					
	- 3 pcs Circuit Breaker, 30 A					
	Circuit Breaker 300A with pole box	set	1	1		
3.a	Supply, Delivery & Installation of Automatic Transfer Switch for 75 KVA Generator Set at the Port of Hilongos, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)	
3.17	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Hilongos, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)	

Breakdown of Materials (Minimum Requirement)

tem No.	Description	Unit of Measure	Quantity	Total	Delivered, Weeks/ Month
	Supply, Delivery, Installation, Testing and Commissioning				
4	of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	lot	1	1	
	Stranded Wire 200mm	meter	65	65	
	PVC Pipe, 3" dia.	length	13	13	
	PVC Elbow, 3" dia.	рс	11	11	
	Circuit Breaker, 200 A	рс	1	1	Two (2) months after the
	Stranded Wire 60mm	meter	48	48	effectivity of Notice to
	Eye Terminal 200mm	рс	10	10	Proceed (NTP)
	Panel Board 10 Branches with breakers:	set	1	1	350 310
	- 1 pc Circuit Breaker, 300 A				
	- 3 pcs Circuit Breaker, 100 A				
	- 3 pcs Circuit Breaker, 30 A				
	Circuit Breaker 300A with pole box	set	1	1	
4.a	Supply, Delivery & Installation Automatic Transfer Switch for 75 KVA Generator Set at the Port of Baybay, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)
4.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Baybay, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)
5	Supply, Delivery, Installation, Testing and Commissioning	Text			
J	of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	lot	1	1	
	Stranded Wire 200mm	meter	65	65	
	PVC Pipe, 3" dia.	length	12	12	
	PVC Elbow, 3" dia.	рс	8	8	
	Circuit Breaker 400A with pole box	set	1	1	T. (2)
	Circuit Breaker 250A with moulded case	рс	1	1	Two (2) months after the effectivity of Notice to
	Eye Terminal 200mm	рс	2	2	Proceed (NTP)
	Circuit Breaker 100A (bolt on)	рс	1	1	Troceed (IVIF)
	Solderless connector	рс	2	2	
	Stranded Wire 150mm	meter	4	4	
	Ct11\AE4-4		12	12	
	Stranded Vvire 14mm	motor			
	Stranded Wire 14mm Electrical Tape	рс	3	3	
	Floatrical Tana	20.000.0000000	3	3	
	Electrical Tape Rubber Tape	рс			Two (2) months after the
5.a	Electrical Tape	рс			Two (2) months after the effectivity of Notice to Proceed (NTP)

Breakdown of Materials (Minimum Requirement)

SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF ONE(1) UNIT 150 KVA GENERATOR SET INCL. AUTOMATIC TRANSFER SWITCH AND THREE (3) 50 KVA TRANSFORMERS AT THE PORT OF ORMOC, & FIVE(5) UNITS 75 KVA GENERATOR SETS WITH AUTOMATIC TRANSFER SWITCH AND FIVE (5) 75 KVA TRANSFORMERS AT THE PORTS OF MAASIN, HILONGOS, BAYBAY, NAVAL & PALOMPON

tem No.	Description	Unit of Measure	Quantity	Total	Delivered, Weeks/ Months
6	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	lot	1	1	
	Stranded Wire 200mm	meter	182	182	
	PVC Pipe, 3" dia.	length	28	28	
	PVC Elbow, 3" dia.	рс	11	11	
	Eye Terminal 200mm	рс	2	2	T (2)
	Circuit Breaker 300A with pole box	set	1	1	Two (2) months after the
	Panel Board 10 Branched	рс	1	1	effectivity of Notice to Proceed (NTP)
	Circuit Breaker 300A	рс	1	1	Troceed (NTF)
	Circuit Breaker 100A	рс	2	2	
	Circuit Breaker 400A	рс	2	2	
	Circuit Breaker 30A	рс	2	2	
	Circuit Breaker 20A	рс	2	2	
	Circuit Breaker 15A	рс	2	2	
6.a	Supply, Delivery & Installation of Automatic Transfer Switch for 75 KVA Generator Set at the Port of Palompon, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)
6.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Palompon, Leyte	lot	1	1	Two (2) months after the effectivity of Notice to Proceed (NTP)

Name of Company	Printed and Signature of Authorized Representative

I hereby certify to comply and deliver all of the above minimum requirements

BILL OF QUANTITIES (AMENDED)

m Na	December	Unit of			
em No.	Description	Measure	Quantity	Unit Cost	Total
1	Supply, Delivery, Installation, Testing and Commissioning of 150 KVA Generator Three (3) Phase at Baseport Ormoc	lot	1		
	Stranded Wire 400mm	meter	36		
	Eye Terminal 400mm	рс	3		
	PVC Pipe, 3" dia.	length	4		
	PVC Elbow, 3" dia.	рс	6		
1.a	Supply, Delivery of Installation Automatic Transfer Switch for 150 KVA Generator Set at the Port of Ormoc	lot	1		
	130 KVA Generator Set at the Fort of Ormoc				
4.1	Supply, Delivery and Installation of Transformer 50 KVA,		240		
1.b	3 Phase at Baseport Ormoc	lot	3		
	Supply, Delivery, Installation, Testing and Commissioning				
2	of 75 KVA Generator Set Single Phase at the Port of	lot	1		
	Maasin, So. Leyte				
	Stranded Wire 200mm	meter	85		
	PVC Pipe, 3" dia.	length	15		
	PVC Elbow, 3" dia.	1077	1,70,000		
	Panel Board 10 Branches with breakers:	pc	8		
	- 1 pc Circuit Breaker, 400 A	set			
	- 2 pcs Circuit Breaker, 100 A				
	- 6 pcs Circuit Breaker, 40 A				
	Eye Terminal 200mm	рс	2		
	Circuit Breaker 400 A with pole box	set	1		
	Electrical Tape	рс	2		
	Rubber Tape	рс	2		
	Circuit Breaker 100 A	рс	4		
2.a	Supply, Delivery of Installation Automatic Transfer Switch for 75 KVA Generator Set at the Port of Maasin, So. Leyte	lot	1		
2.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Maasin, So. Leyte	lot	1		
	Supply, Delivery, Installation, Testing and Commissioning				
3	of 75 KVA Generator Set Single Phase at the Port of Hilongos, Leyte	lot	1		
	Stranded Wire 200mm	meter	65		
	PVC Pipe, 3" dia.	length	13		
	PVC Elbow, 3" dia.	pc	11		
	Circuit Breaker, 250 A	рс	1		
	Stranded Wire 60mm	meter	48		
	Eye Terminal 200mm		10		
	Panel Board 10 Branches with breakers:	pc	1		
	- 1 pc Circuit Breaker, 300 A	set	1		
	- 4 pcs Circuit Breaker, 100 A				
	- 3 pcs Circuit Breaker, 30 A Circuit Breaker 300A with pole box	set	1		
	en dat broater oom with pole box	SEL			
	Supply, Delivery & Installation of Automatic Transfer	V			
3.a	Switch for 75 KVA Generator Set at the Port of Hilongos, Leyte	lot	1		
	Supply, Delivery and Installation of Transformer 75KVA,	1		1	

BILL OF QUANTITIES (AMENDED)

	BAYBAY, NAVAL 8	& PALOMPO	ON		
tem No.	Description	Unit of Measure	Quantity	Unit Cost	Total
4	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Single Phase Set at the Port of Baybay, Leyte	lot	1		
	Stranded Wire 200mm	meter	65		
	PVC Pipe, 3" dia.	length	13		
	PVC Elbow, 3" dia.	рс	11		
	Circuit Breaker, 200 A	рс	1		
	Stranded Wire 60mm	meter	48		
	Eye Terminal 200mm	рс	10		
	Panel Board 10 Branches with breakers:	set	1		
	- 1 pc Circuit Breaker, 300 A				
	- 3 pcs Circuit Breaker, 100 A				
	- 3 pcs Circuit Breaker, 30 A				
	Circuit Breaker 300A with pole box	set	1		
4.a	Supply, Delivery & Installation Automatic Transfer Switch for 75 KVA Generator Set at the Port of Baybay, Leyte	lot	1		
4.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Baybay, Leyte	lot	1		
5	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Pahse at the Port of Naval, Biliran	lot	1		
	Stranded Wire 200mm	meter	65		
	PVC Pipe, 3" dia.	length	12		
	PVC Elbow, 3" dia.	рс	8		
	Circuit Breaker 400A with pole box	set	1		
	Circuit Breaker 250A with moulded case	рс	1		
	Eye Terminal 200mm	рс	2		
	Circuit Breaker 100A (bolt on)	рс	1		
	Solderless connector	рс	2		
	Stranded Wire 150mm	meter	4		
	Stranded Wire 14mm	meter	12		
	Electrical Tape	рс	3		
	Rubber Tape	рс	3		
	Supply, Delivery of Installation Automatic Transfer Switch for 75 KVA Generator Set at the Port of Naval, Biliran	lot	1		
	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Naval, Biliran	lot	1		

BILL OF QUANTITIES (AMENDED)

em No.	Description	Unit of Measure	Quantity	Unit Cost	Total
6	Supply, Delivery, Installation, Testing and Commissioning of 75 KVA Generator Set Single Phase at the Port of Palompon, Leyte	lot	1		
	Stranded Wire 200mm	meter	182		
	PVC Pipe, 3" dia.	length	28		
	PVC Elbow, 3" dia.	рс	11		
	Eye Terminal 200mm	рс	2		
	Circuit Breaker 300A with pole box	set	1		
	Panel Board 10 Branched	рс	1		
	Circuit Breaker 300A	рс	1		
	Circuit Breaker 100A	рс	2		
	Circuit Breaker 400A	рс	2		
	Circuit Breaker 30A	рс	2		
	Circuit Breaker 20A	рс	2		
	Circuit Breaker 15A	рс	2		
6.a	Supply, Delivery & Installation of Automatic Transfer Switch for 75 KVA Generator Set at the Port of Palompon, Leyte	lot	1		
6.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Palompon, Leyte	lot	1		

nereb	y certify to comply and deliver all of the above minim	um requ	irements	
6.b	Supply, Delivery and Installation of Transformer 75KVA, Single Phase at the Port of Palompon, Leyte	lot	1	
	Supply Delivery and Installation of Ton Company			
	Leyte			