

BILL OF QUANTITIES

Project Name : PROVISION OF ELECTRICAL UNDERGROUND DUCT AND POWER SUPPLY
(SINGLE PHASE) FOR PORT OPERATIONS BUILDING (POB)

Location : PORT OF BABAK, DAVAO DEL NORTE

Item No	Description	Unit	Quantity	Unit Cost	Amount
1	Demolition of existing Pavement for underground electrical duct (0.6mx64m) at Pesos:	sq.m	38.4		
	_____ per lot				
2	Excavation and Disposal unsuitable materials (for electrical ducting 0.6mx0.6mx101.66) at Pesos:	cu.m	36.6		
	_____ per lot				
3	Supply, Spread, and Compact Aggregate Base Coarse at Pesos:	cu.m	7		
	_____ per lot				
4	Fabrication of Reinforcing Steel Bars for Concrete electrical duct at Pesos:	Kg.	1960		
	_____ per lot				
5	Concreting works for electrical duct and restoration of affected concrete pavement at Pesos:	cu.m	27.9		
	_____ per lot				

